Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of Work:Improvements To Roads and Drains And Other Developmental Works At Akskshaya,Thirumalanagar,Muneshwara Layout,Sri Sai Layout, B Sector And Surrounding Areas in Ward No-03 And 04 Of Yelahanka Division Under Amruth Nagarothan Grants[PACKAGE NO-03]

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
1	Removing and Resetting of Footpath Slab and pointing in C.M (1:3) (Approved Rate)								
	Approved Rate	235.00							
	Area Weightage 10%	23.50							
	Total	258.50							
		Sqm							
	Attur Layout								
	1st Main Road	2	74.00	0.75		111.00			
	1st Main Road Continue	2	68.00	0.75		102.00			
	2nd Main Rd	2	72.00	0.90		129.60			
	2nd Main Rd Continue	2	53.00	0.90		95.40			
	2nd Main Rd Continue	2	73.00	0.90		131.40			
	2nd Main Rd Continue	2	73.00	0.75		109.50			
	2nd Main Rd Continue	2	69.00	0.90		124.20			
	3rd Main Rd	2	75.00	0.90		135.00			
	3rd Main Rd Continue	2	74.00	0.90		133.20			
	3rd Main Rd Continue	2	55.00	0.90		99.00			
	3rd Main Rd Continue	2	73.50	0.90		132.30			
	4th Main Rd	2	72.00	0.75		108.00			
	4th Main Rd Continue	2	55.00	0.90		99.00			
	4th Main Rd Continue	2	75.00	0.90		135.00			
	4th Main Rd Continue	2	76.00	0.75		114.00			
	5th Main Rd	2	47.00	0.90		84.60			
	5th Main Rd Continue	2	73.00	0.75		109.50			
	5th Main Rd Continue	2	72.00	0.90		129.60			
	5th Main Rd Continue	2	57.00	0.90		102.60			
	5th Main Rd Continue	2	72.00	0.90		129.60			
	6th Main Rd	2	67.00	0.90		120.60			
	6th Main Rd Continue	2	57.00	0.90		102.60			
	6th Main Rd Continue	2	73.00	0.90		131.40			
	6th Main Rd Continue	2	75.00	0.90		135.00			
	6th Main Rd Continue	2	47.00	0.90		84.60			
	7th Main Rd	2	46.00	0.90		82.80			
	7th Main Rd Continue	2	75.00	0.75		112.50			
	7th Main Rd Continue	2	73.00	0.75		109.50			
	7th Main Rd Continue	2	67.00	0.90		120.60			
	7th Main Rd Continue	2	68.00	0.90		122.40			
	8th Main Rd	2	65.00	0.90		117.00			
	8th Main Rd Continue	2	56.00	0.75		84.00			
	8th Main Rd Continue	2	74.00	0.90		133.20			
	8th Main Rd Continue	2	73.00	0.90		131.40			
	8th Main Rd Continue	2	45.00	0.75		67.50			
	10th Main Rd	2	219.00	0.75		328.50			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd Cross Rd	2	270.00	0.90		486.00			
	3rd Cross Rd	2	287.00	0.90		516.60			
	4th Cross Rd	2	265.00	0.90		477.00			
	Escorts Colony								
	2nd A Main Rd	2	210.00	0.90		378.00			
	6th A Main Rd	2	156.00	0.90		280.80			
	6th B Cross Rd	2	126.00	0.75		189.00			
	Escorts Colony LHS	1	261.00	0.90		234.90			
	Escorts Colony RHS	1	261.00	0.90		234.90			
	6th C Cross Rd	2	139.00	0.90		250.20			
	7th A Main Rd	2	239.00	0.90		430.20			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	2	343.00	0.90		617.40			
	1st Cross rd	2	64.00	0.75		96.00			
	2nd Cross rd	2	64.00	0.75		96.00			
	3rd Cross rd	2	65.00	0.75		97.50			
	4th Cross rd	2	65.00	0.75		97.50			
	5th Cross rd	2	65.00	0.75		97.50			
	6th Cross rd	2	65.00	0.75		97.50			
	7th Cross rd	2	65.00	0.75		97.50			
	3rd Cross Rd	1	323.00	0.90		290.70			
	Tirumalnagara								
	3rd Cross Rd	2	314.00	0.90		565.20			
	Santhosh nagara								
	Health Care Home Rd	2	44.00	0.75		66.00			
	7th Cross rd	1	125.00	0.75		93.75			
	Connecting Rd-2	1	26.00	0.75		19.50			
	6th Cross Rd	2	115.50	0.75		173.25			
	Connecting Rd-1	2	23.00	0.75		34.50			
	1st Cross Rd	1	140.00	0.90		126.00			
	2nd Cross Rd	2	155.00	0.75		232.50			
	4th Cross rd	2	149.00	0.90		268.20			
	Veerasagara								
	6th A Cross Rd	2	65.00	0.75		97.50			
	6th Cross Rd	2	57.00	0.75		85.50			
	6th B Cross Rd	2	93.00	0.75		139.50			
	6th Cross Rd	1	134.00	0.90		120.60			
	9th Main rd	2	99.00	0.90		178.20			
	11th Main Rd	2	54.50	0.90		98.10			
	12th Main Rd	1	64.00	0.75		48.00			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.90		40.50			
	2nd Cross Rd	1	45.50	0.90		40.95			
	6th Cross Rd [4th Cross Rd]	1	46.00	0.90		41.40			
	4th Cross Rd	1	45.00	0.90		40.50			
	4th Cross Rd RHS	1	45.00	0.90		40.50			
	9th Cross Rd Left Side	2	99.00	0.90		178.20			
	9th Cross Rd Right Side	2	170.00	0.90		306.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	10th Cross Rd Left Side	2	44.00	0.90		79.20			
	10th Cross Rd Right Side	2	170.00	0.75		255.00			
	11th Cross Rd	2	48.00	0.75		72.00			
	1st Cross Rd	2	102.00	0.90		183.60			
	5th Cross Rd	2	270.00	0.75		405.00			
	4th Cross Rd	1	172.00	0.90		154.80			
	3rd Cross Rd	2	190.00	0.75		285.00			
						13832.25			
	Consider 60%					8299.35			
	Deduct 25% Missing/Damaged Slab					2074.84			
						6224.51			
	Attur Village								
	Angavadi Left Side Rd	1	121.00	0.90		108.90			
	Attur Main Rd	1	80.00	0.60		48.00			
	2nd Cross Rd	2	118.00	0.90		212.40			
						369.30			
	Consider 60%					221.58			
	Deduct 40% Missing/Damaged Slab					88.63			
						132.95			
						6357.46	Sqm	258.50	1643403.54
2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) (V-I.No 1.4,Page No-5 PWD SR 2021-22)								
	Basic Rate	186.00							
	Loading And Unloading	118.00							
	Sub Total	304.00							
	Area Weightage 10%	30.40							
	Total Rate	334.40							
	Rcc Drain								
	Ward No-04								
	B-Sector								
	7th B Main Rd LHS	1	233.00	1.40	1.10	358.82			
	7th B Main Rd RHS	1	233.00	1.10	1.10	281.93			
	6th B Main Rd	2	355.00	1.40	1.10	1093.40			
	4th B cross Rd	2	155.00	1.10	1.05	358.05			
	6th B Main Rd	2	40.00	1.10	1.00	88.00			
	Ward No-03								
	Akshay Nagara								
	3rd Cross Rd	1	323.00	1.00	1.00	323.00			
	Tirumalnagara								
	Cross Rd	2	37.00	1.10	1.10	89.54			
	1st Cross Rd LHS	1	280.00	1.00	1.15	322.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	B/w Rd(From 1st Crs To 2nd	1	129.00	1.40	1.40	252.84			
	Sri Sai Layout								
	2nd A Main Rd	2	141.00	1.00	1.00	282.00			
	Rd-2	2	152.50	1.10	1.10	369.05			
	Rd-2 Continue	2	120.00	1.10	1.00	264.00			
	Cross Rd 1 & 2	2	16.00	1.10	1.00	35.20			
	Santhosh nagara								
	9th Cross cross rd-4	2	36.00	1.10	1.00	79.20			
	7th Cross rd RHS	1	174.00	1.10	1.00	191.40			
	1st Cross Rd LHS	1	161.00	1.00	1.00	161.00			
	2nd Cross Rd RHS	1	161.00	1.10	1.00	177.10			
	Veerasagara								
	4th Cross Rd LHS	1	80.00	1.00	1.10	88.00			
	4th Cross Rd RHS	1	135.00	1.00	1.10	148.50			
	4th A Cross Rd	2	22.50	1.00	1.10	49.50			
	4th B Cross Rd	2	22.50	1.00	1.10	49.50			
	11th Cross Rd	1	125.00	1.00	1.10	137.50			
	5th Cross Rd	2	94.00	1.00	1.10	206.80			
	6th Cross Rd	1	134.00	1.00	1.10	147.40			
	Attur Village								
	Attur Village Rd	2	115.00	1.10	1.10	278.30			
	Cross Rd-1	1	48.00	1.00	1.10	52.80			
	Cross Rd-2	2	103.00	1.00	1.10	226.60			
	Venkata Ramanappa Layout								
	1st Cross Rd	1	121.00	1.40	1.10	186.34			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	1.10	1.10	54.45			
	2nd Cross Rd	1	45.00	1.10	1.10	54.45			
	3rd Cross Rd	1	45.00	1.10	1.10	54.45			
	4th Cross Rd	1	45.00	1.10	1.10	54.45			
	5th Cross Rd	1	45.00	1.10	1.10	54.45			
	Connecting Drain	1	82.00	1.10	1.10	99.22			
	1st Main rd	2	122.00	1.10	1.10	295.24			
	6th Cross 1st Cross Rd	2	28.00	1.00	1.10	61.60			
	6th Cross 2nd Cross Rd	2	25.00	1.00	1.10	55.00			
	6th Cross 3rd Cross Rd	2	23.00	1.00	1.10	50.60			
	6th Cross 4th Cross Rd	2	23.00	1.00	1.10	50.60			
	4th Cross Rd	1	85.00	1.10	1.10	102.85			
	3rd Cross Rd	2	77.00	1.00	1.10	169.40			
	For Culverts	8	7.00	1.80	1.00	100.80			
		45	6.25	1.50	1.00	421.88			
	Santhosh nagara								
	6th Cross Dead End Culvert	1	4.40	3.30	2.20	31.94			
	Desilt								
	Attur Layout								
	1st Main Road	2	74.00	0.45	0.45	29.97			
	1st Main Road Continue	2	68.00	0.45	0.45	27.54			
	2nd Main Rd	2	72.00	0.60	0.60	51.84			
	2nd Main Rd Continue	2	53.00	0.60	0.45	28.62			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd Main Rd Continue	2	73.00	0.60	0.45	39.42			
	2nd Main Rd Continue	2	73.00	0.45	0.45	29.57			
	2nd Main Rd Continue	2	69.00	0.60	0.50	41.40			
	3rd Main Rd	2	75.00	0.60	0.55	49.50			
	3rd Main Rd Continue	2	74.00	0.60	0.45	39.96			
	3rd Main Rd Continue	2	55.00	0.60	0.45	29.70			
	3rd Main Rd Continue	2	73.50	0.60	0.55	48.51			
	4th Main Rd	2	72.00	0.45	0.50	32.40			
	4th Main Rd Continue	2	55.00	0.60	0.60	39.60			
	4th Main Rd Continue	2	75.00	0.60	0.60	54.00			
	4th Main Rd Continue	2	76.00	0.45	0.60	41.04			
	5th Main Rd Continue	2	72.00	0.60	0.45	38.88			
	5th Main Rd Continue	2	73.00	0.45	0.60	39.42			
	5th Main Rd Continue	2	72.00	0.60	0.55	47.52			
	5th Main Rd Continue	2	57.00	0.60	0.50	34.20			
	6th Main Rd	2	67.00	0.60	0.45	36.18			
	6th Main Rd Continue	2	57.00	0.60	0.45	30.78			
	6th Main Rd Continue	2	73.00	0.60	0.50	43.80			
	6th Main Rd Continue	2	75.00	0.60	0.45	40.50			
	6th Main Rd Continue	2	47.00	0.60	0.45	25.38			
	7th Main Rd	2	46.00	0.60	0.50	27.60			
	7th Main Rd Continue	2	75.00	0.45	0.50	33.75			
	7th Main Rd Continue	2	73.00	0.45	0.45	29.57			
	7th Main Rd Continue	2	67.00	0.60	0.45	36.18			
	7th Main Rd Continue	2	68.00	0.60	0.45	36.72			
	8th Main Rd	2	65.00	0.60	0.45	35.10			
	8th Main Rd Continue	2	56.00	0.45	0.45	22.68			
	8th Main Rd Continue	2	74.00	0.60	0.45	39.96			
	8th Main Rd Continue	2	73.00	0.60	0.55	48.18			
	8th Main Rd Continue	2	45.00	0.45	0.45	18.23			
	11th Main Rd	1	212.00	0.45	0.60	57.24			
	1st Cross Rd	2	261.00	0.60	0.60	187.92			
	2nd Cross Rd	2	270.00	0.60	0.60	194.40			
	3rd Cross Rd	2	287.00	0.60	0.60	206.64			
	4th Cross Rd	2	265.00	0.60	0.60	190.80			
	Escorts Colony								
	2nd A Main Rd	2	210.00	0.60	0.55	138.60			
	6th A Main Rd	2	156.00	0.60	0.45	84.24			
	6th B Cross Rd	2	126.00	0.45	0.60	68.04			
	6thC Cross Rd	2	50.00	0.60	0.60	36.00			
	Escorts Colony LHS	1	89.00	0.60	0.60	32.04			
	Escorts Colony RHS	1	89.00	0.60	0.60	32.04			
	7th A Main Rd	2	239.00	0.60	0.55	157.74			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	2	343.00	0.60	0.60	246.96			
	1st Cross rd	2	64.00	0.45	0.55	31.68			
	2nd Cross rd	2	64.00	0.45	0.60	34.56			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd Cross rd	2	65.00	0.45	0.60	35.10			
	4th Cross rd	2	65.00	0.45	0.50	29.25			
	5th Cross rd	2	65.00	0.45	0.60	35.10			
	6th Cross rd	2	65.00	0.45	0.55	32.18			
	7th Cross rd	2	65.00	0.45	0.60	35.10			
	3rd Cross Rd	1	323.00	0.60	0.60	116.28			
	Tirumalnagara								
	3rd Cross Rd	2	314.00	0.60	0.55	207.24			
	Santhosh nagara								
	Health Care Home Rd	2	44.00	0.45	0.50	19.80			
	Amrutha Gara Care Road	2	37.00	0.45	0.60	19.98			
	Connecting Rd-2	1	24.00	0.45	0.45	4.86			
	Connecting Rd-1	2	25.00	0.45	0.45	10.13			
	Sri Lasya Road [19]	2	19.00	0.60	0.45	10.26			
	Door No13	2	10.00	0.60	0.45	5.40			
	Varaha Entreprises Rd	2	18.00	0.60	0.45	9.72			
	2nd Cross Rd	1	125.00	0.45	0.60	33.75			
	4th Cross rd	2	137.00	0.45	0.45	55.49			
	6th Cross Rd	2	219.00	0.45	0.60	118.26			
	7th Cross rd	1	121.00	0.60	0.55	39.93			
	Veerasagara								
	6th A Cross Rd	2	65.00	0.45	0.60	35.10			
	6th Cross Rd	2	57.00	0.45	0.60	30.78			
	6th B Cross Rd	2	93.00	0.45	0.60	50.22			
	6th Cross Rd	1	134.00	0.60	0.50	40.20			
	9th Main rd	2	99.00	0.60	0.60	71.28			
	10th Main rd	1	43.00	0.60	0.50	12.90			
	11th Main Rd	2	54.50	0.60	0.60	39.24			
	12th Main Rd	1	64.00	0.45	0.40	11.52			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.60	0.50	13.50			
	2nd Cross Rd	1	45.50	0.60	0.50	13.65			
	3rd Cross Rd	1	46.00	0.60	0.50	13.80			
	4th Cross Rd	1	45.00	0.60	0.55	14.85			
	5th Cross Rd	1	45.00	0.60	0.57	15.39			
	9th Cross Rd Left Side	2	99.00	0.60	0.50	59.40			
	9th Cross Rd Right Side	2	170.00	0.60	0.50	102.00			
	10th Cross Rd Left Side	2	44.00	0.60	0.50	26.40			
	10th Cross Rd Right Side	2	170.00	0.45	0.60	91.80			
	11th Cross Rd	2	48.00	0.45	0.55	23.76			
	1st Cross Rd	2	102.00	0.60	0.60	73.44			
	5th Cross Rd	2	270.00	0.45	0.45	109.35			
	4thA Cross Rd	1	85.00	0.60	0.60	30.60			
	4th Cross Rd	1	184.00	0.60	0.50	55.20			
	3rd Cross Rd	2	190.00	0.45	0.50	85.50			
	Attur Village								
	Attur Main Rd	1	80.00	0.60	0.50	24.00			
	2nd Cross Rd	2	118.00	0.60	0.60	84.96			
						12902.39	Cum	334.40	4314558.88

providing and laying 52 mm thick cement concrete flooring with concrete
hardener topping, under layer 40 mm thick cement concrete
2 coarse sand : 4 graded

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix **1:3:6 (M10) Using 40 mm** nominal size graded crushed coarse aggregates (V-1, P.No-15, I No-2.1.3 of PWD SR 2021-22)								
	Basic Rate	**5752.00**							
	Area Weightage 10%	**575.20**							
	Total Rate	**6327.20**							
	Rcc Drain								
	Ward No-04								
	B-Sector								
	7th B Main Rd LHS	1	233.00	1.40	0.15	48.93			
	7th B Main Rd RHS	1	233.00	1.10	0.15	38.45			
	6th B Main Rd	2	355.00	1.40	0.15	149.10			
	4th B cross Rd	2	155.00	1.10	0.15	51.15			
	6th B Main Rd	2	40.00	1.10	0.15	13.20			
	Ward No-03								
	Akshay Nagara								
	3rd Cross Rd	1	323.00	1.00	0.15	48.45			
	Tirumalnagara								
	Cross Rd	2	37.00	1.10	0.15	12.21			
	1st Cross Rd LHS	1	280.00	1.00	0.15	42.00			
	B/w Rd(From 1st Crs To 2nd	1	129.00	1.40	0.15	27.09			
	Sri Sai Layout								
	2nd A Main Rd	2	141.00	1.00	0.15	42.30			
	Rd-2	2	152.50	1.10	0.15	50.33			
	Rd-2 Continue	2	120.00	1.10	0.15	39.60			
	Cross Rd 1 & 2	2	16.00	1.10	0.15	5.28			
	Santhosh nagara								
	9th Cross cross rd-4	2	36.00	1.10	0.15	11.88			
	7th Cross rd RHS	1	174.00	1.10	0.15	28.71			
	1st Cross Rd LHS	1	161.00	1.00	0.15	24.15			
	2nd Cross Rd RHS	1	161.00	1.10	0.15	26.57			
	Veerasagara								
	4th Cross Rd LHS	1	80.00	1.00	0.15	12.00			
	4th Cross Rd RHS	1	135.00	1.00	0.15	20.25			
	4th A Cross Rd	2	22.50	1.00	0.15	6.75			
	4th B Cross Rd	2	22.50	1.00	0.15	6.75			
	11th Cross Rd	1	125.00	1.00	0.15	18.75			
	5th Cross Rd	2	94.00	1.00	0.15	28.20			
	6th Cross Rd	1	134.00	1.00	0.15	20.10			
	Attur Village								
	Attur Village Rd	2	115.00	1.10	0.15	37.95			
	Cross Rd-1	1	48.00	1.00	0.15	7.20			
	Cross Rd-2	2	103.00	1.00	0.15	30.90			
	Venkata Ramanappa Layout								
	1st Cross Rd	1	121.00	1.40	0.15	25.41			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Muneshwara Layout								
	1st Cross Rd	1	45.00	1.10	0.15	7.43			
	2nd Cross Rd	1	45.00	1.10	0.15	7.43			
	3rd Cross Rd	1	45.00	1.10	0.15	7.43			
	4th Cross Rd	1	45.00	1.10	0.15	7.43			
	5th Cross Rd	1	45.00	1.10	0.15	7.43			
	Connecting Drain	1	82.00	1.10	0.15	13.53			
	1st Main rd	2	122.00	1.10	0.15	40.26			
	6th Cross 1st Cross Rd	2	28.00	1.00	0.15	8.40			
	6th Cross 2nd Cross Rd	2	24.00	1.00	0.15	7.20			
	6th Cross 3rd Cross Rd	2	23.00	1.00	0.15	6.90			
	6th Cross 4th Cross Rd	2	22.00	1.00	0.15	6.60			
	4th Cross Rd	1	85.00	1.00	0.15	12.75			
	3rd Cross Rd	2	77.00	1.00	0.15	23.10			
	For Culverts	8	7.00	1.80	0.15	15.12			
		45	6.25	1.50	0.15	63.28			
	Santhosh nagara								
	6th Cross Dead End Culvert	1	4.40	3.30	0.15	2.18			
	For Cobble Stone								
	Apartment Side								
	S-LIG, 39,40,41,42								
	39 Back Side	1	5.50	3.50	0.15	2.89			
	40 Back Side	1	6.00	6.00	0.15	5.40			
	41 Behing Neha Prakash Hospital	1	22.00	10.50	0.15	34.65			
	42 Front Side	1	33.00	5.80	0.15	28.71			
	42 Back Side	1	30.00	15.00	0.15	67.50			
	42 Right Side	1	8.00	5.20	0.15	6.24			
		1	6.00	1.80	0.15	1.62			
	15th Block								
	Part-A	1	31.00	5.00	0.15	23.25			
	Part-B	1	9.00	3.50	0.15	4.73			
	Part-C	1	31.00	7.50	0.15	34.88			
	Part-D	1	9.00	3.50	0.15	4.73			
	Part-E	1	6.30	5.30	0.15	5.01			
	Part-F	1	9.40	5.30	0.15	7.47			
	S-HIG32								
	Part-A	1	9.30	5.00	0.15	6.98			
	Part-B	1	6.10	5.40	0.15	4.94			
	S-HIG B-09								
		1	29.00	6.00	0.15	26.10			
		1	37.40	5.50	0.15	30.86			
	Opp To Annapurnashweri Catering								
	Part-A	1	33.00	4.60	0.15	22.77			
	Part-B	1	10.50	5.30	0.15	8.35			
	Part-C	1	22.00	5.00	0.15	16.50			
	Part-D	1	10.50	16.20	0.15	25.52			
	Part-E	1	60.00	6.50	0.15	58.50			
	Part-F	4	8.50	2.50	0.15	12.75			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Part-G	3	8.50	3.00	0.15	11.48			
	S-LIG 42								
	Beside Neha Prakasha Hospital								
	Part-A	1	27.00	5.00	0.15	20.25			
	Part-B	1	30.00	22.00	0.15	99.00			
	Part-C	1	27.00	4.50	0.15	18.23			
	Part-D	2	8.50	2.50	0.15	6.38			
	Part-E	2	8.50	3.00	0.15	7.65			
	Part-F	1	20.50	5.80	0.15	17.84			
	Part-G	1	15.00	8.00	0.15	18.00			
	Part-H	1	5.00	5.00	0.15	3.75			
	Part-I	1	8.30	3.00	0.15	3.74			
	Part-J	1	37.00	5.00	0.15	27.75			
	Part-K	1	20.00	7.60	0.15	22.80			
	Part-L	1	37.00	4.80	0.15	26.64			
	Part-M	2	8.50	2.50	0.15	6.38			
	Part-N	2	8.50	3.00	0.15	7.65			
	Deduct Sump	-4	4.00	3.00	0.15	-7.20			
	Ward No-04								
	For Pathway								
	7thB Cross Rd	1	29.00	6.00	0.15	26.10			
	Burial Ground								
	Burial Ground Compound								
	North Side								
	Footing Every 3.50mtr	26	1.50	1.50	0.15	8.78			
	For SSM Foundation	1	53.00	0.90	0.15	7.16			
	For SSM For Gate	1	3.50	0.75	0.15	0.39			
	Vaidhika Sabha building								
	Footing	16	2.00	2.00	0.15	9.60			
	SSM Foundation								
		5	19.10	0.75	0.15	10.74			
		4	13.75	0.75	0.15	6.19			
		4	1.55	0.75	0.15	0.70			
	Sump	1	3.20	3.20	0.15	1.54			
						1911.91	Cum	6327.20	12097006.90
4	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.(V-III, I.No 13.1 Page No 99, PWD SR 2021-22) issue rate dated 07-04-22								
	Basic Rate	103329.00							
	Area Weightage 10%	10332.90							
	Total Rate	113661.90							
	For RCC Drain, 60kg/Sqm	1	2045.59	60.00		122735.52			
	For RCC Drain Coping 45kg/Sqm	1	10.89	45.00		490.05			
	For RCC Culvert, 90kg/Sqm	1	171.45	90.00		15430.56			
						138.66	Tn	113661.90	15759919.52

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
5	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (V-1,P.No.17, I.No.2.4.2 of PWD SR 2021-22)								
	Basic Rate	6256.00							
	5% for Centring	312.80							
	Sub Total	6568.80							
	Area Weightage 10%	656.88							
	Total Rate	7225.68							
	Rcc Drain Raft								
	Ward No-04								
	B-Sector								
	7th B Main Rd LHS	1	233.00	1.20	0.15	41.94			
	7th B Main Rd RHS	1	233.00	0.90	0.15	31.46			
	6th B Main Rd	2	355.00	1.20	0.15	127.80			
	4th B cross Rd	2	155.00	0.90	0.15	41.85			
	6th B Main Rd	2	40.00	0.90	0.15	10.80			
	Ward No-03								
	Akshay Nagara								
	3rd Cross Rd	1	323.00	0.80	0.15	38.76			
	Tirumalnagara								
	Cross Rd	2	37.00	0.90	0.15	9.99			
	1st Cross Rd LHS	1	280.00	0.80	0.15	33.60			
	B/w Rd(From 1st Crs To 2nd	1	129.00	1.20	0.15	23.22			
	Sri Sai Layout								
	2nd A Main Rd	2	141.00	0.80	0.15	33.84			
	Rd-2	2	152.50	0.90	0.15	41.18			
	Rd-2 Continue	2	120.00	0.90	0.15	32.40			
	Cross Rd 1 & 2	2	16.00	0.90	0.15	4.32			
	Santhosh nagara								
	9th Cross cross rd-4	2	36.00	0.90	0.15	9.72			
	7th Cross rd RHS	1	174.00	0.90	0.15	23.49			
	1st Cross Rd LHS	1	161.00	0.80	0.15	19.32			
	2nd Cross Rd RHS	1	161.00	0.90	0.15	21.74			
	Veerasagara								
	4th Cross Rd LHS	1	80.00	0.80	0.15	9.60			
	4th Cross Rd RHS	1	135.00	0.80	0.15	16.20			
	4th A Cross Rd	2	22.50	0.80	0.15	5.40			
	4th B Cross Rd	2	22.50	0.80	0.15	5.40			
	11th Cross Rd	1	125.00	0.80	0.15	15.00			
	5th Cross Rd	2	94.00	0.80	0.15	22.56			
	6th Cross Rd	1	134.00	0.80	0.15	16.08			
	Attur Village								
	Attur Village Rd	2	115.00	0.90	0.15	31.05			
	Cross Rd-1	1	48.00	0.80	0.15	5.76			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Rd-2	2	103.00	0.80	0.15	24.72			
	Venkata Ramanappa Layout								
	1st Cross Rd	1	121.00	1.20	0.15	21.78			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.90	0.15	6.08			
	2nd Cross Rd	1	45.00	0.90	0.15	6.08			
	3rd Cross Rd	1	45.00	0.90	0.15	6.08			
	4th Cross Rd	1	45.00	0.90	0.15	6.08			
	5th Cross Rd	1	45.00	0.90	0.15	6.08			
	Connecting Drain	1	82.00	0.90	0.15	11.07			
	1st Main rd	2	122.00	0.90	0.15	32.94			
	6th Cross Rd	2	38.00	0.90	0.15	10.26			
	6th Cross 1st Cross Rd	2	28.00	0.80	0.15	6.72			
	6th Cross 2nd Cross Rd	2	25.00	0.80	0.15	6.00			
	6th Cross 3rd Cross Rd	2	23.00	0.80	0.15	5.52			
	6th Cross 4th Cross Rd	2	23.00	0.80	0.15	5.52			
	4th Cross Rd	1	85.00	0.90	0.15	11.48			
	3rd Cross Rd	2	77.00	0.80	0.15	18.48			
	Rcc Drain Wall								
	Ward No-04								
	B-Sector								
	7th B Main Rd LHS	2	233.00	0.15	0.75	52.43			
	7th B Main Rd RHS	2	233.00	0.15	0.65	45.44			
	6th B Main Rd	4	355.00	0.15	0.70	149.10			
	4th B cross Rd	4	155.00	0.15	0.60	55.80			
	6th B Main Rd	4	40.00	0.15	0.60	14.40			
	Ward No-03								
	Akshay Nagara								
	3rd Cross Rd	2	323.00	0.15	0.65	62.99			
	Tirumalnagara								
	Cross Rd	4	37.00	0.15	0.65	14.43			
	1st Cross Rd LHS	2	280.00	0.15	0.60	50.40			
	B/w Rd(From 1st Crs To 2nd	2	129.00	0.15	0.90	34.83			
	Sri Sai Layout								
	2nd A Main Rd	4	141.00	0.15	0.60	50.76			
	Rd-2	4	152.50	0.15	0.60	54.90			
	Rd-2 Continue	4	120.00	0.15	0.60	43.20			
	Cross Rd 1 & 2	4	16.00	0.15	0.60	5.76			
	Santhosh nagara								
	9th Cross cross rd-4	4	36.00	0.15	0.60	12.96			
	7th Cross rd RHS	2	174.00	0.15	0.60	31.32			
	1st Cross Rd LHS	2	161.00	0.15	0.60	28.98			
	2nd Cross Rd RHS	2	161.00	0.15	0.60	28.98			
	Veerasagara								
	4th Cross Rd LHS	2	80.00	0.15	0.60	14.40			
	4th Cross Rd RHS	2	135.00	0.15	0.65	26.33			
	4th A Cross Rd	4	22.50	0.15	0.60	8.10			
	4th B Cross Rd	4	22.50	0.15	0.60	8.10			
	11th Cross Rd	2	125.00	0.15	0.60	22.50			
	5th Cross Rd	4	94.00	0.15	0.60	33.84			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Cross Rd	2	134.00	0.15	0.60	24.12			
	Attur Village								
	Attur Village Rd	4	115.00	0.15	0.65	44.85			
	Cross Rd-1	2	48.00	0.15	0.60	8.64			
	Cross Rd-2	4	103.00	0.15	0.60	37.08			
	Venkata Ramanappa Layout								
	1st Cross Rd	2	121.00	0.15	0.85	30.86			
	Muneshwara Layout								
	1st Cross Rd	2	45.00	0.15	0.60	8.10			
	2nd Cross Rd	2	45.00	0.15	0.60	8.10			
	3rd Cross Rd	2	45.00	0.15	0.60	8.10			
	4th Cross Rd	2	45.00	0.15	0.60	8.10			
	5th Cross Rd	2	45.00	0.15	0.60	8.10			
	Connecting Drain	2	82.00	0.15	0.75	18.45			
	1st Main rd	4	122.00	0.15	0.60	43.92			
	6th Cross Rd	4	38.00	0.15	0.60	13.68			
	6th Cross 1st Cross Rd	4	28.00	0.15	0.55	9.24			
	6th Cross 2nd Cross Rd	4	25.00	0.15	0.55	8.25			
	6th Cross 3rd Cross Rd	4	23.00	0.15	0.55	7.59			
	6th Cross 4th Cross Rd	4	23.00	0.15	0.59	8.14			
	4th Cross Rd	2	85.00	0.15	0.60	15.30			
	3rd Cross Rd	4	77.00	0.15	0.60	27.72			
						2045.59			
	Drain Coping								
	Angavadi Left Side Rd	2	121.00	0.15	0.30	10.89			
	Culvert Raft								
		8	7.00	1.50	0.20	16.80			
		45	6.25	1.20	0.20	67.50			
	Santhosh nagara								
	6th Cross Dead End Culvert	1	4.40	3.00	0.20	2.64			
	Culvert Wall								
		16	7.00	0.23	0.50	12.88			
		90	6.25	0.23	0.50	64.69			
	Santhosh nagara								
	6th Cross Dead End Culvert	2	4.40	0.23	1.80	3.64			
	Top Slab	1	4.40	3.00	0.25	3.30			
						171.45			
						2227.93	Cum	7225.68	16098328.75
6	Providing and fixing **precast reinforced cement concrete covering slabs of 10Cm thick** made of M20 with OPC cement,with 20mm and down size graded granite metal coarse aggregate @0.70 mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work								
	Data Rate	2072.00							
	Ward No-04								
	B-Sector								
	7th B Main Rd LHS	1	233.00	1.20		279.60			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	7th B Main Rd RHS	1	233.00	0.90		209.70			
	6th B Main Rd	2	355.00	1.20		852.00			
	4th B cross Rd	2	155.00	0.90		279.00			
	6th B Main Rd	2	40.00	0.90		72.00			
						1692.30			
	Deduct 30% Existing Slab					507.69			
						1184.61			
	Ward No-03								
	Akshay Nagara								
	3rd Cross Rd	1	323.00	0.90		290.70			
	Tirumalnagara								
	Cross Rd	2	37.00	0.90		66.60			
	1st Cross Rd LHS	1	280.00	0.90		252.00			
	B/w Rd(From 1st Crs To 2nd	1	129.00	1.20		154.80			
	Sri Sai Layout								
	2nd A Main Rd	2	141.00	0.90		253.80			
	Rd-2	2	152.50	0.90		274.50			
	Rd-2 Continue	2	120.00	0.90		216.00			
	Cross Rd 1 & 2	2	16.00	0.90		28.80			
	Santhosh nagara								
	9th Cross cross rd-4	2	36.00	0.90		64.80			
	7th Cross rd RHS	1	174.00	0.90		156.60			
	1st Cross Rd LHS	1	161.00	0.90		144.90			
	2nd Cross Rd RHS	1	161.00	0.90		144.90			
	Veerasagara								
	4th Cross Rd LHS	1	80.00	0.75		60.00			
	4th Cross Rd RHS	1	135.00	0.75		101.25			
	4th A Cross Rd	2	22.00	0.75		33.00			
	4th B Cross Rd	2	22.00	0.75		33.00			
	11th Cross Rd	1	125.00	0.75		93.75			
	5th Cross Rd	2	94.00	0.75		141.00			
	6th Cross Rd	1	134.00	0.75		100.50			
	Attur Village								
	Attur Village Rd	2	115.00	0.90		207.00			
	Cross Rd-1	1	48.00	0.90		43.20			
	Cross Rd-2	2	103.00	0.90		185.40			
	Venkata Ramanappa Layout								
	1st Cross Rd	1	121.00	1.20		145.20			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.90		40.50			
	2nd Cross Rd	1	45.00	0.90		40.50			
	3rd Cross Rd	1	45.00	0.90		40.50			
	4th Cross Rd	1	45.00	0.90		40.50			
	5th Cross Rd	1	45.00	0.90		40.50			
	Connecting Drain	1	82.00	0.90		73.80			
	1st Main rd	2	122.00	0.90		219.60			
	6th Cross Rd	2	38.00	0.90		68.40			
	6th Cross 1st Cross Rd	2	28.00	0.75		42.00			
	6th Cross 2nd Cross Rd	2	25.00	0.75		37.50			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Cross 3rd Cross Rd	2	23.00	0.75		34.50			
	6th Cross 4th Cross Rd	2	23.00	0.75		34.50			
	4th Cross Rd	1	85.00	0.75		63.75			
	3rd Cross Rd	2	77.00	0.75		115.50			
	Add Missing/Damaged Slab					2163.47			
						7431.83	**Sqm**	**2072.00**	**15398750.72**
7	Providing and fixing **RCC precast cover slab of 230mm thick** for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)								
	Data Rate	**5037.00**							
	For Culverts								
		8	7.00	1.50		84.00			
		45	6.25	1.20		337.50			
	Deduct Available Slab	-10	0.60	1.20		-7.20			
						414.30	**Sqm**	**5037.00**	**2086829.10**
8	Providing and laying in position **plain cement concrete** for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. **Mix 1:3:6 (M10) Using 20 mm** nominal size graded crushed coarse aggregates (V-I, No-2.1.4, P.No-15 of PWD SR 2021-22).								
	Basic rate	**5926.00**							
	Area Weightage 10%	**592.60**							
	Total	**6518.60**							
	For Below Kerb Stone								
	Ward No-04								
	B-Sector								
	7th B Main Rd LHS	1	233.00	0.20	0.10	4.66			
	7th B Main Rd RHS	1	233.00	0.20	0.10	4.66			
	6th B Main Rd	2	355.00	0.20	0.10	14.20			
	4th B cross Rd	2	155.00	0.20	0.10	6.20			
	6th B Main Rd	2	40.00	0.20	0.10	1.60			
	Ward No-03								
	Attur Layout								
	1st Cross Rd	2	261.00	0.20	0.10	10.44			
	2nd Cross Rd	2	270.00	0.20	0.10	10.80			
	3rd Cross Rd	2	287.00	0.20	0.10	11.48			
	4th Cross Rd	2	265.00	0.20	0.10	10.60			
	Apartment Side								
	Apartment Surrounding	1	555.00	0.20	0.10	11.10			
	Akshay Nagara								
	Main Road	2	300.00	0.20	0.10	12.00			
	8th Main Rd	1	323.00	0.20	0.10	6.46			
	Sri Sai Layout								
	Rd-1	2	141.00	0.20	0.10	5.64			
	Rd-2	2	152.50	0.20	0.10	6.10			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Rd-2 Continue	2	120.00	0.20	0.10	4.80			
	Rd-3	2	16.00	0.20	0.10	0.64			
	Tirumalnagara								
	1st Cross Rd LHS	1	280.00	0.20	0.10	5.60			
	Cross Rd	2	37.00	0.20	0.10	1.48			
	Santhosh nagara								
	7th Cross rd	1	174.00	0.20	0.10	3.48			
	6th Cross Rd LHS	1	161.00	0.20	0.10	3.22			
	6th Cross Rd RHS	1	161.00	0.20	0.10	3.22			
	Veerasagara								
	4th Cross Rd	2	148.00	0.20	0.10	5.92			
	6th A Cross Rd	2	65.00	0.20	0.10	2.60			
	6th Cross Rd	2	57.00	0.20	0.10	2.28			
	6th B Cross Rd	2	93.00	0.20	0.10	3.72			
	5th Cross Rd	1	130.00	0.20	0.10	2.60			
	5th A Cross Rd	2	94.00	0.20	0.10	3.76			
	6th Cross Rd	2	134.00	0.20	0.10	5.36			
	9th Main rd	2	99.00	0.20	0.10	3.96			
	10th Main rd	2	43.00	0.20	0.10	1.72			
	11th Main Rd	2	54.50	0.20	0.10	2.18			
	12th Main Rd	2	64.00	0.20	0.10	2.56			
	Muneshwara Layout								
	9th Cross Rd Left Side	2	99.00	0.20	0.10	3.96			
	9th Cross Rd Right Side	2	170.00	0.20	0.10	6.80			
	10th Cross Rd Left Side	2	44.00	0.20	0.10	1.76			
	10th Cross Rd Right Side	2	170.00	0.20	0.10	6.80			
	11th Cross Rd Left Side	2	48.00	0.20	0.10	1.92			
	1st Main Rd	2	122.00	0.20	0.10	4.88			
	1st Cross Rd	2	102.00	0.20	0.10	4.08			
	5th Cross Rd	2	270.00	0.20	0.10	10.80			
	4th Cross Rd	2	85.00	0.20	0.10	3.40			
		2	92.00	0.20	0.10	3.68			
	3rd Cross Rd	2	190.00	0.20	0.10	7.60			
						230.72	**Cum**	**6518.60**	**1503971.39**
9	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work (Approved Rate)								
	Approved rate	**507.00**							
	Ward No-04								
	B-Sector								
	7th B Main Rd LHS	1	233.00			233.00			
	7th B Main Rd RHS	1	233.00			233.00			
	6th B Main Rd	2	355.00			710.00			
	4th B cross Rd	2	155.00			310.00			
	6th B Main Rd	2	40.00			80.00			
	Ward No-03								
	Attur Layout								
	1st Cross Rd	2	261.00			522.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd Cross Rd	2	270.00			540.00			
	3rd Cross Rd	2	287.00			574.00			
	4th Cross Rd	2	265.00			530.00			
						3732.00	M		
	Deduct 30% Existing Kerb					1119.60			
						2612.40	M		
	Akshay Nagara								
	Main Road	2	300.00			600.00			
	3rd Cross Rd	1	323.00			323.00			
	Sri Sai Layout								
	Rd-2	2	152.50			305.00			
						1228.00	M		
	20 % Existing Kerb					245.60			
						982.40	M		
	Veerasagara								
	4th Cross Rd	2	148.00			296.00			
	6th A Cross Rd	2	65.00			130.00			
	6th Cross Rd	2	57.00			114.00			
	6th B Cross Rd	2	93.00			186.00			
	5th Cross Rd	1	130.00			130.00			
	5th A Cross Rd	2	94.00			188.00			
	6th Cross Rd	2	134.00			268.00			
	9th Main rd	2	99.00			198.00			
	10th Main rd	2	43.00			86.00			
	11th Main Rd	2	54.50			109.00			
	12th Main Rd	2	64.00			128.00			
	Muneshwara Layout								
	9th Cross Rd Left Side	2	99.00			198.00			
	9th Cross Rd Right Side	2	170.00			340.00			
	10th Cross Rd Left Side	2	44.00			88.00			
	10th Cross Rd Right Side	2	170.00			340.00			
	11th Cross Rd Left Side	2	48.00			96.00			
	1st Main Rd	2	122.00			244.00			
	1st Cross Rd	2	102.00			204.00			
	5th Cross Rd	2	270.00			540.00			
	4th Cross Rd	2	85.00			170.00			
		2	92.00			184.00			
	3rd Cross Rd	2	190.00			380.00			
						4617.00	M		
	50 percent Existing Kerb					2308.50			
						2308.50	M		
	Apartment Side								
	Apartment Surrounding	1	555.00			555.00			
	Tirumalnagara								
	1st Cross Rd LHS	1	280.00			280.00			
	Cross Rd	2	37.00			74.00			
	Sri Sai Layout								
	Rd-1	2	141.00			282.00			
	Rd-2 Continue	2	120.00			240.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Rd-3	2	16.00			32.00			
	Santhosh nagara								
	7th Cross rd	1	174.00			174.00			
	6th Cross Rd LHS	1	161.00			161.00			
	6th Cross Rd RHS	1	161.00			161.00			
						1959.00	M		
						7862.30	M		
						17472.00	Nos	507.00	8858304.00
10	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces (V-III, P.No.56, I.No.8.10 of PW, PWD SR 2021-22)								
	Basic Rate	85.00							
	Area Weightage 10%	8.50							
	Total Rate	93.50							
	Ward No-04								
	B-Sector								
	7th B Main Rd LHS	1	233.00		0.35	81.55			
	7th B Main Rd RHS	1	233.00		0.35	81.55			
	6th B Main Rd	2	355.00		0.35	248.50			
	4th B cross Rd	2	155.00		0.35	108.50			
	6th B Main Rd	2	40.00		0.35	28.00			
	Ward No-03								
	Attur Layout								
	1st Cross Rd	2	261.00		0.35	182.70			
	2nd Cross Rd	2	270.00		0.35	189.00			
	3rd Cross Rd	2	287.00		0.35	200.90			
	4th Cross Rd	2	265.00		0.35	185.50			
	Akshay Nagara								
	Main Road	2	300.00		0.35	210.00			
	3rd Cross Rd	1	323.00		0.35	113.05			
	Sri Sai Layout								
	Rd-1	2	141.00		0.35	98.70			
	Rd-2	2	152.50		0.35	106.75			
	Rd-2 Continue	2	120.00		0.35	84.00			
	Rd-3	2	16.00		0.35	11.20			
	Veerasagara								
	4th Cross Rd	2	148.00		0.35	103.60			
	6th A Cross Rd	2	65.00		0.35	45.50			
	6th Cross Rd	2	57.00		0.35	39.90			
	6th B Cross Rd	2	93.00		0.35	65.10			
	5th Cross Rd	1	130.00		0.35	45.50			
	5th A Cross Rd	2	94.00		0.35	65.80			
	6th Cross Rd	2	134.00		0.35	93.80			
	9th Main rd	2	99.00		0.35	69.30			
	10th Main rd	2	43.00		0.35	30.10			
	11th Main Rd	2	54.50		0.35	38.15			
	12th Main Rd	2	64.00		0.35	44.80			
	Muneshwara Layout								
	9th Cross Rd Left Side	2	99.00		0.35	69.30			
	9th Cross Rd Right Side	2	170.00		0.35	119.00			
	10th Cross Rd Left Side	2	44.00		0.35	30.80			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	10th Cross Rd Right Side	2	170.00		0.35	119.00			
	11th Cross Rd Left Side	2	48.00		0.35	33.60			
	1st Main Rd	2	122.00		0.35	85.40			
	1st Cross Rd	2	102.00		0.35	71.40			
	5th Cross Rd	2	270.00		0.35	189.00			
	4th Cross Rd	2	85.00		0.35	59.50			
		2	92.00		0.35	64.40			
	3rd Cross Rd	2	190.00		0.35	133.00			
	Apartment Side								
	Apartment Surrounding	1	555.00		0.35	194.25			
	Tirumalnagara								
	1st Cross Rd LHS	1	280.00		0.35	98.00			
	Cross Rd	2	37.00		0.35	25.90			
	Santhosh nagara								
	7th Cross rd	1	174.00		0.35	60.90			
	6th Cross Rd LHS	1	161.00		0.35	56.35			
	6th Cross Rd RHS	1	161.00		0.35	56.35			
						4037.60	Sqm	93.50	377515.60
11	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work ((V-I, P.No-8, I No-1.12 of PWD SR 2021-22)								
	Basic Rate	65.00							
	Area Weightage 10%	6.50							
	Total Rate	71.50							
	Asphalt Road								
	Edge Correctin/ Damage Portion								
	Ward No-04								
	B-Sector								
	4th B cross Rd	1	20.00	6.00	0.25	30.00			
	7th B Cross Rd	1	139.00	1.50	0.25	52.13			
	6th B Main Rd	1	40.00	1.40	0.25	14.00			
	7th B main Rd	1	40.00	1.90	0.25	19.00			
	9th Cross Rd	1	50.00	1.70	0.25	21.25			
	Attur Layout								
	Attur Village Main Rd	1	72.00	0.90	0.25	16.20			
	2nd Main Rd Continue	1	53.00	1.00	0.25	13.25			
	2nd Main Rd Continue	1	73.00	0.90	0.25	16.43			
	2nd Main Rd Continue	1	73.00	1.00	0.25	18.25			
	2nd Main Rd Continue	1	69.00	0.80	0.25	13.80			
	3rd Main Rd	1	75.00	1.00	0.25	18.75			
	3rd Main Rd Continue	1	74.00	1.10	0.25	20.35			
	3rd Main Rd Continue	1	55.00	1.05	0.25	14.44			
	3rd Main Rd Continue	1	73.50	0.80	0.25	14.70			
	4th Main Rd	1	72.00	0.90	0.25	16.20			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th Main Rd Continue	1	55.00	0.90	0.25	12.38			
	4th Main Rd Continue	1	75.00	0.80	0.25	15.00			
	4th Main Rd Continue	1	76.00	0.70	0.25	13.30			
	5th Main Rd	1	47.00	0.80	0.25	9.40			
	5th Main Rd Continue	1	73.00	0.90	0.25	16.43			
	5th Main Rd Continue	1	72.00	0.75	0.25	13.50			
	5th Main Rd Continue	1	57.00	0.80	0.25	11.40			
	5th Main Rd Continue	1	72.00	0.75	0.25	13.50			
	6th Main Rd	1	67.00	0.90	0.25	15.08			
	6th Main Rd Continue	1	57.00	0.80	0.25	11.40			
	6th Main Rd Continue	1	73.00	0.80	0.25	14.60			
	6th Main Rd Continue	1	75.00	0.90	0.25	16.88			
	6th Main Rd Continue	1	47.00	0.75	0.25	8.81			
	7th Main Rd	1	46.00	0.90	0.25	10.35			
	7th Main Rd Continue	1	75.00	0.90	0.25	16.88			
	7th Main Rd Continue	1	73.00	0.80	0.25	14.60			
	7th Main Rd Continue	1	67.00	0.80	0.25	13.40			
	7th Main Rd Continue	1	68.00	0.80	0.25	13.60			
	8th Main Rd	1	65.00	0.90	0.25	14.63			
	8th Main Rd Continue	1	56.00	0.90	0.25	12.60			
	8th Main Rd Continue	1	74.00	0.90	0.25	16.65			
	8th Main Rd Continue	1	73.00	0.90	0.25	16.43			
	5th Cross Rd	1	45.00	0.90	0.25	10.13			
	10th Main Rd	1	219.00	0.90	0.25	49.28			
	11th Main Rd	1	212.00	0.90	0.25	47.70			
	1st Cross Rd	1	261.00	0.90	0.25	58.73			
	2nd Cross Rd	1	270.00	0.90	0.25	60.75			
	3rd Cross Rd	1	287.00	0.90	0.25	64.58			
	4th Cross Rd	1	265.00	0.90	0.25	59.63			
	Escorts Colony								
	1st Cross Rd	1	210.00	0.85	0.25	44.63			
	6th C Cross Rd	1	126.00	0.90	0.25	28.35			
	6th B Cross Rd	1	113.00	0.90	0.25	25.43			
	4th A Main Rd	1	139.00	0.90	0.25	31.28			
	6th A Main Rd	1	156.00	0.90	0.25	35.10			
	7th A Main Rd	1	239.00	0.85	0.25	50.79			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	0.90	0.25	77.18			
	1st Cross rd	1	64.00	0.90	0.25	14.40			
	2nd Cross rd	1	64.00	0.90	0.25	14.40			
	3rd Cross rd	1	65.00	0.90	0.25	14.63			
	4th Cross rd	1	65.00	0.90	0.25	14.63			
	5th Cross rd	1	65.00	0.90	0.25	14.63			
	6th Cross rd	1	65.00	0.90	0.25	14.63			
	7th Cross rd	1	65.00	0.90	0.25	14.63			
	3rd Cross Rd	1	323.00	0.90	0.25	72.68			
	Tirumalnagara								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd Cross Rd	1	314.00	1.50	0.25	117.75			
	1st Cross Rd	1	37.00	1.20	0.25	11.10			
	Santhosh nagara								
	Connecting RD-1	1	26.00	0.60	0.25	3.90			
	Connecting RD-2	1	44.00	0.60	0.25	6.60			
	Tharman Sharma Rd	1	33.00	0.60	0.25	4.95			
	9th B Cross Rd	1	36.00	0.60	0.25	5.40			
	7th Cross rd	1	174.00	0.60	0.25	26.10			
	1st Cross Rd	1	37.00	0.60	0.25	5.55			
	6th Cross Rd	1	429.00	1.60	0.25	171.60			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	0.60	0.25	2.85			
	Varaha Entreprises Rd	1	22.00	0.70	0.25	3.85			
	Cross Rd-6	1	23.00	0.70	0.25	4.03			
	Sri Lasya Rd	1	25.00	0.70	0.25	4.38			
	Health Care Home Rd	1	125.00	0.70	0.25	21.88			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	0.50	0.25	5.38			
	Cross Rd-5	1	24.00	0.50	0.25	3.00			
	Cross Rd-C	1	19.00	0.50	0.25	2.38			
	Cross Rd-2	1	19.00	0.50	0.25	2.38			
	Cross Rd-1	1	65.00	0.50	0.25	8.13			
	4th Cross rd	1	149.00	1.40	0.25	52.15			
	2nd Cross Rd	1	161.00	1.40	0.25	56.35			
	Ramadasappa Garden1st Cross rd	1	166.00	1.35	0.25	56.03			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	1.50	0.25	55.50			
	6th A Cross Rd	1	65.00	1.30	0.25	21.13			
	6th Cross Rd	1	57.00	1.20	0.25	17.10			
	8th Main Cross Rd-2	1	93.00	1.10	0.25	25.58			
	6th B Cross Rd	1	104.00	1.30	0.25	33.80			
	4th A Cross Rd	1	22.50	1.00	0.25	5.63			
	4th B Cross Rd	1	22.50	1.00	0.25	5.63			
	4th C Cross Rd	1	22.50	1.10	0.25	6.19			
	5thA Cross Rd	1	130.00	1.30	0.25	42.25			
	Chitra Layout [Harshitha Nilaya]	1	94.00	1.40	0.25	32.90			
	6th Cross Rd	1	134.00	1.50	0.25	50.25			
	9th Main rd	1	99.00	1.30	0.25	32.18			
	10th Main rd	1	43.00	1.20	0.25	12.90			
	11th Main Rd	1	54.50	1.20	0.25	16.35			
	Chitra Layout 3rd Cross Rd	1	64.00	1.30	0.25	20.80			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	1.20	0.25	13.50			
	2nd Cross Rd	1	45.50	1.20	0.25	13.65			
	3rd Cross Rd	1	46.00	1.00	0.25	11.50			
	4th Cross Rd	1	45.00	1.10	0.25	12.38			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	5th Cross Rd	1	45.00	1.30	0.25	14.63			
	7th Cross Rd	1	96.00	1.40	0.25	33.60			
	9th Cross Rd Left Side	1	99.00	1.30	0.25	32.18			
	9th Cross Rd Right Side	1	170.00	1.40	0.25	59.50			
	10th Cross Rd Left Side	1	44.00	1.10	0.25	12.10			
	10th Cross Rd Right Side	1	170.00	1.10	0.25	46.75			
	11th Cross Rd	1	48.00	5.80	0.25	69.60			
	1st Main Rd	1	122.00	1.10	0.25	33.55			
	1st Cross Rd	1	102.00	1.30	0.25	33.15			
	6th Cross 1st Cross Rd	1	28.00	1.00	0.25	7.00			
	6th Cross 2nd Cross Rd	1	25.00	0.90	0.25	5.63			
	6th Cross 3rd Cross Rd	1	23.00	0.90	0.25	5.18			
	6th Cross 4th Cross Rd	1	23.00	0.90	0.25	5.18			
	5th Cross Rd	1	270.00	1.60	0.25	108.00			
	4th Cross Rd	1	85.00	1.30	0.25	27.63			
		1	92.00	1.30	0.25	29.90			
	3rd Cross Rd	1	190.00	1.50	0.25	71.25			
	Cut Portion								
	Attur Layout								
	Attur Village Main Rd	1	72.00	1.10	0.25	19.80			
	2nd Main Rd Continue	1	53.00	1.10	0.25	14.58			
	2nd Main Rd Continue	1	73.00	1.10	0.25	20.08			
	2nd Main Rd Continue	1	73.00	1.20	0.25	21.90			
	2nd Main Rd Continue	1	69.00	1.00	0.25	17.25			
	3rd Main Rd	1	75.00	1.10	0.25	20.63			
	3rd Main Rd Continue	1	74.00	1.10	0.25	20.35			
	3rd Main Rd Continue	1	55.00	1.10	0.25	15.13			
	3rd Main Rd Continue	1	73.50	1.10	0.25	20.21			
	4th Main Rd	1	72.00	1.20	0.25	21.60			
	4th Main Rd Continue	1	55.00	1.20	0.25	16.50			
	4th Main Rd Continue	1	75.00	1.20	0.25	22.50			
	4th Main Rd Continue	1	76.00	1.20	0.25	22.80			
	5th Main Rd	1	47.00	1.00	0.25	11.75			
	5th Main Rd Continue	1	73.00	1.00	0.25	18.25			
	5th Main Rd Continue	1	72.00	1.00	0.25	18.00			
	5th Main Rd Continue	1	57.00	1.00	0.25	14.25			
	5th Main Rd Continue	1	72.00	1.00	0.25	18.00			
	6th Main Rd	1	67.00	1.10	0.25	18.43			
	6th Main Rd Continue	1	57.00	1.10	0.25	15.68			
	6th Main Rd Continue	1	73.00	1.10	0.25	20.08			
	6th Main Rd Continue	1	75.00	1.10	0.25	20.63			
	6th Main Rd Continue	1	47.00	1.10	0.25	12.93			
	7th Main Rd	1	46.00	1.10	0.25	12.65			
	7th Main Rd Continue	1	75.00	1.10	0.25	20.63			
	7th Main Rd Continue	1	73.00	1.10	0.25	20.08			
	7th Main Rd Continue	1	67.00	1.10	0.25	18.43			
	7th Main Rd Continue	1	68.00	1.10	0.25	18.70			
	8th Main Rd	1	65.00	1.00	0.25	16.25			
	8th Main Rd Continue	1	56.00	1.00	0.25	14.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	8th Main Rd Continue	1	74.00	1.00	0.25	18.50			
	8th Main Rd Continue	1	73.00	1.00	0.25	18.25			
	5th Cross Rd	1	45.00	1.00	0.25	11.25			
	10th Main Rd	1	219.00	1.00	0.25	54.75			
	11th Main Rd	1	212.00	1.00	0.25	53.00			
	1st Cross Rd	1	261.00	1.00	0.25	65.25			
	2nd Cross Rd	1	270.00	1.00	0.25	67.50			
	3rd Cross Rd	1	287.00	1.00	0.25	71.75			
	4th Cross Rd	1	265.00	1.00	0.25	66.25			
	Escorts Colony								
	1st Cross Rd	1	210.00	1.20	0.25	63.00			
	6th C Cross Rd	1	126.00	1.20	0.25	37.80			
	6th B Cross Rd	1	113.00	1.20	0.25	33.90			
	4th A Main Rd	1	139.00	1.20	0.25	41.70			
	6th A Main Rd	1	156.00	1.20	0.25	46.80			
	7th A Main Rd	1	239.00	1.20	0.25	71.70			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	1.10	0.25	94.33			
	1st Cross rd	1	64.00	1.10	0.25	17.60			
	2nd Cross rd	1	64.00	1.20	0.25	19.20			
	3rd Cross rd	1	65.00	1.00	0.25	16.25			
	4th Cross rd	1	65.00	1.10	0.25	17.88			
	5th Cross rd	1	65.00	1.10	0.25	17.88			
	6th Cross rd	1	65.00	1.00	0.25	16.25			
	7th Cross rd	1	65.00	1.20	0.25	19.50			
	3rd Cross Rd	1	323.00	1.00	0.25	80.75			
	Attur Village								
	Attur Villagae Rd	1	118.00	2.60	0.25	76.70			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	1.10	0.25	86.35			
	1st Cross Rd	1	37.00	1.20	0.25	11.10			
	Santhosh nagara								
	Connecting RD-1	1	26.00	1.00	0.25	6.50			
	Connecting RD-2	1	44.00	1.00	0.25	11.00			
	Tharman Sharma Rd	1	33.00	1.00	0.25	8.25			
	9th B Cross Rd	1	36.00	1.00	0.25	9.00			
	7th Cross rd	1	174.00	1.00	0.25	43.50			
	1st Cross Rd	1	37.00	1.00	0.25	9.25			
	6th Cross Rd	1	429.00	1.00	0.25	107.25			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	1.10	0.25	5.23			
	Varaha Entreprises Rd	1	22.00	1.20	0.25	6.60			
	Cross Rd-6	1	23.00	1.00	0.25	5.75			
	Sri Lasya Rd	1	25.00	1.10	0.25	6.88			
	Health Care Home Rd	1	125.00	1.20	0.25	37.50			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	1.10	0.25	11.83			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Rd-5	1	24.00	1.10	0.25	6.60			
	White Petal School Rd	1	19.00	1.10	0.25	5.23			
	Cross Rd-2	1	19.00	1.10	0.25	5.23			
	Cross Rd-1	1	65.00	1.10	0.25	17.88			
	4th Cross rd	1	149.00	1.10	0.25	40.98			
	2nd Cross Rd	1	161.00	1.10	0.25	44.28			
	Ramadasappa Garden1st Cross rd	1	166.00	1.10	0.25	45.65			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	0.70	0.25	25.90			
	6th A Cross Rd	1	65.00	0.80	0.25	13.00			
	6th Cross Rd	1	57.00	0.90	0.25	12.83			
	8th Main Cross Rd-2	1	93.00	0.90	0.25	20.93			
	6th B Cross Rd	1	104.00	0.90	0.25	23.40			
	4th A Cross Rd	1	22.50	0.90	0.25	5.06			
	4th B Cross Rd	1	22.50	0.90	0.25	5.06			
	4th C Cross Rd	1	22.50	0.90	0.25	5.06			
	5thA Cross Rd	1	130.00	0.90	0.25	29.25			
	Chitra Layout [Harshitha Nilaya]	1	94.00	0.90	0.25	21.15			
	6th Cross Rd	1	134.00	0.90	0.25	30.15			
	9th Main rd	1	99.00	0.80	0.25	19.80			
	10th Main rd	1	43.00	0.80	0.25	8.60			
	11th Main Rd	1	54.50	0.80	0.25	10.90			
	Chitra Layout 3rd Cross Rd	1	64.00	0.80	0.25	12.80			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.80	0.25	9.00			
	2nd Cross Rd	1	45.50	0.80	0.25	9.10			
	3rd Cross Rd	1	46.00	0.80	0.25	9.20			
	4th Cross Rd	1	45.00	0.80	0.25	9.00			
	5th Cross Rd	1	45.00	0.80	0.25	9.00			
	7th Cross Rd	1	96.00	0.80	0.25	19.20			
	9th Cross Rd Left Side	1	99.00	0.80	0.25	19.80			
	9th Cross Rd Right Side	1	170.00	0.90	0.25	38.25			
	10th Cross Rd Left Side	1	44.00	0.90	0.25	9.90			
	10th Cross Rd Right Side	1	170.00	0.90	0.25	38.25			
	11th Cross Rd	1	48.00	0.90	0.25	10.80			
	1st Main Rd	1	122.00	0.90	0.25	27.45			
	1st Cross Rd	1	102.00	0.90	0.25	22.95			
	6th Cross 1st Cross Rd	1	28.00	0.90	0.25	6.30			
	6th Cross 2nd Cross Rd	1	25.00	0.90	0.25	5.63			
	6th Cross 3rd Cross Rd	1	23.00	0.90	0.25	5.18			
	6th Cross 4th Cross Rd	1	23.00	0.90	0.25	5.18			
	5th Cross Rd	1	270.00	0.90	0.25	60.75			
	4th Cross Rd	1	85.00	0.70	0.25	14.88			
		1	92.00	0.70	0.25	16.10			
	3rd Cross Rd	1	190.00	0.70	0.25	33.25			



Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Sri Sai Layout								
	Cross Rd 1-to Cross Rd-2	1	272.50	5.80	0.35	553.18			
	Cross Rd-3	1	16.00	6.30	0.35	35.28			
	CC Road								
	Attur Layout								
	6th Cross Dead End	1	22.00	3.10	0.25	17.05			
	Burial Ground Entrance								
		1	210.00	4.00	0.30	252.00			
	For Cobble Stone								
	Apartment Side								
	S-LIG, 39,40,41,42								
	39 Back Side	1	5.50	3.50	0.25	4.81			
	40 Back Side	1	6.00	6.00	0.25	9.00			
	41 Behing Neha Prakash Hospital	1	22.00	10.50	0.25	57.75			
	42 Front Side	1	33.00	5.80	0.25	47.85			
	42 Back Side	1	30.00	15.00	0.25	112.50			
	42 Right Side	1	8.00	5.20	0.25	10.40			
		1	6.00	1.80	0.25	2.70			
	15th Block								
	Part-A	1	31.00	5.00	0.25	38.75			
	Part-B	1	9.00	3.50	0.25	7.88			
	Part-C	1	31.00	7.50	0.25	58.13			
	Part-D	1	9.00	3.50	0.25	7.88			
	Part-E	1	6.30	5.30	0.25	8.35			
	Part-F	1	9.40	5.30	0.25	12.46			
	S-HIG32								
	Part-A	1	9.30	5.00	0.25	11.63			
	Part-B	1	6.10	5.40	0.25	8.24			
	S-HIG B-09								
		1	29.00	6.00	0.25	43.50			
		1	37.40	5.50	0.25	51.43			
	Opp To Annapurnashweri Catering								
	Part-A	1	33.00	4.60	0.25	37.95			
	Part-B	1	10.50	5.30	0.25	13.91			
	Part-C	1	22.00	5.00	0.25	27.50			
	Part-D	1	10.50	16.20	0.25	42.53			
	Part-E	1	60.00	6.50	0.25	97.50			
	Part-F	4	8.50	2.50	0.25	21.25			
	Part-G	3	8.50	3.00	0.25	19.13			
	S-LIG 42								
	Beside Neha Prakasha Hospital								
	Part-A	1	27.00	5.00	0.25	33.75			
	Part-B	1	30.00	22.00	0.25	165.00			
	Part-C	1	27.00	4.50	0.25	30.38			
	Part-D	2	8.50	2.50	0.25	10.63			
	Part-E	2	8.50	3.00	0.25	12.75			
	Part-F	1	20.50	5.80	0.25	29.73			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Part-G	1	15.00	8.00	0.25	30.00			
	Part-H	1	5.00	5.00	0.25	6.25			
	Part-I	1	8.30	3.00	0.25	6.23			
	Part-J	1	37.00	5.00	0.25	46.25			
	Part-K	1	20.00	7.60	0.25	38.00			
	Part-L	1	37.00	4.80	0.25	44.40			
	Part-M	2	8.50	2.50	0.25	10.63			
	Part-N	2	8.50	3.00	0.25	12.75			
	Deduct Sump	-4	4.00	3.00	0.25	-12.00			
	Ward No-04								
	For Pathway								
	7thB Cross Rd	1	29.00	6.00	0.25	43.50		5044.86667	
	Debris	35	6.00	3.00	0.25	157.50			
						8088.12	**Cum**	**71.50**	**578300.40**
12	Construction of **Granular Sub-Base of** required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 .(V-III, I No-4.1V,P No-19,KPWD SR 2021-22)								
	Basic Rate	**2347.00**							
	Area Weightage 10%	234.70							
	Total Rate	**2581.70**							
	Asphalt Road								
	Edge Correctin/ Damage Portion								
	Ward No-04								
	B-Sector								
	4th B cross Rd	1	20.00	6.00	0.15	18.00			
	7th B Cross Rd	1	139.00	1.50	0.15	31.28			
	6th B Main Rd	1	40.00	1.40	0.15	8.40			
	7th B main Rd	1	40.00	1.90	0.15	11.40			
	9th Cross Rd	1	50.00	1.70	0.15	12.75			
	Attur Layout								
	Attur Village Main Rd	1	72.00	0.90	0.15	9.72			
	2nd Main Rd Continue	1	53.00	1.00	0.15	7.95			
	2nd Main Rd Continue	1	73.00	0.90	0.15	9.86			
	2nd Main Rd Continue	1	73.00	1.00	0.15	10.95			
	2nd Main Rd Continue	1	69.00	0.80	0.15	8.28			
	3rd Main Rd	1	75.00	1.00	0.15	11.25			
	3rd Main Rd Continue	1	74.00	1.10	0.15	12.21			
	3rd Main Rd Continue	1	55.00	1.05	0.15	8.66			
	3rd Main Rd Continue	1	73.50	0.80	0.15	8.82			
	4th Main Rd	1	72.00	0.90	0.15	9.72			
	4th Main Rd Continue	1	55.00	0.90	0.15	7.43			
	4th Main Rd Continue	1	75.00	0.80	0.15	9.00			
	4th Main Rd Continue	1	76.00	0.70	0.15	7.98			
	5th Main Rd	1	47.00	0.80	0.15	5.64			
	5th Main Rd Continue	1	73.00	0.90	0.15	9.86			
	5th Main Rd Continue	1	72.00	0.75	0.15	8.10			
	5th Main Rd Continue	1	57.00	0.80	0.15	6.84			
	5th Main Rd Continue	1	72.00	0.75	0.15	8.10			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Main Rd	1	67.00	0.90	0.15	9.05			
	6th Main Rd Continue	1	57.00	0.80	0.15	6.84			
	6th Main Rd Continue	1	73.00	0.80	0.15	8.76			
	6th Main Rd Continue	1	75.00	0.90	0.15	10.13			
	6th Main Rd Continue	1	47.00	0.75	0.15	5.29			
	7th Main Rd	1	46.00	0.90	0.15	6.21			
	7th Main Rd Continue	1	75.00	0.90	0.15	10.13			
	7th Main Rd Continue	1	73.00	0.80	0.15	8.76			
	7th Main Rd Continue	1	67.00	0.80	0.15	8.04			
	7th Main Rd Continue	1	68.00	0.80	0.15	8.16			
	8th Main Rd	1	65.00	0.90	0.15	8.78			
	8th Main Rd Continue	1	56.00	0.90	0.15	7.56			
	8th Main Rd Continue	1	74.00	0.90	0.15	9.99			
	8th Main Rd Continue	1	73.00	0.90	0.15	9.86			
	5th Cross Rd	1	45.00	0.90	0.15	6.08			
	10th Main Rd	1	219.00	0.90	0.15	29.57			
	11th Main Rd	1	212.00	0.90	0.15	28.62			
	1st Cross Rd	1	261.00	0.90	0.15	35.24			
	2nd Cross Rd	1	270.00	0.90	0.15	36.45			
	3rd Cross Rd	1	287.00	0.90	0.15	38.75			
	4th Cross Rd	1	265.00	0.90	0.15	35.78			
	Escorts Colony								
	1st Cross Rd	1	210.00	0.85	0.15	26.78			
	6th C Cross Rd	1	126.00	0.90	0.15	17.01			
	6th B Cross Rd	1	113.00	0.90	0.15	15.26			
	4th A Main Rd	1	139.00	0.90	0.15	18.77			
	6th A Main Rd	1	156.00	0.90	0.15	21.06			
	7th A Main Rd	1	239.00	0.85	0.15	30.47			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	0.90	0.15	46.31			
	1st Cross rd	1	64.00	0.90	0.15	8.64			
	2nd Cross rd	1	64.00	0.90	0.15	8.64			
	3rd Cross rd	1	65.00	0.90	0.15	8.78			
	4th Cross rd	1	65.00	0.90	0.15	8.78			
	5th Cross rd	1	65.00	0.90	0.15	8.78			
	6th Cross rd	1	65.00	0.90	0.15	8.78			
	7th Cross rd	1	65.00	0.90	0.15	8.78			
	3rd Cross Rd	1	323.00	0.90	0.15	43.61			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	1.50	0.15	70.65			
	1st Cross Rd	1	37.00	1.20	0.15	6.66			
	Santhosh nagara								
	Connecting RD-1	1	26.00	0.60	0.15	2.34			
	Connecting RD-2	1	44.00	0.60	0.15	3.96			
	Tharman Sharma Rd	1	33.00	0.60	0.15	2.97			
	9th B Cross Rd	1	36.00	0.60	0.15	3.24			
	7th Cross rd	1	174.00	0.60	0.15	15.66			
	1st Cross Rd	1	37.00	0.60	0.15	3.33			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Cross Rd	1	429.00	1.60	0.15	102.96			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	0.60	0.15	1.71			
	Varaha Entreprises Rd	1	22.00	0.70	0.15	2.31			
	Cross Rd-6	1	23.00	0.70	0.15	2.42			
	Sri Lasya Rd	1	25.00	0.70	0.15	2.63			
	Health Care Home Rd	1	125.00	0.70	0.15	13.13			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	0.50	0.15	3.23			
	Cross Rd-5	1	24.00	0.50	0.15	1.80			
	White Petal School Rd	1	19.00	0.50	0.15	1.43			
	Cross Rd-2	1	19.00	0.50	0.15	1.43			
	Cross Rd-1	1	65.00	0.50	0.15	4.88			
	4th Cross rd	1	149.00	1.40	0.15	31.29			
	2nd Cross Rd	1	161.00	1.40	0.15	33.81			
	Ramadasappa Garden1st Cross rd	1	166.00	1.35	0.15	33.62			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	1.50	0.15	33.30			
	6th A Cross Rd	1	65.00	1.30	0.15	12.68			
	6th Cross Rd	1	57.00	1.20	0.15	10.26			
	8th Main Cross Rd-2	1	93.00	1.10	0.15	15.35			
	6th B Cross Rd	1	104.00	1.30	0.15	20.28			
	4th A Cross Rd	1	22.50	1.00	0.15	3.38			
	4th B Cross Rd	1	22.50	1.00	0.15	3.38			
	4th C Cross Rd	1	22.50	1.10	0.15	3.71			
	5thA Cross Rd	1	130.00	1.30	0.15	25.35			
	Chitra Layout [Harshitha Nilaya]	1	94.00	1.40	0.15	19.74			
	6th Cross Rd	1	134.00	1.50	0.15	30.15			
	9th Main rd	1	99.00	1.30	0.15	19.31			
	10th Main rd	1	43.00	1.20	0.15	7.74			
	11th Main Rd	1	54.50	1.20	0.15	9.81			
	Chitra Layout 3rd Cross Rd	1	64.00	1.30	0.15	12.48			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	1.20	0.15	8.10			
	2nd Cross Rd	1	45.50	1.20	0.15	8.19			
	3rd Cross Rd	1	46.00	1.00	0.15	6.90			
	4th Cross Rd	1	45.00	1.10	0.15	7.43			
	5th Cross Rd	1	45.00	1.30	0.15	8.78			
	7th Cross Rd	1	96.00	1.40	0.15	20.16			
	9th Cross Rd Left Side	1	99.00	1.30	0.15	19.31			
	9th Cross Rd Right Side	1	170.00	1.40	0.15	35.70			
	10th Cross Rd Left Side	1	44.00	1.10	0.15	7.26			
	10th Cross Rd Right Side	1	170.00	1.10	0.15	28.05			
	11th Cross Rd	1	48.00	5.80	0.15	41.76			
	1st Main Rd	1	122.00	1.10	0.15	20.13			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Cross Rd	1	102.00	1.30	0.15	19.89			
	6th Cross 1st Cross Rd	1	28.00	1.00	0.15	4.20			
	6th Cross 2nd Cross Rd	1	25.00	0.90	0.15	3.38			
	6th Cross 3rd Cross Rd	1	23.00	0.90	0.15	3.11			
	6th Cross 4th Cross Rd	1	23.00	0.90	0.15	3.11			
	5th Cross Rd	1	270.00	1.60	0.15	64.80			
	4th Cross Rd	1	85.00	1.30	0.15	16.58			
		1	92.00	1.30	0.15	17.94			
	3rd Cross Rd	1	190.00	1.50	0.15	42.75			
	Cut Portion								
	Attur Layout								
	Attur Village Main Rd	1	72.00	1.10	0.15	11.88			
	2nd Main Rd Continue	1	53.00	1.10	0.15	8.75			
	2nd Main Rd Continue	1	73.00	1.10	0.15	12.05			
	2nd Main Rd Continue	1	73.00	1.20	0.15	13.14			
	2nd Main Rd Continue	1	69.00	1.00	0.15	10.35			
	3rd Main Rd	1	75.00	1.10	0.15	12.38			
	3rd Main Rd Continue	1	74.00	1.10	0.15	12.21			
	3rd Main Rd Continue	1	55.00	1.10	0.15	9.08			
	3rd Main Rd Continue	1	73.50	1.10	0.15	12.13			
	4th Main Rd	1	72.00	1.20	0.15	12.96			
	4th Main Rd Continue	1	55.00	1.20	0.15	9.90			
	4th Main Rd Continue	1	75.00	1.20	0.15	13.50			
	4th Main Rd Continue	1	76.00	1.20	0.15	13.68			
	5th Main Rd	1	47.00	1.00	0.15	7.05			
	5th Main Rd Continue	1	73.00	1.00	0.15	10.95			
	5th Main Rd Continue	1	72.00	1.00	0.15	10.80			
	5th Main Rd Continue	1	57.00	1.00	0.15	8.55			
	5th Main Rd Continue	1	72.00	1.00	0.15	10.80			
	6th Main Rd	1	67.00	1.10	0.15	11.06			
	6th Main Rd Continue	1	57.00	1.10	0.15	9.41			
	6th Main Rd Continue	1	73.00	1.10	0.15	12.05			
	6th Main Rd Continue	1	75.00	1.10	0.15	12.38			
	6th Main Rd Continue	1	47.00	1.10	0.15	7.76			
	7th Main Rd	1	46.00	1.10	0.15	7.59			
	7th Main Rd Continue	1	75.00	1.10	0.15	12.38			
	7th Main Rd Continue	1	73.00	1.10	0.15	12.05			
	7th Main Rd Continue	1	67.00	1.10	0.15	11.06			
	7th Main Rd Continue	1	68.00	1.10	0.15	11.22			
	8th Main Rd	1	65.00	1.00	0.15	9.75			
	8th Main Rd Continue	1	56.00	1.00	0.15	8.40			
	8th Main Rd Continue	1	74.00	1.00	0.15	11.10			
	8th Main Rd Continue	1	73.00	1.00	0.15	10.95			
	5th Cross Rd	1	45.00	1.00	0.15	6.75			
	10th Main Rd	1	219.00	1.00	0.15	32.85			
	11th Main Rd	1	212.00	1.00	0.15	31.80			
	1st Cross Rd	1	261.00	1.00	0.15	39.15			
	2nd Cross Rd	1	270.00	1.00	0.15	40.50			
	3rd Cross Rd	1	287.00	1.00	0.15	43.05			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th Cross Rd	1	265.00	1.00	0.15	39.75			
	Escorts Colony								
	1st Cross Rd	1	210.00	1.20	0.15	37.80			
	6th C Cross Rd	1	126.00	1.20	0.15	22.68			
	6th B Cross Rd	1	113.00	1.20	0.15	20.34			
	4th A Main Rd	1	139.00	1.20	0.15	25.02			
	6th A Main Rd	1	156.00	1.20	0.15	28.08			
	7th A Main Rd	1	239.00	1.20	0.15	43.02			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	1.10	0.15	56.60			
	1st Cross rd	1	64.00	1.10	0.15	10.56			
	2nd Cross rd	1	64.00	1.20	0.15	11.52			
	3rd Cross rd	1	65.00	1.00	0.15	9.75			
	4th Cross rd	1	65.00	1.10	0.15	10.73			
	5th Cross rd	1	65.00	1.10	0.15	10.73			
	6th Cross rd	1	65.00	1.00	0.15	9.75			
	7th Cross rd	1	65.00	1.20	0.15	11.70			
	3rd Cross Rd	1	323.00	1.00	0.15	48.45			
	Attur Village								
	Attur Villagae Rd	1	118.00	2.60	0.15	46.02			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	1.10	0.15	51.81			
	1st Cross Rd	1	37.00	1.20	0.15	6.66			
	Santhosh nagara								
	Connecting RD-1	1	26.00	1.00	0.15	3.90			
	Connecting RD-2	1	44.00	1.00	0.15	6.60			
	Tharman Sharma Rd	1	33.00	1.00	0.15	4.95			
	9th B Cross Rd	1	36.00	1.00	0.15	5.40			
	7th Cross rd	1	174.00	1.00	0.15	26.10			
	1st Cross Rd	1	37.00	1.00	0.15	5.55			
	6th Cross Rd	1	429.00	1.00	0.15	64.35			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	1.10	0.15	3.14			
	Varaha Entreprises Rd	1	22.00	1.20	0.15	3.96			
	Cross Rd-6	1	23.00	1.00	0.15	3.45			
	Sri Lasya Rd	1	25.00	1.10	0.15	4.13			
	Health Care Home Rd	1	125.00	1.20	0.15	22.50			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	1.10	0.15	7.10			
	Cross Rd-5	1	24.00	1.10	0.15	3.96			
	White Petal School Rd	1	19.00	1.10	0.15	3.14			
	Cross Rd-2	1	19.00	1.10	0.15	3.14			
	Cross Rd-1	1	65.00	1.10	0.15	10.73			
	4th Cross rd	1	149.00	1.10	0.15	24.59			
	2nd Cross Rd	1	161.00	1.10	0.15	26.57			
	Ramadasappa Garden1st Cross rd	1	166.00	1.10	0.15	27.39			
	Veerasagara Main Rd								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd Cross Rd	1	148.00	0.70	0.15	15.54			
	6th A Cross Rd	1	65.00	0.80	0.15	7.80			
	6th Cross Rd	1	57.00	0.90	0.15	7.70			
	8th Main Cross Rd-2	1	93.00	0.90	0.15	12.56			
	6th B Cross Rd	1	104.00	0.90	0.15	14.04			
	4th A Cross Rd	1	22.50	0.90	0.15	3.04			
	4th B Cross Rd	1	22.50	0.90	0.15	3.04			
	4th C Cross Rd	1	22.50	0.90	0.15	3.04			
	5thA Cross Rd	1	130.00	0.90	0.15	17.55			
	Chitra Layout [Harshitha Nilaya]	1	94.00	0.90	0.15	12.69			
	6th Cross Rd	1	134.00	0.90	0.15	18.09			
	9th Main rd	1	99.00	0.80	0.15	11.88			
	10th Main rd	1	43.00	0.80	0.15	5.16			
	11th Main Rd	1	54.50	0.80	0.15	6.54			
	Chitra Layout 3rd Cross Rd	1	64.00	0.80	0.15	7.68			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.80	0.15	5.40			
	2nd Cross Rd	1	45.50	0.80	0.15	5.46			
	3rd Cross Rd	1	46.00	0.80	0.15	5.52			
	4th Cross Rd	1	45.00	0.80	0.15	5.40			
	5th Cross Rd	1	45.00	0.80	0.15	5.40			
	7th Cross Rd	1	96.00	0.80	0.15	11.52			
	9th Cross Rd Left Side	1	99.00	0.80	0.15	11.88			
	9th Cross Rd Right Side	1	170.00	0.90	0.15	22.95			
	10th Cross Rd Left Side	1	44.00	0.90	0.15	5.94			
	10th Cross Rd Right Side	1	170.00	0.90	0.15	22.95			
	11th Cross Rd	1	48.00	0.90	0.15	6.48			
	1st Main Rd	1	122.00	0.90	0.15	16.47			
	1st Cross Rd	1	102.00	0.90	0.15	13.77			
	6th Cross 1st Cross Rd	1	28.00	0.90	0.15	3.78			
	6th Cross 2nd Cross Rd	1	25.00	0.90	0.15	3.38			
	6th Cross 3rd Cross Rd	1	23.00	0.90	0.15	3.11			
	6th Cross 4th Cross Rd	1	23.00	0.90	0.15	3.11			
	5th Cross Rd	1	270.00	0.90	0.15	36.45			
	4th Cross Rd	1	85.00	0.70	0.15	8.93			
		1	92.00	0.70	0.15	9.66			
	3rd Cross Rd	1	190.00	0.70	0.15	19.95			
	Sri Sai Layout								
	Cross Rd 1-to Cross Rd-2	1	272.50	5.80	0.15	237.08			
	Cross Rd-3	1	16.00	6.30	0.15	15.12			
	For Cobble Stone								
	Apartment Side								
	S-LIG, 39,40,41,42	1	5.50	3.50	0.10	1.93			
	39 Back Side	1	6.00	6.00	0.10	3.60			
	40 Back Side	1	22.00	10.50	0.10	23.10			
	41 Behing Neha Prakash Hospital								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	42 Front Side	1	33.00	5.80	0.10	19.14			
	42 Back Side	1	30.00	15.00	0.10	45.00			
	42 Right Side	1	8.00	5.20	0.10	4.16			
		1	6.00	1.80	0.10	1.08			
	15th Block								
	Part-A	1	31.00	5.00	0.10	15.50			
	Part-B	1	9.00	3.50	0.10	3.15			
	Part-C	1	31.00	7.50	0.10	23.25			
	Part-D	1	9.00	3.50	0.10	3.15			
	Part-E	1	6.30	5.30	0.10	3.34			
	Part-F	1	9.40	5.30	0.10	4.98			
	S-HIG32								
	Part-A	1	9.30	5.00	0.10	4.65			
	Part-B	1	6.10	5.40	0.10	3.29			
	S-HIG B-09								
		1	29.00	6.00	0.10	17.40			
		1	37.40	5.50	0.10	20.57			
	Ward No-04								
	For Pathway								
	7thB Cross Rd	1	29.00	6.00	0.10	17.40			
	Opp To Annapurnashweri Catering								
	Part-A	1	33.00	4.60	0.10	15.18			
	Part-B	1	10.50	5.30	0.10	5.57			
	Part-C	1	22.00	5.00	0.10	11.00			
	Part-D	1	10.50	16.20	0.10	17.01			
	Part-E	1	60.00	6.50	0.10	39.00			
	Part-F	4	8.50	2.50	0.10	8.50			
	Part-G	3	8.50	3.00	0.10	7.65			
	S-LIG 42								
	Beside Neha Prakasha Hospital								
	Part-A	1	27.00	5.00	0.10	13.50			
	Part-B	1	30.00	22.00	0.10	66.00			
	Part-C	1	27.00	4.50	0.10	12.15			
	Part-D	2	8.50	2.50	0.10	4.25			
	Part-E	2	8.50	3.00	0.10	5.10			
	Part-F	1	20.50	5.80	0.10	11.89			
	Part-G	1	15.00	8.00	0.10	12.00			
	Part-H	1	5.00	5.00	0.10	2.50			
	Part-I	1	8.30	3.00	0.10	2.49			
	Part-J	1	37.00	5.00	0.10	18.50			
	Part-K	1	20.00	7.60	0.10	15.20			
	Part-L	2	37.00	4.80	0.10	17.76			
	Part-M	2	8.50	2.50	0.10	4.25			
	Part-N	-4	8.50	3.00	0.10	5.10			
	Deduct Sump		4.00	3.00	0.10	-4.80			
						4243.82	Cum	2581.70	10956270.09

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
13	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density (V-III, P.No-24,I No-4.27A)of PWD SR 2021-22).								
	Basic Rate	**2394.00**							
	Area Weightage 10%	239.40							
	Total Rate	**2633.40**							
	Asphalt Road								
	Edge Correctin/ Damage								
	Ward No-04								
	B-Sector								
	4th B cross Rd	1	20.00	6.00	0.225	27.00			
	7th B Cross Rd	1	139.00	1.50	0.225	46.91			
	6th B Main Rd	1	40.00	1.40	0.225	12.60			
	7th B main Rd	1	40.00	1.90	0.225	17.10			
	9th Cross Rd	1	50.00	1.70	0.225	19.13			
	Attur Layout								
	Attur Village Main Rd	1	72.00	0.90	0.225	14.58			
	2nd Main Rd Continue	1	53.00	1.00	0.225	11.93			
	2nd Main Rd Continue	1	73.00	0.90	0.225	14.78			
	2nd Main Rd Continue	1	73.00	1.00	0.225	16.43			
	2nd Main Rd Continue	1	69.00	0.80	0.225	12.42			
	3rd Main Rd	1	75.00	1.00	0.225	16.88			
	3rd Main Rd Continue	1	74.00	1.10	0.225	18.32			
	3rd Main Rd Continue	1	55.00	1.05	0.225	12.99			
	3rd Main Rd Continue	1	73.50	0.80	0.225	13.23			
	4th Main Rd	1	72.00	0.90	0.225	14.58			
	4th Main Rd Continue	1	55.00	0.90	0.225	11.14			
	4th Main Rd Continue	1	75.00	0.80	0.225	13.50			
	4th Main Rd Continue	1	76.00	0.70	0.225	11.97			
	5th Main Rd	1	47.00	0.80	0.225	8.46			
	5th Main Rd Continue	1	73.00	0.90	0.225	14.78			
	5th Main Rd Continue	1	72.00	0.75	0.225	12.15			
	5th Main Rd Continue	1	57.00	0.80	0.225	10.26			
	5th Main Rd Continue	1	72.00	0.75	0.225	12.15			
	6th Main Rd	1	67.00	0.90	0.225	13.57			
	6th Main Rd Continue	1	57.00	0.80	0.225	10.26			
	6th Main Rd Continue	1	73.00	0.80	0.225	13.14			
	6th Main Rd Continue	1	75.00	0.90	0.225	15.19			
	6th Main Rd Continue	1	47.00	0.75	0.225	7.93			
	7th Main Rd	1	46.00	0.90	0.225	9.32			
	7th Main Rd Continue	1	75.00	0.90	0.225	15.19			
	7th Main Rd Continue	1	73.00	0.80	0.225	13.14			
	7th Main Rd Continue	1	67.00	0.80	0.225	12.06			
	7th Main Rd Continue	1	68.00	0.80	0.225	12.24			
	8th Main Rd	1	65.00	0.90	0.225	13.16			
	8th Main Rd Continue	1	56.00	0.90	0.225	11.34			
	8th Main Rd Continue	1	74.00	0.90	0.225	14.99			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	8th Main Rd Continue	1	73.00	0.90	0.225	14.78			
	5th Cross Rd	1	45.00	0.90	0.225	9.11			
	10th Main Rd	1	219.00	0.90	0.225	44.35			
	11th Main Rd	1	212.00	0.90	0.225	42.93			
	1st Cross Rd	1	261.00	0.90	0.225	52.85			
	2nd Cross Rd	1	270.00	0.90	0.225	54.68			
	3rd Cross Rd	1	287.00	0.90	0.225	58.12			
	4th Cross Rd	1	265.00	0.90	0.225	53.66			
	Escorts Colony								
	1st Cross Rd	1	210.00	0.85	0.225	40.16			
	6th C Cross Rd	1	126.00	0.90	0.225	25.52			
	6th B Cross Rd	1	113.00	0.90	0.225	22.88			
	4th A Main Rd	1	139.00	0.90	0.225	28.15			
	6th A Main Rd	1	156.00	0.90	0.225	31.59			
	7th A Main Rd	1	239.00	0.85	0.225	45.71			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	0.90	0.225	69.46			
	1st Cross rd	1	64.00	0.90	0.225	12.96			
	2nd Cross rd	1	64.00	0.90	0.225	12.96			
	3rd Cross rd	1	65.00	0.90	0.225	13.16			
	4th Cross rd	1	65.00	0.90	0.225	13.16			
	5th Cross rd	1	65.00	0.90	0.225	13.16			
	6th Cross rd	1	65.00	0.90	0.225	13.16			
	7th Cross rd	1	65.00	0.90	0.225	13.16			
	3rd Cross Rd	1	323.00	0.90	0.225	65.41			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	1.50	0.225	105.98			
	1st Cross Rd	1	37.00	1.20	0.225	9.99			
	Santhosh nagara								
	Connecting RD-1	1	26.00	0.60	0.225	3.51			
	Connecting RD-2	1	44.00	0.60	0.225	5.94			
	Tharman Sharma Rd	1	33.00	0.60	0.225	4.46			
	9th B Cross Rd	1	36.00	0.60	0.225	4.86			
	7th Cross rd	1	174.00	0.60	0.225	23.49			
	1st Cross Rd	1	37.00	0.60	0.225	5.00			
	6th Cross Rd	1	429.00	1.60	0.225	154.44			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	0.60	0.225	2.57			
	Varaha Entreprises Rd	1	22.00	0.70	0.225	3.47			
	Cross Rd-6	1	23.00	0.70	0.225	3.62			
	Sri Lasya Rd	1	25.00	0.70	0.225	3.94			
	Health Care Home Rd	1	125.00	0.70	0.225	19.69			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	0.50	0.225	4.84			
	Cross Rd-5	1	24.00	0.50	0.225	2.70			
	White Petal School Rd	1	19.00	0.50	0.225	2.14			
	Cross Rd-2	1	19.00	0.50	0.225	2.14			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Rd-1	1	65.00	0.50	0.225	7.31			
	4th Cross rd	1	149.00	1.40	0.225	46.94			
	2nd Cross Rd	1	161.00	1.40	0.225	50.72			
	Ramadasappa Garden1st Cross rd	1	166.00	1.35	0.225	50.42			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	1.50	0.225	49.95			
	6th A Cross Rd	1	65.00	1.30	0.225	19.01			
	6th Cross Rd	1	57.00	1.20	0.225	15.39			
	8th Main Cross Rd-2	1	93.00	1.10	0.225	23.02			
	6th B Cross Rd	1	104.00	1.30	0.225	30.42			
	4th A Cross Rd	1	22.50	1.00	0.225	5.06			
	4th B Cross Rd	1	22.50	1.00	0.225	5.06			
	4th C Cross Rd	1	22.50	1.10	0.225	5.57			
	5thA Cross Rd	1	130.00	1.30	0.225	38.03			
	Chitra Layout [Harshitha Nilaya]	1	94.00	1.40	0.225	29.61			
	6th Cross Rd	1	134.00	1.50	0.225	45.23			
	9th Main rd	1	99.00	1.30	0.225	28.96			
	10th Main rd	1	43.00	1.20	0.225	11.61			
	11th Main Rd	1	54.50	1.20	0.225	14.72			
	Chitra Layout 3rd Cross Rd	1	64.00	1.30	0.225	18.72			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	1.20	0.225	12.15			
	2nd Cross Rd	1	45.50	1.20	0.225	12.29			
	3rd Cross Rd	1	46.00	1.00	0.225	10.35			
	4th Cross Rd	1	45.00	1.10	0.225	11.14			
	5th Cross Rd	1	45.00	1.30	0.225	13.16			
	7th Cross Rd	1	96.00	1.40	0.225	30.24			
	9th Cross Rd Left Side	1	99.00	1.30	0.225	28.96			
	9th Cross Rd Right Side	1	170.00	1.40	0.225	53.55			
	10th Cross Rd Left Side	1	44.00	1.10	0.225	10.89			
	10th Cross Rd Right Side	1	170.00	1.10	0.225	42.08			
	11th Cross Rd	1	48.00	5.80	0.225	62.64			
	1st Main Rd	1	122.00	1.10	0.225	30.20			
	1st Cross Rd	1	102.00	1.30	0.225	29.84			
	6th Cross 1st Cross Rd	1	28.00	1.00	0.225	6.30			
	6th Cross 2nd Cross Rd	1	25.00	0.90	0.225	5.06			
	6th Cross 3rd Cross Rd	1	23.00	0.90	0.225	4.66			
	6th Cross 4th Cross Rd	1	23.00	0.90	0.225	4.66			
	5th Cross Rd	1	270.00	1.60	0.225	97.20			
	4th Cross Rd	1	85.00	1.30	0.225	24.86			
		1	92.00	1.30	0.225	26.91			
	3rd Cross Rd	1	190.00	1.50	0.225	64.13			
	Cut Portion								
	Attur Layout								
	Attur Village Main Rd	1	72.00	1.10	0.225	17.82			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd Main Rd Continue	1	53.00	1.10	0.225	13.12			
	2nd Main Rd Continue	1	73.00	1.10	0.225	18.07			
	2nd Main Rd Continue	1	73.00	1.20	0.225	19.71			
	2nd Main Rd Continue	1	69.00	1.00	0.225	15.53			
	3rd Main Rd	1	75.00	1.10	0.225	18.56			
	3rd Main Rd Continue	1	74.00	1.10	0.225	18.32			
	3rd Main Rd Continue	1	55.00	1.10	0.225	13.61			
	3rd Main Rd Continue	1	73.50	1.10	0.225	18.19			
	4th Main Rd	1	72.00	1.20	0.225	19.44			
	4th Main Rd Continue	1	55.00	1.20	0.225	14.85			
	4th Main Rd Continue	1	75.00	1.20	0.225	20.25			
	4th Main Rd Continue	1	76.00	1.20	0.225	20.52			
	5th Main Rd	1	47.00	1.00	0.225	10.58			
	5th Main Rd Continue	1	73.00	1.00	0.225	16.43			
	5th Main Rd Continue	1	72.00	1.00	0.225	16.20			
	5th Main Rd Continue	1	57.00	1.00	0.225	12.83			
	5th Main Rd Continue	1	72.00	1.00	0.225	16.20			
	6th Main Rd	1	67.00	1.10	0.225	16.58			
	6th Main Rd Continue	1	57.00	1.10	0.225	14.11			
	6th Main Rd Continue	1	73.00	1.10	0.225	18.07			
	6th Main Rd Continue	1	75.00	1.10	0.225	18.56			
	6th Main Rd Continue	1	47.00	1.10	0.225	11.63			
	7th Main Rd	1	46.00	1.10	0.225	11.39			
	7th Main Rd Continue	1	75.00	1.10	0.225	18.56			
	7th Main Rd Continue	1	73.00	1.10	0.225	18.07			
	7th Main Rd Continue	1	67.00	1.10	0.225	16.58			
	7th Main Rd Continue	1	68.00	1.10	0.225	16.83			
	8th Main Rd	1	65.00	1.00	0.225	14.63			
	8th Main Rd Continue	1	56.00	1.00	0.225	12.60			
	8th Main Rd Continue	1	74.00	1.00	0.225	16.65			
	8th Main Rd Continue	1	73.00	1.00	0.225	16.43			
	5th Cross Rd	1	45.00	1.00	0.225	10.13			
	10th Main Rd	1	219.00	1.00	0.225	49.28			
	11th Main Rd	1	212.00	1.00	0.225	47.70			
	1st Cross Rd	1	261.00	1.00	0.225	58.73			
	2nd Cross Rd	1	270.00	1.00	0.225	60.75			
	3rd Cross Rd	1	287.00	1.00	0.225	64.58			
	4th Cross Rd	1	265.00	1.00	0.225	59.63			
	Escorts Colony								
	1st Cross Rd	1	210.00	1.20	0.225	56.70			
	6th C Cross Rd	1	126.00	1.20	0.225	34.02			
	6th B Cross Rd	1	113.00	1.20	0.225	30.51			
	4th A Main Rd	1	139.00	1.20	0.225	37.53			
	6th A Main Rd	1	156.00	1.20	0.225	42.12			
	7th A Main Rd	1	239.00	1.20	0.225	64.53			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	1.10	0.225	84.89			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Cross rd	1	64.00	1.10	0.225	15.84			
	2nd Cross rd	1	64.00	1.20	0.225	17.28			
	3rd Cross rd	1	65.00	1.00	0.225	14.63			
	4th Cross rd	1	65.00	1.10	0.225	16.09			
	5th Cross rd	1	65.00	1.10	0.225	16.09			
	6th Cross rd	1	65.00	1.00	0.225	14.63			
	7th Cross rd	1	65.00	1.20	0.225	17.55			
	3rd Cross Rd	1	323.00	1.00	0.225	72.68			
	Attur Village								
	Attur Villagae Rd	1	118.00	2.60	0.225	69.03			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	1.10	0.225	77.72			
	1st Cross Rd	1	37.00	1.20	0.225	9.99			
	Santhosh nagara								
	Connecting RD-1	1	26.00	1.00	0.225	5.85			
	Connecting RD-2	1	44.00	1.00	0.225	9.90			
	Tharman Sharma Rd	1	33.00	1.00	0.225	7.43			
	9th B Cross Rd	1	36.00	1.00	0.225	8.10			
	7th Cross rd	1	174.00	1.00	0.225	39.15			
	1st Cross Rd	1	37.00	1.00	0.225	8.33			
	6th Cross Rd	1	429.00	1.00	0.225	96.53			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	1.10	0.225	4.70			
	Varaha Entreprises Rd	1	22.00	1.20	0.225	5.94			
	Cross Rd-6	1	23.00	1.00	0.225	5.18			
	Sri Lasya Rd	1	25.00	1.10	0.225	6.19			
	Health Care Home Rd	1	125.00	1.20	0.225	33.75			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	1.10	0.225	10.64			
	Cross Rd-5	1	24.00	1.10	0.225	5.94			
	Cross Rd-C	1	19.00	1.10	0.225	4.70			
	Cross Rd-2	1	19.00	1.10	0.225	4.70			
	Cross Rd-1	1	65.00	1.10	0.225	16.09			
	4th Cross rd	1	149.00	1.10	0.225	36.88			
	2nd Cross Rd	1	161.00	1.10	0.225	39.85			
	Ramadasappa Garden1st Cross rd	1	166.00	1.10	0.225	41.09			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	0.70	0.225	23.31			
	6th A Cross Rd	1	65.00	0.80	0.225	11.70			
	6th Cross Rd	1	57.00	0.90	0.225	11.54			
	8th Main Cross Rd-2	1	93.00	0.90	0.225	18.83			
	6th B Cross Rd	1	104.00	0.90	0.225	21.06			
	4th A Cross Rd	1	22.50	0.90	0.225	4.56			
	4th B Cross Rd	1	22.50	0.90	0.225	4.56			
	4th C Cross Rd	1	22.50	0.90	0.225	4.56			
	5thA Cross Rd	1	130.00	0.90	0.225	26.33			
	Chitra Layout [Harshitha Nilaya]	1	94.00	0.90	0.225	19.04			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Cross Rd	1	134.00	0.90	0.225	27.14			
	9th Main rd	1	99.00	0.80	0.225	17.82			
	10th Main rd	1	43.00	0.80	0.225	7.74			
	11th Main Rd	1	54.50	0.80	0.225	9.81			
	Chitra Layout 3rd Cross Rd	1	64.00	0.80	0.225	11.52			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.80	0.225	8.10			
	2nd Cross Rd	1	45.50	0.80	0.225	8.19			
	3rd Cross Rd	1	46.00	0.80	0.225	8.28			
	4th Cross Rd	1	45.00	0.80	0.225	8.10			
	5th Cross Rd	1	45.00	0.80	0.225	8.10			
	7th Cross Rd	1	96.00	0.80	0.225	17.28			
	9th Cross Rd Left Side	1	99.00	0.80	0.225	17.82			
	9th Cross Rd Right Side	1	170.00	0.90	0.225	34.43			
	10th Cross Rd Left Side	1	44.00	0.90	0.225	8.91			
	10th Cross Rd Right Side	1	170.00	0.90	0.225	34.43			
	11th Cross Rd	1	48.00	0.90	0.225	9.72			
	1st Main Rd	1	122.00	0.90	0.225	24.71			
	1st Cross Rd	1	102.00	0.90	0.225	20.66			
	6th Cross 1st Cross Rd	1	28.00	0.90	0.225	5.67			
	6th Cross 2nd Cross Rd	1	25.00	0.90	0.225	5.06			
	6th Cross 3rd Cross Rd	1	23.00	0.90	0.225	4.66			
	6th Cross 4th Cross Rd	1	23.00	0.90	0.225	4.66			
	5th Cross Rd	1	270.00	0.90	0.225	54.68			
	4th Cross Rd	1	85.00	0.70	0.225	13.39			
		1	92.00	0.70	0.225	14.49			
	3rd Cross Rd	1	190.00	0.70	0.225	29.93			
	Sri Sai Layout								
	Cross Rd 1-to Cross Rd-2	1	272.50	5.80	0.225	355.61			
	Cross Rd-3	1	16.00	6.30	0.225	22.68			
						5609.00	Cum	2633.40	14770747.18
14	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means. (V-III, P.No-29,I No-5.1(i) of PWD SR 2021-22).								
	Basic Rate	44.00							
	Area Weightage 10%	4.40							
	Total Rate	48.40							
	Asphalt Road								
	For Profile correction								
	Ward No-04								
	B-Sector	1	20.00	6.00		120.00			
	4th B cross Rd	1	139.00	6.30		875.70			
	7th B Cross Rd	1	40.00	5.80		232.00			
	6th B Main Rd	1	40.00	6.60		264.00			
	7th B main Rd	1	50.00	5.10		255.00			
	9th Cross Rd								
	Attur Layout	1	72.00	4.30		309.60			
	Attur Village Main Rd								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	2nd Main Rd Continue	1	53.00	3.90		206.70			
	2nd Main Rd Continue	1	73.00	4.80		350.40			
	2nd Main Rd Continue	1	73.00	4.70		343.10			
	3rd Main Rd	1	69.00	5.00		345.00			
	3rd Main Rd Continue	1	75.00	4.50		337.50			
	3rd Main Rd Continue	1	74.00	4.20		310.80			
	3rd Main Rd Continue	1	55.00	4.00		220.00			
	4th Main Rd	1	73.50	4.60		338.10			
	4th Main Rd Continue	1	72.00	4.40		316.80			
	4th Main Rd Continue	1	55.00	4.20		231.00			
	4th Main Rd Continue	1	75.00	4.20		315.00			
	5th Main Rd	1	76.00	5.00		380.00			
	5th Main Rd Continue	1	47.00	4.60		216.20			
	5th Main Rd Continue	1	73.00	5.60		408.80			
	5th Main Rd Continue	1	72.00	5.00		360.00			
	5th Main Rd Continue	1	57.00	4.90		279.30			
	5th Main Rd Continue	1	72.00	5.40		388.80			
	6th Main Rd	1	67.00	4.00		268.00			
	6th Main Rd Continue	1	57.00	4.40		250.80			
	6th Main Rd Continue	1	73.00	4.40		321.20			
	6th Main Rd Continue	1	75.00	4.30		322.50			
	6th Main Rd Continue	1	47.00	3.60		169.20			
	7th Main Rd	1	46.00	4.40		202.40			
	7th Main Rd Continue	1	75.00	4.30		322.50			
	7th Main Rd Continue	1	73.00	5.00		365.00			
	7th Main Rd Continue	1	67.00	4.50		301.50			
	7th Main Rd Continue	1	68.00	4.70		319.60			
	8th Main Rd	1	65.00	5.80		377.00			
	8th Main Rd Continue	1	56.00	5.00		280.00			
	8th Main Rd Continue	1	74.00	5.00		370.00			
	8th Main Rd Continue	1	73.00	4.90		357.70			
	5th Cross Rd	1	45.00	4.50		202.50			
	10th Main Rd	1	219.00	4.60		1007.40			
	11th Main Rd	1	212.00	4.00		848.00			
	1st Cross Rd	1	261.00	6.80		1774.80			
	2nd Cross Rd	1	270.00	6.50		1755.00			
	3rd Cross Rd	1	287.00	6.50		1865.50			
	4th Cross Rd	1	265.00	6.80		1802.00			
	Santhosh nagara								
	Connecting RD-1	1	26.00	4.00		104.00			
	Connecting RD-2	1	44.00	4.00		176.00			
	Tharman Sharma Rd	1	33.00	4.00		132.00			
	9th B Cross Rd	1	36.00	4.00		144.00			
	7th Cross rd	1	174.00	4.20		730.80			
	1st Cross Rd	1	37.00	4.40		162.80			
	6th Cross Rd	1	429.00	5.60		2402.40			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	5.30		100.70			
	Varaha Entreprises Rd	1	22.00	5.10		112.20			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Cross Rd-6	1	23.00	4.80		110.40			
	Sri Lasya Rd	1	25.00	4.80		120.00			
	Health Care Home Rd	1	125.00	5.80		725.00			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	4.00		172.00			
	Cross Rd-5	1	24.00	4.20		100.80			
	White Petal School Rd	1	19.00	3.80		72.20			
	Cross Rd-2	1	19.00	4.50		85.50			
	Cross Rd-1	1	65.00	5.10		331.50			
	4th Cross rd	1	149.00	5.10		759.90			
	2nd Cross Rd	1	161.00	4.50		724.50			
	Ramadasappa Garden1st Cross rd	1	166.00	5.50		913.00			
						29066.10			
	Profile correction 20%					**5813.22**			
	Edge Correctin/ Damage								
	Ward No-04								
	B-Sector								
	4th B cross Rd	1	20.00	6.00		120.00			
	7th B Cross Rd	1	139.00	1.50		208.50			
	6th B Main Rd	1	40.00	1.40		56.00			
	7th B main Rd	1	40.00	1.90		76.00			
	9th Cross Rd	1	50.00	1.70		85.00			
	Attur Layout								
	Attur Village Main Rd	1	72.00	0.90		64.80			
	2nd Main Rd Continue	1	53.00	1.00		53.00			
	2nd Main Rd Continue	1	73.00	0.90		65.70			
	2nd Main Rd Continue	1	73.00	1.00		73.00			
	2nd Main Rd Continue	1	69.00	0.80		55.20			
	3rd Main Rd	1	75.00	1.00		75.00			
	3rd Main Rd Continue	1	74.00	1.10		81.40			
	3rd Main Rd Continue	1	55.00	1.05		57.75			
	3rd Main Rd Continue	1	73.50	0.80		58.80			
	4th Main Rd	1	72.00	0.90		64.80			
	4th Main Rd Continue	1	55.00	0.90		49.50			
	4th Main Rd Continue	1	75.00	0.80		60.00			
	4th Main Rd Continue	1	76.00	0.70		53.20			
	5th Main Rd	1	47.00	0.80		37.60			
	5th Main Rd Continue	1	73.00	0.90		65.70			
	5th Main Rd Continue	1	72.00	0.75		54.00			
	5th Main Rd Continue	1	57.00	0.80		45.60			
	5th Main Rd Continue	1	72.00	0.75		54.00			
	6th Main Rd	1	67.00	0.90		60.30			
	6th Main Rd Continue	1	57.00	0.80		45.60			
	6th Main Rd Continue	1	73.00	0.80		58.40			
	6th Main Rd Continue	1	75.00	0.90		67.50			
	6th Main Rd Continue	1	47.00	0.75		35.25			
	7th Main Rd	1	46.00	0.90		41.40			
	7th Main Rd Continue	1	75.00	0.90		67.50			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	7th Main Rd Continue	1	73.00	0.80		58.40			
	7th Main Rd Continue	1	67.00	0.80		53.60			
	7th Main Rd Continue	1	68.00	0.80		54.40			
	8th Main Rd	1	65.00	0.90		58.50			
	8th Main Rd Continue	1	56.00	0.90		50.40			
	8th Main Rd Continue	1	74.00	0.90		66.60			
	8th Main Rd Continue	1	73.00	0.90		65.70			
	5th Cross Rd	1	45.00	0.90		40.50			
	10th Main Rd	1	219.00	0.90		197.10			
	11th Main Rd	1	212.00	0.90		190.80			
	1st Cross Rd	1	261.00	0.90		234.90			
	2nd Cross Rd	1	270.00	0.90		243.00			
	3rd Cross Rd	1	287.00	0.90		258.30			
	4th Cross Rd	1	265.00	0.90		238.50			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	0.90		308.70			
	1st Cross rd	1	64.00	0.90		57.60			
	2nd Cross rd	1	64.00	0.90		57.60			
	3rd Cross rd	1	65.00	0.90		58.50			
	4th Cross rd	1	65.00	0.90		58.50			
	5th Cross rd	1	65.00	0.90		58.50			
	6th Cross rd	1	65.00	0.90		58.50			
	7th Cross rd	1	65.00	0.90		58.50			
	3rd Cross Rd	1	323.00	0.90		290.70			
	Santhosh nagara								
	Connecting RD-1	1	26.00	0.60		15.60			
	Connecting RD-2	1	44.00	0.60		26.40			
	Tharman Sharma Rd	1	33.00	0.60		19.80			
	9th B Cross Rd	1	36.00	0.60		21.60			
	7th Cross rd	1	174.00	0.60		104.40			
	1st Cross Rd	1	37.00	0.60		22.20			
	6th Cross Rd	1	429.00	1.60		686.40			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	0.60		11.40			
	Varaha Entreprises Rd	1	22.00	0.70		15.40			
	Cross Rd-6	1	23.00	0.70		16.10			
	Sri Lasya Rd	1	25.00	0.70		17.50			
	Health Care Home Rd	1	125.00	0.70		87.50			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	0.50		21.50			
	Cross Rd-5	1	24.00	0.50		12.00			
	White Petal School Rd	1	19.00	0.50		9.50			
	Cross Rd-2	1	19.00	0.50		9.50			
	Cross Rd-1	1	65.00	0.50		32.50			
	4th Cross rd	1	149.00	1.40		208.60			
	2nd Cross Rd	1	161.00	1.40		225.40			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Ramadasappa Garden1st Cross rd	1	166.00	1.35		224.10			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	1.50		222.00			
	6th A Cross Rd	1	65.00	1.30		84.50			
	6th Cross Rd	1	57.00	1.20		68.40			
	8th Main Cross Rd-2	1	93.00	1.10		102.30			
	6th B Cross Rd	1	104.00	1.30		135.20			
	4th A Cross Rd	1	22.50	1.00		22.50			
	4th B Cross Rd	1	22.50	1.00		22.50			
	4th C Cross Rd	1	22.50	1.10		24.75			
	5thA Cross Rd	1	130.00	1.30		169.00			
	Chitra Layout [Harshitha Nilaya]	1	94.00	1.40		131.60			
	6th Cross Rd	1	134.00	1.50		201.00			
	9th Main rd	1	99.00	1.30		128.70			
	10th Main rd	1	43.00	1.20		51.60			
	11th Main Rd	1	54.50	1.20		65.40			
	Chitra Layout 3rd Cross Rd	1	64.00	1.30		83.20			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	1.20		54.00			
	2nd Cross Rd	1	45.50	1.20		54.60			
	3rd Cross Rd	1	46.00	1.00		46.00			
	4th Cross Rd	1	45.00	1.10		49.50			
	5th Cross Rd	1	45.00	1.30		58.50			
	7th Cross Rd	1	96.00	1.40		134.40			
	9th Cross Rd Left Side	1	99.00	1.30		128.70			
	9th Cross Rd Right Side	1	170.00	1.40		238.00			
	10th Cross Rd Left Side	1	44.00	1.10		48.40			
	10th Cross Rd Right Side	1	170.00	1.10		187.00			
	11th Cross Rd	1	48.00	5.80		278.40			
	1st Main Rd	1	122.00	1.10		134.20			
	1st Cross Rd	1	102.00	1.30		132.60			
	6th Cross 1st Cross Rd	1	28.00	1.00		28.00			
	6th Cross 2nd Cross Rd	1	25.00	0.90		22.50			
	6th Cross 3rd Cross Rd	1	23.00	0.90		20.70			
	6th Cross 4th Cross Rd	1	23.00	0.90		20.70			
	5th Cross Rd	1	270.00	1.60		432.00			
	4th Cross Rd	1	85.00	1.30		110.50			
		1	92.00	1.30		119.60			
	3rd Cross Rd	1	190.00	1.50		285.00			
	Cut Portion								
	Attur Layout								
	Attur Village Main Rd	1	72.00	1.10		79.20			
	2nd Main Rd Continue	1	53.00	1.10		58.30			
	2nd Main Rd Continue	1	73.00	1.10		80.30			
	2nd Main Rd Continue	1	73.00	1.20		87.60			
	2nd Main Rd Continue	1	69.00	1.00		69.00			
	2nd Main Rd Continue								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd Main Rd	1	75.00	1.10		82.50			
	3rd Main Rd Continue	1	74.00	1.10		81.40			
	3rd Main Rd Continue	1	55.00	1.10		60.50			
	4th Main Rd	1	73.50	1.10		80.85			
	4th Main Rd Continue	1	72.00	1.20		86.40			
	4th Main Rd Continue	1	55.00	1.20		66.00			
	4th Main Rd Continue	1	75.00	1.20		90.00			
	5th Main Rd	1	76.00	1.20		91.20			
	5th Main Rd Continue	1	47.00	1.00		47.00			
	5th Main Rd Continue	1	73.00	1.00		73.00			
	5th Main Rd Continue	1	72.00	1.00		72.00			
	5th Main Rd Continue	1	57.00	1.00		57.00			
	6th Main Rd	1	72.00	1.00		72.00			
	6th Main Rd Continue	1	67.00	1.10		73.70			
	6th Main Rd Continue	1	57.00	1.10		62.70			
	6th Main Rd Continue	1	73.00	1.10		80.30			
	6th Main Rd Continue	1	75.00	1.10		82.50			
	7th Main Rd	1	47.00	1.10		51.70			
	7th Main Rd Continue	1	46.00	1.10		50.60			
	7th Main Rd Continue	1	75.00	1.10		82.50			
	7th Main Rd Continue	1	73.00	1.10		80.30			
	7th Main Rd Continue	1	67.00	1.10		73.70			
	8th Main Rd	1	68.00	1.10		74.80			
	8th Main Rd Continue	1	65.00	1.00		65.00			
	8th Main Rd Continue	1	56.00	1.00		56.00			
	8th Main Rd Continue	1	74.00	1.00		74.00			
	5th Cross Rd	1	73.00	1.00		73.00			
	10th Main Rd	1	45.00	1.00		45.00			
	11th Main Rd	1	219.00	1.00		219.00			
	1st Cross Rd	1	212.00	1.00		212.00			
	2nd Cross Rd	1	261.00	1.00		261.00			
	3rd Cross Rd	1	270.00	1.00		270.00			
	4th Cross Rd	1	287.00	1.00		287.00			
	Escorts Colony	1	265.00	1.00		265.00			
	1st Cross Rd	1	210.00	1.20		252.00			
	6th C Cross Rd	1	126.00	1.20		151.20			
	6th B Cross Rd	1	113.00	1.20		135.60			
	4th A Main Rd	1	139.00	1.20		166.80			
	6th A Main Rd	1	156.00	1.20		187.20			
	7th A Main Rd	1	239.00	1.20		286.80			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	1.10		377.30			
	1st Cross rd	1	64.00	1.10		70.40			
	2nd Cross rd	1	64.00	1.20		76.80			
	3rd Cross rd	1	65.00	1.00		65.00			
	4th Cross rd	1	65.00	1.10		71.50			
	5th Cross rd	1	65.00	1.10		71.50			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th Cross rd	1	65.00	1.00		65.00			
	7th Cross rd	1	65.00	1.20		78.00			
	3rd Cross Rd	1	323.00	1.00		323.00			
	Attur Village								
	Attur Villagae Rd	1	118.00	6.60		778.80			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	6.90		2166.60			
	1st Cross Rd	1	37.00	7.00		259.00			
	Santhosh nagara								
	Connecting RD-1	1	26.00	1.00		26.00			
	Connecting RD-2	1	44.00	1.00		44.00			
	Tharman Sharma Rd	1	33.00	1.00		33.00			
	9th B Cross Rd	1	36.00	1.00		36.00			
	7th Cross rd	1	174.00	1.00		174.00			
	1st Cross Rd	1	37.00	1.00		37.00			
	6th Cross Rd	1	429.00	1.00		429.00			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	1.10		20.90			
	Varaha Entreprises Rd	1	22.00	1.20		26.40			
	Cross Rd-6	1	23.00	1.00		23.00			
	Sri Lasya Rd	1	25.00	1.10		27.50			
	Health Care Home Rd	1	125.00	1.20		150.00			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	1.10		47.30			
	Cross Rd-5	1	24.00	1.10		26.40			
	White Petal School Rd	1	19.00	1.10		20.90			
	Cross Rd-2	1	19.00	1.10		20.90			
	Cross Rd-1	1	65.00	1.10		71.50			
	4th Cross rd	1	149.00	1.10		163.90			
	2nd Cross Rd	1	161.00	1.10		177.10			
	Ramadasappa Garden1st Cross rd	1	166.00	1.10		182.60			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	0.70		103.60			
	6th A Cross Rd	1	65.00	0.80		52.00			
	6th Cross Rd	1	57.00	0.90		51.30			
	8th Main Cross Rd-2	1	93.00	0.90		83.70			
	6th B Cross Rd	1	104.00	0.90		93.60			
	4th A Cross Rd	1	22.50	0.90		20.25			
	4th B Cross Rd	1	22.50	0.90		20.25			
	4th C Cross Rd	1	22.50	0.90		20.25			
	5thA Cross Rd	1	130.00	0.90		117.00			
	Chitra Layout [Harshitha Nilaya]	1	94.00	0.90		84.60			
	6th Cross Rd	1	134.00	0.90		120.60			
	9th Main rd	1	99.00	0.80		79.20			
	10th Main rd	1	43.00	0.80		34.40			
	11th Main Rd	1	54.50	0.80		43.60			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Chitra Layout 3rd Cross Rd	1	64.00	0.80		51.20			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.80		36.00			
	2nd Cross Rd	1	45.50	0.80		36.40			
	3rd Cross Rd	1	46.00	0.80		36.80			
	4th Cross Rd	1	45.00	0.80		36.00			
	5th Cross Rd	1	45.00	0.80		36.00			
	7th Cross Rd	1	96.00	0.80		76.80			
	9th Cross Rd Left Side	1	99.00	0.80		79.20			
	9th Cross Rd Right Side	1	170.00	0.90		153.00			
	10th Cross Rd Left Side	1	44.00	0.90		39.60			
	10th Cross Rd Right Side	1	170.00	0.90		153.00			
	11th Cross Rd	1	48.00	0.90		43.20			
	1st Main Rd	1	122.00	0.90		109.80			
	1st Cross Rd	1	102.00	0.90		91.80			
	6th Cross 1st Cross Rd	1	28.00	0.90		25.20			
	6th Cross 2nd Cross Rd	1	25.00	0.90		22.50			
	6th Cross 3rd Cross Rd	1	23.00	0.90		20.70			
	6th Cross 4th Cross Rd	1	23.00	0.90		20.70			
	5th Cross Rd	1	270.00	0.90		243.00			
	4th Cross Rd	1	85.00	0.70		59.50			
		1	92.00	0.70		64.40			
	3rd Cross Rd	1	190.00	0.70		133.00			
	Sri Sai Layout								
	Cross Rd 1-to Cross Rd-2	1	272.50	5.80		1580.50			
	Cross Rd-3	1	16.00	6.30		100.80			
						31872.27	**Sqm**	**48.40**	**1542617.87**
15	Providing and applying **tack coat** with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom.(V-III, P.No-29,I No-5.3(i) of PWD SR 2021-22).								
	Basic Rate	**12.00**							
	Area Weightage 10%	**1.20**							
	Total Rate	**13.20**							
	Asphalt Road								
	For Profile correction								
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	7.00		2401.00			
	1st Cross rd	1	64.00	7.00		448.00			
	2nd Cross rd	1	64.00	7.10		454.40			
	3rd Cross rd	1	65.00	7.00		455.00			
	4th Cross rd	1	65.00	6.20		403.00			
	5th Cross rd	1	65.00	6.40		416.00			
	6th Cross rd	1	65.00	6.70		435.50			
	7th Cross rd	1	65.00	6.70		435.50			
	3rd Cross Rd	1	323.00	6.50		2099.50			
	Attur Village								

Providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2 coarse sand : 4 graded

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Attur Village Rd								
	Veerasagara	1	118.00	6.60		778.80			
	3rd Cross Rd								
	6th A Cross Rd	1	148.00	5.00		740.00			
	6th Cross Rd	1	65.00	4.80		312.00			
	8th Main Cross Rd-2	1	57.00	4.70		267.90			
	6th B Cross Rd	1	93.00	5.10		474.30			
	4th A Cross Rd	1	104.00	5.30		551.20			
	4th B Cross Rd	1	22.50	4.40		99.00			
	4th C Cross Rd	1	22.50	4.00		90.00			
	5thA Cross Rd	1	22.50	4.10		92.25			
	Chitra Layout [Harshitha Nilaya]	1	130.00	4.40		572.00			
	6th Cross Rd	1	94.00	5.90		554.60			
	9th Main rd	1	134.00	5.60		750.40			
	10th Main rd	1	99.00	5.50		544.50			
	11th Main Rd	1	43.00	5.70		245.10			
	Chitra Layout 3rd Cross Rd	1	54.50	5.80		316.10			
	Muneshwara Layout	1	64.00	5.10		326.40			
	1st Cross Rd								
	2nd Cross Rd	1	45.00	5.00		225.00			
	3rd Cross Rd	1	45.50	5.10		232.05			
	4th Cross Rd	1	46.00	4.70		216.20			
	5th Cross Rd	1	45.00	4.60		207.00			
	7th Cross Rd	1	45.00	4.70		211.50			
	9th Cross Rd Left Side	1	96.00	4.00		384.00			
	9th Cross Rd Right Side	1	99.00	6.00		594.00			
	10th Cross Rd Left Side	1	170.00	5.60		952.00			
	10th Cross Rd Right Side	1	44.00	5.40		237.60			
	11th Cross Rd	1	170.00	5.60		952.00			
	1st Main Rd	1	48.00	5.80		278.40			
	1st Cross Rd	1	122.00	5.90		719.80			
	6th Cross 1st Cross Rd	1	102.00	5.20		530.40			
	6th Cross 2nd Cross Rd	1	28.00	5.20		145.60			
	6th Cross 3rd Cross Rd	1	25.00	4.60		115.00			
	6th Cross 4th Cross Rd	1	23.00	5.10		117.30			
	5th Cross Rd	1	23.00	4.80		110.40			
	4th Cross Rd	1	270.00	5.60		1512.00			
		1	85.00	5.00		425.00			
		1	92.00	5.30		487.60			
	3rd Cross Rd	1	190.00	5.90		1121.00			
						24036.30			
	Cnsider 20%					4807.26			
	For BC								
	Ward No-04								
	B-Sector								
	4th B cross Rd	1	20.00	6.00		120.00			
	7th B Cross Rd	1	139.00	6.30		875.70			
	6th B Main Rd	1	40.00	5.80		232.00			

Providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2 coarse sand : 4 graded

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	7th B main Rd	1	40.00	6.60		264.00			
	9th Cross Rd	1	50.00	5.10		255.00			
	Attur Layout								
	Attur Main Rd	1	72.00	4.30		309.60			
	2nd Main Rd Continue	1	53.00	3.90		206.70			
	2nd Main Rd Continue	1	73.00	4.80		350.40			
	2nd Main Rd Continue	1	73.00	4.70		343.10			
	2nd Main Rd Continue	1	69.00	5.00		345.00			
	3rd Main Rd	1	75.00	4.50		337.50			
	3rd Main Rd Continue	1	74.00	4.20		310.80			
	3rd Main Rd Continue	1	55.00	4.00		220.00			
	3rd Main Rd Continue	1	73.50	4.60		338.10			
	4th Main Rd	1	72.00	4.40		316.80			
	4th Main Rd Continue	1	55.00	4.20		231.00			
	4th Main Rd Continue	1	75.00	4.20		315.00			
	4th Main Rd Continue	1	76.00	5.00		380.00			
	5th Main Rd	1	47.00	4.60		216.20			
	5th Main Rd Continue	1	73.00	5.60		408.80			
	5th Main Rd Continue	1	72.00	5.00		360.00			
	5th Main Rd Continue	1	57.00	4.90		279.30			
	5th Main Rd Continue	1	72.00	5.40		388.80			
	6th Main Rd	1	67.00	4.00		268.00			
	6th Main Rd Continue	1	57.00	4.40		250.80			
	6th Main Rd Continue	1	73.00	4.40		321.20			
	6th Main Rd Continue	1	75.00	4.30		322.50			
	6th Main Rd Continue	1	47.00	3.60		169.20			
	7th Main Rd	1	46.00	4.40		202.40			
	7th Main Rd Continue	1	75.00	4.30		322.50			
	7th Main Rd Continue	1	73.00	5.00		365.00			
	7th Main Rd Continue	1	67.00	4.50		301.50			
	7th Main Rd Continue	1	68.00	4.70		319.60			
	8th Main Rd	1	65.00	5.80		377.00			
	8th Main Rd Continue	1	56.00	5.00		280.00			
	8th Main Rd Continue	1	74.00	5.00		370.00			
	8th Main Rd Continue	1	73.00	4.90		357.70			
	5th Cross Rd	1	45.00	4.50		202.50			
	10th Main Rd	1	219.00	4.60		1007.40			
	11th Main Rd	1	212.00	4.00		848.00			
	1st Cross Rd	1	261.00	6.80		1774.80			
	2nd Cross Rd	1	270.00	6.50		1755.00			
	3rd Cross Rd	1	287.00	6.50		1865.50			
	4th Cross Rd	1	265.00	6.80		1802.00			
	Escorts Colony								
	1st Cross Rd	1	210.00	7.10		1491.00			
	6th C Cross Rd	1	126.00	4.00		504.00			
	6th B Cross Rd	1	113.00	4.00		452.00			
	4th A Main Rd	1	139.00	6.80		945.20			
	6th A Main Rd	1	156.00	4.40		686.40			



Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th B Main Rd	1	53.00	4.40		233.20			
	7th A Main Rd	1	239.00	5.20		1242.80			
	Akshay Nagara								
	Main Road [From Sandeep Unnikrishan Rd]	1	343.00	7.00		2401.00			
	1st Cross rd	1	64.00	7.00		448.00			
	2nd Cross rd	1	64.00	7.10		454.40			
	3rd Cross rd	1	65.00	7.00		455.00			
	4th Cross rd	1	65.00	6.20		403.00			
	5th Cross rd	1	65.00	6.40		416.00			
	6th Cross rd	1	65.00	6.70		435.50			
	7th Cross rd	1	65.00	6.70		435.50			
	3rd Cross Rd	1	323.00	6.50		2099.50			
	Attur Village								
	Attur Villagae Rd	1	118.00	6.60		778.80			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	6.90		2166.60			
	1st Cross Rd	1	37.00	7.00		259.00			
	Santhosh nagara								
	Connecting RD-1	1	26.00	4.00		104.00			
	Connecting RD-2	1	44.00	4.00		176.00			
	Tharman Sharma Rd	1	33.00	4.00		132.00			
	9th B Cross Rd	1	36.00	4.00		144.00			
	7th Cross rd	1	174.00	4.20		730.80			
	1st Cross Rd	1	37.00	4.40		162.80			
	6th Cross Rd	1	429.00	5.60		2402.40			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	5.30		100.70			
	Varaha Entreprises Rd	1	22.00	5.10		112.20			
	Cross Rd-6	1	23.00	4.80		110.40			
	Sri Lasya Rd	1	25.00	4.80		120.00			
	Health Care Home Rd	1	125.00	5.80		725.00			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	4.00		172.00			
	Cross Rd-5	1	24.00	4.20		100.80			
	White Petal School Rd	1	19.00	3.80		72.20			
	Cross Rd-2	1	19.00	4.50		85.50			
	Cross Rd-1	1	65.00	5.10		331.50			
	4th Cross rd	1	149.00	5.10		759.90			
	2nd Cross Rd	1	161.00	4.50		724.50			
	Ramadasappa Garden1st Cross rd	1	166.00	5.50		913.00			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	5.00		740.00			
	6th A Cross Rd	1	65.00	4.80		312.00			
	6th Cross Rd	1	57.00	4.70		267.90			
	8th Main Cross Rd-2	1	93.00	5.10		474.30			
	6th B Cross Rd	1	104.00	5.30		551.20			

providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2 coarse sand : 4 graded

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th A Cross Rd	1	22.50	4.40		99.00			
	4th B Cross Rd	1	22.50	4.00		90.00			
	4th C Cross Rd	1	22.50	4.10		92.25			
	5thA Cross Rd	1	130.00	4.40		572.00			
	Chitra Layout [Harshitha Nilaya]	1	94.00	5.90		554.60			
	6th Cross Rd	1	134.00	5.60		750.40			
	9th Main rd	1	99.00	5.50		544.50			
	10th Main rd	1	43.00	5.70		245.10			
	11th Main Rd	1	54.50	5.80		316.10			
	Chitra Layout 3rd Cross Rd	1	64.00	5.10		326.40			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	5.00		225.00			
	2nd Cross Rd	1	45.50	5.10		232.05			
	3rd Cross Rd	1	46.00	4.70		216.20			
	4th Cross Rd	1	45.00	4.60		207.00			
	5th Cross Rd	1	45.00	4.70		211.50			
	7th Cross Rd	1	96.00	4.00		384.00			
	9th Cross Rd Left Side	1	99.00	6.00		594.00			
	9th Cross Rd Right Side	1	170.00	5.60		952.00			
	10th Cross Rd Left Side	1	44.00	5.40		237.60			
	10th Cross Rd Right Side	1	170.00	5.60		952.00			
	11th Cross Rd	1	48.00	5.80		278.40			
	1st Main Rd	1	122.00	5.90		719.80			
	1st Cross Rd	1	102.00	5.20		530.40			
	6th Cross 1st Cross Rd	1	28.00	5.20		145.60			
	6th Cross 2nd Cross Rd	1	25.00	4.60		115.00			
	6th Cross 3rd Cross Rd	1	23.00	5.10		117.30			
	6th Cross 4th Cross Rd	1	23.00	4.80		110.40			
	5th Cross Rd	1	270.00	5.60		1512.00			
	4th Cross Rd	1	85.00	5.00		425.00			
		1	92.00	5.30		487.60			
	3rd Cross Rd	1	190.00	5.90		1121.00			
	Sri Sai Layout								
	Cross Rd 1-to Cross Rd-2	1	272.50	5.80		1580.50			
	Cross Rd-3	1	16.00	6.30		100.80			
	Cut Portion								
	Attur Layout								
	Attur Village Main Rd	1	72.00	1.10		79.20			
	2nd Main Rd Continue	1	53.00	1.10		58.30			
	2nd Main Rd Continue	1	73.00	1.10		80.30			
	2nd Main Rd Continue	1	73.00	1.20		87.60			
	2nd Main Rd Continue	1	69.00	1.00		69.00			
	3rd Main Rd	1	75.00	1.10		82.50			
	3rd Main Rd Continue	1	74.00	1.10		81.40			
	3rd Main Rd Continue	1	55.00	1.10		60.50			
	3rd Main Rd Continue	1	73.50	1.10		80.85			

providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2 coarse sand : 4 graded

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th Main Rd	1	72.00	1.20		86.40			
	4th Main Rd Continue	1	55.00	1.20		66.00			
	4th Main Rd Continue	1	75.00	1.20		90.00			
	5th Main Rd	1	76.00	1.20		91.20			
	5th Main Rd Continue	1	47.00	1.00		47.00			
	5th Main Rd Continue	1	73.00	1.00		73.00			
	5th Main Rd Continue	1	72.00	1.00		72.00			
	5th Main Rd Continue	1	57.00	1.00		57.00			
	6th Main Rd	1	72.00	1.00		72.00			
	6th Main Rd Continue	1	67.00	1.10		73.70			
	6th Main Rd Continue	1	57.00	1.10		62.70			
	6th Main Rd Continue	1	73.00	1.10		80.30			
	6th Main Rd Continue	1	75.00	1.10		82.50			
	6th Main Rd Continue	1	47.00	1.10		51.70			
	7th Main Rd	1	46.00	1.10		50.60			
	7th Main Rd Continue	1	75.00	1.10		82.50			
	7th Main Rd Continue	1	73.00	1.10		80.30			
	7th Main Rd Continue	1	67.00	1.10		73.70			
	7th Main Rd Continue	1	68.00	1.10		74.80			
	8th Main Rd	1	65.00	1.00		65.00			
	8th Main Rd Continue	1	56.00	1.00		56.00			
	8th Main Rd Continue	1	74.00	1.00		74.00			
	8th Main Rd Continue	1	73.00	1.00		73.00			
	5th Cross Rd	1	45.00	1.00		45.00			
	10th Main Rd	1	219.00	1.00		219.00			
	11th Main Rd	1	212.00	1.00		212.00			
	1st Cross Rd	1	261.00	1.00		261.00			
	2nd Cross Rd	1	270.00	1.00		270.00			
	3rd Cross Rd	1	287.00	1.00		287.00			
	4th Cross Rd	1	265.00	1.00		265.00			
	Escorts Colony								
	1st Cross Rd	1	210.00	7.10		1491.00			
	6th C Cross Rd	1	126.00	4.00		504.00			
	6th B Cross Rd	1	113.00	4.00		452.00			
	4th A Main Rd	1	139.00	6.80		945.20			
	6th A Main Rd	1	156.00	4.40		686.40			
	7th A Main Rd	1	239.00	5.20		1242.80			
						76766.61	**Sqm**	**13.20**	**1013319.25**
16	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects. (V-III, P.No-33,I No-5.12C of PWD SR 2021-22).								
	Basic Rate	**9889.00**							
	Area Weightage 10%	**988.90**							
	Total Rate	**10877.90**							
	Asphalt Road								
	For Profile correction								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Ward No-04								
	B-Sector								
	4th B cross Rd	1	20.00	6.00	0.05	6.00			
	7th B Cross Rd	1	139.00	6.30	0.05	43.79			
	6th B Main Rd	1	40.00	5.80	0.05	11.60			
	7th B main Rd	1	40.00	6.60	0.05	13.20			
	9th Cross Rd	1	50.00	5.10	0.05	12.75			
	Attur Layout								
	Attur Village Main Rd	1	72.00	4.30	0.05	15.48			
	2nd Main Rd Continue	1	53.00	3.90	0.05	10.34			
	2nd Main Rd Continue	1	73.00	4.80	0.05	17.52			
	2nd Main Rd Continue	1	73.00	4.70	0.05	17.16			
	2nd Main Rd Continue	1	69.00	5.00	0.05	17.25			
	3rd Main Rd	1	75.00	4.50	0.05	16.88			
	3rd Main Rd Continue	1	74.00	4.20	0.05	15.54			
	3rd Main Rd Continue	1	55.00	4.00	0.05	11.00			
	3rd Main Rd Continue	1	73.50	4.60	0.05	16.91			
	4th Main Rd	1	72.00	4.40	0.05	15.84			
	4th Main Rd Continue	1	55.00	4.20	0.05	11.55			
	4th Main Rd Continue	1	75.00	4.20	0.05	15.75			
	4th Main Rd Continue	1	76.00	5.00	0.05	19.00			
	5th Main Rd	1	47.00	4.60	0.05	10.81			
	5th Main Rd Continue	1	73.00	5.60	0.05	20.44			
	5th Main Rd Continue	1	72.00	5.00	0.05	18.00			
	5th Main Rd Continue	1	57.00	4.90	0.05	13.97			
	5th Main Rd Continue	1	72.00	5.40	0.05	19.44			
	6th Main Rd	1	67.00	4.00	0.05	13.40			
	6th Main Rd Continue	1	57.00	4.40	0.05	12.54			
	6th Main Rd Continue	1	73.00	4.40	0.05	16.06			
	6th Main Rd Continue	1	75.00	4.30	0.05	16.13			
	6th Main Rd Continue	1	47.00	3.60	0.05	8.46			
	7th Main Rd	1	46.00	4.40	0.05	10.12			
	7th Main Rd Continue	1	75.00	4.30	0.05	16.13			
	7th Main Rd Continue	1	73.00	5.00	0.05	18.25			
	7th Main Rd Continue	1	67.00	4.50	0.05	15.08			
	7th Main Rd Continue	1	68.00	4.70	0.05	15.98			
	8th Main Rd	1	65.00	5.80	0.05	18.85			
	8th Main Rd Continue	1	56.00	5.00	0.05	14.00			
	8th Main Rd Continue	1	74.00	5.00	0.05	18.50			
	8th Main Rd Continue	1	73.00	4.90	0.05	17.89			
	5th Cross Rd	1	45.00	4.50	0.05	10.13			
	10th Main Rd	1	219.00	4.60	0.05	50.37			
	11th Main Rd	1	212.00	4.00	0.05	42.40			
	1st Cross Rd	1	261.00	6.80	0.05	88.74			
	2nd Cross Rd	1	270.00	6.50	0.05	87.75			
	3rd Cross Rd	1	287.00	6.50	0.05	93.28			
	4th Cross Rd	1	265.00	6.80	0.05	90.10			
	Akshay Nagara Main Road	1	343.00	7.00	0.05	120.05			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Cross rd	1	64.00	7.00	0.05	22.40			
	2nd Cross rd	1	64.00	7.10	0.05	22.72			
	3rd Cross rd	1	65.00	7.00	0.05	22.75			
	4th Cross rd	1	65.00	6.20	0.05	20.15			
	5th Cross rd	1	65.00	6.40	0.05	20.80			
	6th Cross rd	1	65.00	6.70	0.05	21.78			
	7th Cross rd	1	65.00	6.70	0.05	21.78			
	3rd Cross Rd	1	323.00	6.50	0.05	104.98			
	Attur Village								
	Attur Village Rd	1	118.00	6.60	0.05	38.94			
	Santhosh nagara								
	Connecting RD-1	1	26.00	4.00	0.05	5.20			
	Connecting RD-2	1	44.00	4.00	0.05	8.80			
	Tharman Sharma Rd	1	33.00	4.00	0.05	6.60			
	9th B Cross Rd	1	36.00	4.00	0.05	7.20			
	7th Cross rd	1	174.00	4.20	0.05	36.54			
	1st Cross Rd	1	37.00	4.40	0.05	8.14			
	6th Cross Rd	1	429.00	5.60	0.05	120.12			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	5.30	0.05	5.04			
	Varaha Entreprises Rd	1	22.00	5.10	0.05	5.61			
	Cross Rd-6	1	23.00	4.80	0.05	5.52			
	Sri Lasya Rd	1	25.00	4.80	0.05	6.00			
	Health Care Home Rd	1	125.00	5.80	0.05	36.25			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	4.00	0.05	8.60			
	Cross Rd-5	1	24.00	4.20	0.05	5.04			
	Cross Rd-C	1	19.00	3.80	0.05	3.61			
	Cross Rd-2	1	19.00	4.50	0.05	4.28			
	Cross Rd-1	1	65.00	5.10	0.05	16.58			
	4th Cross rd	1	149.00	5.10	0.05	38.00			
	2nd Cross Rd	1	161.00	4.50	0.05	36.23			
	Ramadasappa Garden1st Cross rd	1	166.00	5.50	0.05	45.65			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	5.00	0.05	37.00			
	6th A Cross Rd	1	65.00	4.80	0.05	15.60			
	6th Cross Rd	1	57.00	4.70	0.05	13.40			
	8th Main Cross Rd-2	1	93.00	5.10	0.05	23.72			
	6th B Cross Rd	1	104.00	5.30	0.05	27.56			
	4th A Cross Rd	1	22.50	4.40	0.05	4.95			
	4th B Cross Rd	1	22.50	4.00	0.05	4.50			
	4th C Cross Rd	1	22.50	4.10	0.05	4.61			
	5thA Cross Rd	1	130.00	4.40	0.05	28.60			
	Chitra Layout [Harshitha Nilaya]	1	94.00	5.90	0.05	27.73			
	6th Cross Rd	1	134.00	5.60	0.05	37.52			
	9th Main rd	1	99.00	5.50	0.05	27.23			
	10th Main rd	1	43.00	5.70	0.05	12.26			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	11th Main Rd	1	54.50	5.80	0.05	15.81			
	Chitra Layout 3rd Cross Rd	1	64.00	5.10	0.05	16.32			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	5.00	0.05	11.25			
	2nd Cross Rd	1	45.50	5.10	0.05	11.60			
	3rd Cross Rd	1	46.00	4.70	0.05	10.81			
	4th Cross Rd	1	45.00	4.60	0.05	10.35			
	5th Cross Rd	1	45.00	4.70	0.05	10.58			
	7th Cross Rd	1	96.00	4.00	0.05	19.20			
	9th Cross Rd Left Side	1	99.00	6.00	0.05	29.70			
	9th Cross Rd Right Side	1	170.00	5.60	0.05	47.60			
	10th Cross Rd Left Side	1	44.00	5.40	0.05	11.88			
	10th Cross Rd Right Side	1	170.00	5.60	0.05	47.60			
	11th Cross Rd	1	48.00	5.80	0.05	13.92			
	1st Main Rd	1	122.00	5.90	0.05	35.99			
	1st Cross Rd	1	102.00	5.20	0.05	26.52			
	6th Cross 1st Cross Rd	1	28.00	5.20	0.05	7.28			
	6th Cross 2nd Cross Rd	1	25.00	4.60	0.05	5.75			
	6th Cross 3rd Cross Rd	1	23.00	5.10	0.05	5.87			
	6th Cross 4th Cross Rd	1	23.00	4.80	0.05	5.52			
	5th Cross Rd	1	270.00	5.60	0.05	75.60			
	4th Cross Rd	1	85.00	5.00	0.05	21.25			
		1	92.00	5.30	0.05	24.38			
	3rd Cross Rd	1	190.00	5.90	0.05	56.05			
						2655.12			
	Profile correction 20%					**531.02**			
	Edge Correctin/ Damage Portion								
	Ward No-04								
	B-Sector								
	4th B cross Rd	1	20.00	6.00	0.05	6.00			
	7th B Cross Rd	1	139.00	1.50	0.05	10.43			
	6th B Main Rd	1	40.00	1.40	0.05	2.80			
	7th B main Rd	1	40.00	1.90	0.05	3.80			
	9th Cross Rd	1	50.00	1.70	0.05	4.25			
	Attur Layout								
	Attur Village Main Rd	1	72.00	0.90	0.05	3.24			
	2nd Main Rd Continue	1	53.00	1.00	0.05	2.65			
	2nd Main Rd Continue	1	73.00	0.90	0.05	3.29			
	2nd Main Rd Continue	1	73.00	1.00	0.05	3.65			
	2nd Main Rd Continue	1	69.00	0.80	0.05	2.76			
	3rd Main Rd	1	75.00	1.00	0.05	3.75			
	3rd Main Rd Continue	1	74.00	1.10	0.05	4.07			
	3rd Main Rd Continue	1	55.00	1.05	0.05	2.89			
	3rd Main Rd Continue	1	73.50	0.80	0.05	2.94			
	4th Main Rd	1	72.00	0.90	0.05	3.24			
	4th Main Rd Continue	1	55.00	0.90	0.05	2.48			

Providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th Main Rd Continue	1	75.00	0.80	0.05	3.00			
	4th Main Rd Continue	1	76.00	0.70	0.05	2.66			
	5th Main Rd	1	47.00	0.80	0.05	1.88			
	5th Main Rd Continue	1	73.00	0.90	0.05	3.29			
	5th Main Rd Continue	1	72.00	0.75	0.05	2.70			
	5th Main Rd Continue	1	87.00	0.80	0.05	3.48			
	6th Main Rd	1	72.00	0.75	0.05	2.70			
	6th Main Rd Continue	1	67.00	0.90	0.05	3.02			
	6th Main Rd Continue	1	87.00	0.80	0.05	3.48			
	6th Main Rd Continue	1	73.00	0.80	0.05	2.92			
	6th Main Rd Continue	1	78.00	0.90	0.05	3.38			
	7th Main Rd	1	47.00	0.75	0.05	1.76			
	7th Main Rd Continue	1	46.00	0.90	0.05	2.07			
	7th Main Rd Continue	1	75.00	0.90	0.05	3.38			
	7th Main Rd Continue	1	73.00	0.80	0.05	2.92			
	7th Main Rd Continue	1	67.00	0.80	0.05	2.68			
	8th Main Rd	1	68.00	0.80	0.05	2.72			
	8th Main Rd Continue	1	65.00	0.90	0.05	2.93			
	8th Main Rd Continue	1	56.00	0.90	0.05	2.52			
	8th Main Rd Continue	1	74.00	0.90	0.05	3.33			
	5th Cross Rd	1	73.00	0.90	0.05	3.29			
	10th Main Rd	1	45.00	0.90	0.05	2.03			
	11th Main Rd	1	219.00	0.90	0.05	9.86			
	1st Cross Rd	1	212.00	0.90	0.05	9.54			
	2nd Cross Rd	1	261.00	0.90	0.05	11.75			
	3rd Cross Rd	1	270.00	0.90	0.05	12.15			
	4th Cross Rd	1	287.00	0.90	0.05	12.92			
	Akshay Nagara	1	265.00	0.90	0.05	11.93			
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	0.90	0.05	15.44			
	1st Cross rd	1	64.00	0.90	0.05	2.88			
	2nd Cross rd	1	64.00	0.90	0.05	2.88			
	3rd Cross rd	1	65.00	0.90	0.05	2.93			
	4th Cross rd	1	65.00	0.90	0.05	2.93			
	5th Cross rd	1	65.00	0.90	0.05	2.93			
	6th Cross rd	1	65.00	0.90	0.05	2.93			
	7th Cross rd	1	65.00	0.90	0.05	2.93			
	3rd Cross Rd	1	323.00	0.90	0.05	14.54			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	6.90	0.05	108.33			
	1st Cross Rd	1	37.00	7.00	0.05	12.95			
	Santhosh nagara								
	Connecting RD-1	1	26.00	0.60	0.05	0.78			
	Connecting RD-2	1	44.00	0.60	0.05	1.32			
	Tharman Sharma Rd	1	33.00	0.60	0.05	0.99			
	9th B Cross Rd	1	36.00	0.60	0.05	1.08			
	7th Cross rd	1	174.00	0.60	0.05	5.22			

7 Providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2 coarse sand : 4 graded

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Cross Rd	1	37.00	0.60	0.05	1.11			
	6th Cross Rd	1	429.00	1.60	0.05	34.32			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	0.60	0.05	0.57			
	Varaha Entreprises Rd	1	22.00	0.70	0.05	0.77			
	Cross Rd-6	1	23.00	0.70	0.05	0.81			
	Sri Lasya Rd	1	25.00	0.70	0.05	0.88			
	Health Care Home Rd	1	125.00	0.70	0.05	4.38			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	0.50	0.05	1.08			
	Cross Rd-5	1	24.00	0.50	0.05	0.60			
	White Petal School Rd	1	19.00	0.50	0.05	0.48			
	Cross Rd-2	1	19.00	0.50	0.05	0.48			
	Cross Rd-1	1	65.00	0.50	0.05	1.63			
	4th Cross rd	1	149.00	1.40	0.05	10.43			
	2nd Cross Rd	1	161.00	1.40	0.05	11.27			
	Ramadasappa Garden1st Cross rd	1	166.00	1.35	0.05	11.21			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	1.50	0.05	11.10			
	6th A Cross Rd	1	65.00	1.30	0.05	4.23			
	6th Cross Rd	1	57.00	1.20	0.05	3.42			
	8th Main Cross Rd-2	1	93.00	1.10	0.05	5.12			
	6th B Cross Rd	1	104.00	1.30	0.05	6.76			
	4th A Cross Rd	1	22.50	1.00	0.05	1.13			
	4th B Cross Rd	1	22.50	1.00	0.05	1.13			
	4th C Cross Rd	1	22.50	1.10	0.05	1.24			
	5thA Cross Rd	1	130.00	1.30	0.05	8.45			
	Chitra Layout [Harshitha Nilaya]	1	94.00	1.40	0.05	6.58			
	6th Cross Rd	1	134.00	1.50	0.05	10.05			
	9th Main rd	1	99.00	1.30	0.05	6.44			
	10th Main rd	1	43.00	1.20	0.05	2.58			
	11th Main Rd	1	54.50	1.20	0.05	3.27			
	Chitra Layout 3rd Cross Rd	1	64.00	1.30	0.05	4.16			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	1.20	0.05	2.70			
	2nd Cross Rd	1	45.50	1.20	0.05	2.73			
	3rd Cross Rd	1	46.00	1.00	0.05	2.30			
	4th Cross Rd	1	45.00	1.10	0.05	2.48			
	5th Cross Rd	1	45.00	1.30	0.05	2.93			
	7th Cross Rd	1	96.00	1.40	0.05	6.72			
	9th Cross Rd Left Side	1	99.00	1.30	0.05	6.44			
	9th Cross Rd Right Side	1	170.00	1.40	0.05	11.90			
	10th Cross Rd Left Side	1	44.00	1.10	0.05	2.42			
	10th Cross Rd Right Side	1	170.00	1.10	0.05	9.35			
	11th Cross Rd	1	48.00	5.80	0.05	13.92			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Main Rd	1	122.00	1.10	0.05	6.71			
	1st Cross Rd	1	102.00	1.30	0.05	6.63			
	6th Cross 1st Cross Rd	1	28.00	1.00	0.05	1.40			
	6th Cross 2nd Cross Rd	1	25.00	0.90	0.05	1.13			
	6th Cross 3rd Cross Rd	1	23.00	0.90	0.05	1.04			
	6th Cross 4th Cross Rd	1	23.00	0.90	0.05	1.04			
	5th Cross Rd	1	270.00	1.60	0.05	21.60			
	4th Cross Rd	1	85.00	1.30	0.05	5.53			
		1	92.00	1.30	0.05	5.98			
	3rd Cross Rd	1	190.00	1.50	0.05	14.25			
	Cut Portion								
	Attur Layout								
	Attur Village Main Rd	1	72.00	1.10	0.05	3.96			
	2nd Main Rd Continue	1	53.00	1.10	0.05	2.92			
	2nd Main Rd Continue	1	73.00	1.10	0.05	4.02			
	2nd Main Rd Continue	1	73.00	1.20	0.05	4.38			
	2nd Main Rd Continue	1	69.00	1.00	0.05	3.45			
	3rd Main Rd	1	75.00	1.10	0.05	4.13			
	3rd Main Rd Continue	1	74.00	1.10	0.05	4.07			
	3rd Main Rd Continue	1	55.00	1.10	0.05	3.03			
	3rd Main Rd Continue	1	73.50	1.10	0.05	4.04			
	4th Main Rd	1	72.00	1.20	0.05	4.32			
	4th Main Rd Continue	1	55.00	1.20	0.05	3.30			
	4th Main Rd Continue	1	75.00	1.20	0.05	4.50			
	4th Main Rd Continue	1	76.00	1.20	0.05	4.56			
	5th Main Rd	1	47.00	1.00	0.05	2.35			
	5th Main Rd Continue	1	73.00	1.00	0.05	3.65			
	5th Main Rd Continue	1	72.00	1.00	0.05	3.60			
	5th Main Rd Continue	1	57.00	1.00	0.05	2.85			
	5th Main Rd Continue	1	72.00	1.00	0.05	3.60			
	6th Main Rd	1	67.00	1.10	0.05	3.69			
	6th Main Rd Continue	1	57.00	1.10	0.05	3.14			
	6th Main Rd Continue	1	73.00	1.10	0.05	4.02			
	6th Main Rd Continue	1	75.00	1.10	0.05	4.13			
	6th Main Rd Continue	1	47.00	1.10	0.05	2.59			
	7th Main Rd	1	46.00	1.10	0.05	2.53			
	7th Main Rd Continue	1	75.00	1.10	0.05	4.13			
	7th Main Rd Continue	1	73.00	1.10	0.05	4.02			
	7th Main Rd Continue	1	67.00	1.10	0.05	3.69			
	7th Main Rd Continue	1	68.00	1.10	0.05	3.74			
	8th Main Rd	1	65.00	1.00	0.05	3.25			
	8th Main Rd Continue	1	56.00	1.00	0.05	2.80			
	8th Main Rd Continue	1	74.00	1.00	0.05	3.70			
	8th Main Rd Continue	1	73.00	1.00	0.05	3.65			
	5th Cross Rd	1	45.00	1.00	0.05	2.25			
	10th Main Rd	1	219.00	1.00	0.05	10.95			
	11th Main Rd	1	212.00	1.00	0.05	10.60			
	1st Cross Rd	1	261.00	1.00	0.05	13.05			
	2nd Cross Rd	1	270.00	1.00	0.05	13.50			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd Cross Rd	1	287.00	1.00	0.05	14.35			
	4th Cross Rd	1	265.00	1.00	0.05	13.25			
	Escorts Colony								
	1st Cross Rd	1	210.00	7.10	0.05	74.55			
	6th C Cross Rd	1	126.00	4.00	0.05	25.20			
	6th B Cross Rd	1	113.00	4.00	0.05	22.60			
	4th A Main Rd	1	139.00	6.80	0.05	47.26			
	6th A Main Rd	1	156.00	4.40	0.05	34.32			
	7th A Main Rd	1	239.00	5.20	0.05	62.14			
	Akshay Nagara								
	Main Road[From Sandeep Unnikrishan Rd]	1	343.00	1.10	0.05	18.87			
	1st Cross rd	1	64.00	1.10	0.05	3.52			
	2nd Cross rd	1	64.00	1.20	0.05	3.84			
	3rd Cross rd	1	65.00	1.00	0.05	3.25			
	4th Cross rd	1	65.00	1.10	0.05	3.58			
	5th Cross rd	1	65.00	1.10	0.05	3.58			
	6th Cross rd	1	65.00	1.00	0.05	3.25			
	7th Cross rd	1	65.00	1.20	0.05	3.90			
	3rd Cross Rd	1	323.00	1.00	0.05	16.15			
	Attur Village								
	Attur Villagae Rd	1	118.00	6.60	0.05	38.94			
	Santhosh nagara								
	Connecting RD-1	1	26.00	1.00	0.05	1.30			
	Connecting RD-2	1	44.00	1.00	0.05	2.20			
	Tharman Sharma Rd	1	33.00	1.00	0.05	1.65			
	9th B Cross Rd	1	36.00	1.00	0.05	1.80			
	7th Cross rd	1	174.00	1.00	0.05	8.70			
	1st Cross Rd	1	37.00	1.00	0.05	1.85			
	6th Cross Rd	1	429.00	1.00	0.05	21.45			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	1.10	0.05	1.05			
	Varaha Entreprises Rd	1	22.00	1.20	0.05	1.32			
	Cross Rd-6	1	23.00	1.00	0.05	1.15			
	Sri Lasya Rd	1	25.00	1.10	0.05	1.38			
	Health Care Home Rd	1	125.00	1.20	0.05	7.50			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	1.10	0.05	2.37			
	Cross Rd-5	1	24.00	1.10	0.05	1.32			
	Cross Rd-C	1	19.00	1.10	0.05	1.05			
	Cross Rd-2	1	19.00	1.10	0.05	1.05			
	Cross Rd-1	1	65.00	1.10	0.05	3.58			
	4th Cross rd	1	149.00	1.10	0.05	8.20			
	2nd Cross Rd	1	161.00	1.10	0.05	8.86			
	Ramadasappa Garden1st Cross rd	1	166.00	1.10	0.05	9.13			
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	0.70	0.05	5.18			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	6th A Cross Rd	1	65.00	0.80	0.05	2.60			
	6th Cross Rd	1	57.00	0.90	0.05	2.57			
	8th Main Cross Rd-2	1	93.00	0.90	0.05	4.19			
	6th B Cross Rd	1	104.00	0.90	0.05	4.68			
	4th A Cross Rd	1	22.50	0.90	0.05	1.01			
	4th B Cross Rd	1	22.50	0.90	0.05	1.01			
	4th C Cross Rd	1	22.50	0.90	0.05	1.01			
	5thA Cross Rd	1	130.00	0.90	0.05	5.85			
	Chitra Layout [Harshitha Nilaya]	1	94.00	0.90	0.05	4.23			
	6th Cross Rd	1	134.00	0.90	0.05	6.03			
	9th Main rd	1	99.00	0.80	0.05	3.96			
	10th Main rd	1	43.00	0.80	0.05	1.72			
	11th Main Rd	1	54.50	0.80	0.05	2.18			
	Chitra Layout 3rd Cross Rd	1	64.00	0.80	0.05	2.56			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	0.80	0.05	1.80			
	2nd Cross Rd	1	45.50	0.80	0.05	1.82			
	3rd Cross Rd	1	46.00	0.80	0.05	1.84			
	4th Cross Rd	1	45.00	0.80	0.05	1.80			
	5th Cross Rd	1	45.00	0.80	0.05	1.80			
	7th Cross Rd	1	96.00	0.80	0.05	3.84			
	9th Cross Rd Left Side	1	99.00	0.80	0.05	3.96			
	9th Cross Rd Right Side	1	170.00	0.90	0.05	7.65			
	10th Cross Rd Left Side	1	44.00	0.90	0.05	1.98			
	10th Cross Rd Right Side	1	170.00	0.90	0.05	7.65			
	11th Cross Rd	1	48.00	0.90	0.05	2.16			
	1st Main Rd	1	122.00	0.90	0.05	5.49			
	1st Cross Rd	1	102.00	0.90	0.05	4.59			
	6th Cross 1st Cross Rd	1	28.00	0.90	0.05	1.26			
	6th Cross 2nd Cross Rd	1	25.00	0.90	0.05	1.13			
	6th Cross 3rd Cross Rd	1	23.00	0.90	0.05	1.04			
	6th Cross 4th Cross Rd	1	23.00	0.90	0.05	1.04			
	5th Cross Rd	1	270.00	0.90	0.05	12.15			
	4th Cross Rd	1	85.00	0.70	0.05	2.98			
		1	92.00	0.70	0.05	3.22			
	3rd Cross Rd	1	190.00	0.70	0.05	6.65			
	Sri Sai Layout								
	Cross Rd 1-to Cross Rd-2	1	272.50	5.80	0.05	79.03			
	Cross Rd-3	1	16.00	6.30	0.05	5.04			
						2041.07	**Cum**	**10877.90**	**22202517.28**
17	Providing and laying **Bituminous Concrete with 40/60 TPH** capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects (V-III, P.No.36, I.No.5.16C of PWD SR 2021-22).								
	Basic Rate	**11531.00**							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Area Weightage 10%	1153.10							
	Total Rate	12684.10							
	Asphalt Road								
	For BC								
	Ward No-04								
	B-Sector								
	4th B cross Rd	1	20.00	6.00	0.04	4.80			
	7th B Cross Rd	1	139.00	6.30	0.04	35.03			
	6th B Main Rd	1	40.00	5.80	0.04	9.28			
	7th B main Rd	1	40.00	6.60	0.04	10.56			
	9th Cross Rd	1	50.00	5.10	0.04	10.20			
	Attur Layout								
	Attur Village Main Rd	1	72.00	4.30	0.04	12.38			
	2nd Main Rd Continue	1	53.00	3.90	0.04	8.27			
	2nd Main Rd Continue	1	73.00	4.80	0.04	14.02			
	2nd Main Rd Continue	1	73.00	4.70	0.04	13.72			
	2nd Main Rd Continue	1	69.00	5.00	0.04	13.80			
	3rd Main Rd	1	75.00	4.50	0.04	13.50			
	3rd Main Rd Continue	1	74.00	4.20	0.04	12.43			
	3rd Main Rd Continue	1	55.00	4.00	0.04	8.80			
	3rd Main Rd Continue	1	73.50	4.60	0.04	13.52			
	4th Main Rd	1	72.00	4.40	0.04	12.67			
	4th Main Rd Continue	1	55.00	4.20	0.04	9.24			
	4th Main Rd Continue	1	75.00	4.20	0.04	12.60			
	4th Main Rd Continue	1	76.00	5.00	0.04	15.20			
	5th Main Rd	1	47.00	4.60	0.04	8.65			
	5th Main Rd Continue	1	73.00	5.60	0.04	16.35			
	5th Main Rd Continue	1	72.00	5.00	0.04	14.40			
	5th Main Rd Continue	1	57.00	4.90	0.04	11.17			
	5th Main Rd Continue	1	72.00	5.40	0.04	15.55			
	6th Main Rd	1	67.00	4.00	0.04	10.72			
	6th Main Rd Continue	1	57.00	4.40	0.04	10.03			
	6th Main Rd Continue	1	73.00	4.40	0.04	12.85			
	6th Main Rd Continue	1	75.00	4.30	0.04	12.90			
	6th Main Rd Continue	1	47.00	3.60	0.04	6.77			
	7th Main Rd	1	46.00	4.40	0.04	8.10			
	7th Main Rd Continue	1	75.00	4.30	0.04	12.90			
	7th Main Rd Continue	1	73.00	5.00	0.04	14.60			
	7th Main Rd Continue	1	67.00	4.50	0.04	12.06			
	7th Main Rd Continue	1	68.00	4.70	0.04	12.78			
	8th Main Rd	1	65.00	5.80	0.04	15.08			
	8th Main Rd Continue	1	56.00	5.00	0.04	11.20			
	8th Main Rd Continue	1	74.00	5.00	0.04	14.80			
	8th Main Rd Continue	1	73.00	4.90	0.04	14.31			
	5th Cross Rd	1	45.00	4.50	0.04	8.10			
	10th Main Rd	1	219.00	4.60	0.04	40.30			
	11th Main Rd	1	212.00	4.00	0.04	33.92			
	1st Cross Rd	1	261.00	6.80	0.04	70.99			
	2nd Cross Rd	1	270.00	6.50	0.04	70.20			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd Cross Rd	1	287.00	6.50	0.04	74.62			
	4th Cross Rd	1	265.00	6.80	0.04	72.08			
	Escorts Colony								
	1st Cross Rd	1	210.00	7.10	0.04	59.64			
	6th C Cross Rd	1	126.00	4.00	0.04	20.16			
	6th B Cross Rd	1	113.00	4.00	0.04	18.08			
	4th A Main Rd	1	139.00	6.80	0.04	37.81			
	6th A Main Rd	1	156.00	4.40	0.04	27.46			
	7th A Main Rd	1	239.00	5.20	0.04	49.71			
	Akshay Nagara								
	Main Road [From Sandeep Unnikrishan Rd]	1	343.00	7.00	0.04	96.04			
	1st Cross rd	1	64.00	7.00	0.04	17.92			
	2nd Cross rd	1	64.00	7.10	0.04	18.18			
	3rd Cross rd	1	65.00	7.00	0.04	18.20			
	4th Cross rd	1	65.00	6.20	0.04	16.12			
	5th Cross rd	1	65.00	6.40	0.04	16.64			
	6th Cross rd	1	65.00	6.70	0.04	17.42			
	7th Cross rd	1	65.00	6.70	0.04	17.42			
	3rd Cross Rd	1	323.00	6.50	0.04	83.98			
	Attur Village								
	Attur Villagae Rd	1	118.00	6.60	0.04	31.15			
	Tirumalnagara								
	3rd Cross Rd	1	314.00	6.90	0.04	86.66			
	1st Cross Rd	1	37.00	7.00	0.04	10.36			
	Santhosh nagara								
	Connecting RD-1	1	26.00	4.00	0.04	4.16			
	Connecting RD-2	1	44.00	4.00	0.04	7.04			
	Tharman Sharma Rd	1	33.00	4.00	0.04	5.28			
	9th B Cross Rd	1	36.00	4.00	0.04	5.76			
	7th Cross rd	1	174.00	4.20	0.04	29.23			
	1st Cross Rd	1	37.00	4.40	0.04	6.51			
	6th Cross Rd	1	429.00	5.60	0.04	96.10			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	1	19.00	5.30	0.04	4.03			
	Varaha Entreprises Rd	1	22.00	5.10	0.04	4.49			
	Cross Rd-6	1	23.00	4.80	0.04	4.42			
	Sri Lasya Rd	1	25.00	4.80	0.04	4.80			
	Health Care Home Rd	1	125.00	5.80	0.04	29.00			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	1	43.00	4.00	0.04	6.88			
	Cross Rd-5	1	24.00	4.20	0.04	4.03			
	White Petal School Rd	1	19.00	3.80	0.04	2.89			
	Cross Rd-2	1	19.00	4.50	0.04	3.42			
	Cross Rd-1	1	65.00	5.10	0.04	13.26			
	4th Cross rd	1	149.00	5.10	0.04	30.40			
	2nd Cross Rd	1	161.00	4.50	0.04	28.98			
	Ramadasappa Garden1st Cross rd	1	166.00	5.50	0.04	36.52			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Veerasagara Main Rd								
	3rd Cross Rd	1	148.00	5.00	0.04	29.60			
	6th A Cross Rd	1	65.00	4.80	0.04	12.48			
	6th Cross Rd	1	57.00	4.70	0.04	10.72			
	8th Main Cross Rd-2	1	93.00	5.10	0.04	18.97			
	6th B Cross Rd	1	104.00	5.30	0.04	22.05			
	4th A Cross Rd	1	22.50	4.40	0.04	3.96			
	4th B Cross Rd	1	22.50	4.00	0.04	3.60			
	4th C Cross Rd	1	22.50	4.10	0.04	3.69			
	5thA Cross Rd	1	130.00	4.40	0.04	22.88			
	Chitra Layout [Harshitha Nilaya]	1	94.00	5.90	0.04	22.18			
	6th Cross Rd	1	134.00	5.60	0.04	30.02			
	9th Main rd	1	99.00	5.50	0.04	21.78			
	10th Main rd	1	43.00	5.70	0.04	9.80			
	11th Main Rd	1	54.50	5.80	0.04	12.64			
	Chitra Layout 3rd Cross Rd	1	64.00	5.10	0.04	13.06			
	Muneshwara Layout								
	1st Cross Rd	1	45.00	5.00	0.04	9.00			
	2nd Cross Rd	1	45.50	5.10	0.04	9.28			
	3rd Cross Rd	1	46.00	4.70	0.04	8.65			
	4th Cross Rd	1	45.00	4.60	0.04	8.28			
	5th Cross Rd	1	45.00	4.70	0.04	8.46			
	7th Cross Rd	1	96.00	4.00	0.04	15.36			
	9th Cross Rd Left Side	1	99.00	6.00	0.04	23.76			
	9th Cross Rd Right Side	1	170.00	5.60	0.04	38.08			
	10th Cross Rd Left Side	1	44.00	5.40	0.04	9.50			
	10th Cross Rd Right Side	1	170.00	5.60	0.04	38.08			
	11th Cross Rd	1	48.00	5.80	0.04	11.14			
	1st Main Rd	1	122.00	5.90	0.04	28.79			
	1st Cross Rd	1	102.00	5.20	0.04	21.22			
	6th Cross 1st Cross Rd	1	28.00	5.20	0.04	5.82			
	6th Cross 2nd Cross Rd	1	25.00	4.60	0.04	4.60			
	6th Cross 3rd Cross Rd	1	23.00	5.10	0.04	4.69			
	6th Cross 4th Cross Rd	1	23.00	4.80	0.04	4.42			
	5th Cross Rd	1	270.00	5.60	0.04	60.48			
	4th Cross Rd	1	85.00	5.00	0.04	17.00			
		1	92.00	5.30	0.04	19.50			
	3rd Cross Rd	1	190.00	5.90	0.04	44.84			
	Sri Sai Layout								
	Cross Rd 1-to Cross Rd-2	1	272.50	5.80	0.04	63.22			
	Cross Rd-3	1	16.00	6.30	0.04	4.03			
						2501.23	Cum	12684.10	31725826.07
18	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes.(V-III,I No-8.15, P.No-57 of KPWD SR 2021-22)								
	Basic Rate	478.00							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Area Weightage 10%	47.80							
	Total Rate	525.80							
	Asphalt Road								
	Ward No-04								
	B-Sector								
	4th B cross Rd	2	20.00	0.10		4.00			
	7th B Cross Rd	2	139.00	0.10		27.80			
	6th B Main Rd	2	40.00	0.10		8.00			
	7th B main Rd	2	40.00	0.10		8.00			
	9th Cross Rd	2	50.00	0.10		10.00			
	Attur Layout								
	Attur Village Main Rd	2	72.00	0.10		14.40			
	2nd Main Rd Continue	2	53.00	0.10		10.60			
	2nd Main Rd Continue	2	73.00	0.10		14.60			
	2nd Main Rd Continue	2	73.00	0.10		14.60			
	2nd Main Rd Continue	2	69.00	0.10		13.80			
	3rd Main Rd	2	75.00	0.10		15.00			
	3rd Main Rd Continue	2	74.00	0.10		14.80			
	3rd Main Rd Continue	2	55.00	0.10		11.00			
	3rd Main Rd Continue	2	73.50	0.10		14.70			
	4th Main Rd	2	72.00	0.10		14.40			
	4th Main Rd Continue	2	55.00	0.10		11.00			
	4th Main Rd Continue	2	75.00	0.10		15.00			
	4th Main Rd Continue	2	76.00	0.10		15.20			
	5th Main Rd	2	47.00	0.10		9.40			
	5th Main Rd Continue	2	73.00	0.10		14.60			
	5th Main Rd Continue	2	72.00	0.10		14.40			
	5th Main Rd Continue	2	57.00	0.10		11.40			
	5th Main Rd Continue	2	72.00	0.10		14.40			
	6th Main Rd	2	67.00	0.10		13.40			
	6th Main Rd Continue	2	57.00	0.10		11.40			
	6th Main Rd Continue	2	73.00	0.10		14.60			
	6th Main Rd Continue	2	75.00	0.10		15.00			
	6th Main Rd Continue	2	47.00	0.10		9.40			
	7th Main Rd	2	46.00	0.10		9.20			
	7th Main Rd Continue	2	75.00	0.10		15.00			
	7th Main Rd Continue	2	73.00	0.10		14.60			
	7th Main Rd Continue	2	67.00	0.10		13.40			
	7th Main Rd Continue	2	68.00	0.10		13.60			
	8th Main Rd	2	65.00	0.10		13.00			
	8th Main Rd Continue	2	56.00	0.10		11.20			
	8th Main Rd Continue	2	74.00	0.10		14.80			
	8th Main Rd Continue	2	73.00	0.10		14.60			
	5th Cross Rd	2	45.00	0.10		9.00			
	10th Main Rd	2	219.00	0.10		43.80			
	11th Main Rd	2	212.00	0.10		42.40			
	1st Cross Rd	2	261.00	0.10		52.20			
	2nd Cross Rd	2	270.00	0.10		54.00			
	3rd Cross Rd	2	287.00	0.10		57.40			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th Cross Rd	2	265.00	0.10		53.00			
	Escorts Colony								
	1st Cross Rd	2	210.00	0.10		42.00			
	6th C Cross Rd	2	126.00	0.10		25.20			
	6th B Cross Rd	2	113.00	0.10		22.60			
	4th A Main Rd	2	139.00	0.10		27.80			
	6th A Main Rd	2	156.00	0.10		31.20			
	7th A Main Rd	2	239.00	0.10		47.80			
	Akshay Nagara								
	Main Road [From Sandeep Unnikrishan Rd]	2	343.00	0.10		68.60			
	1st Cross rd	2	64.00	0.10		12.80			
	2nd Cross rd	2	64.00	0.10		12.80			
	3rd Cross rd	2	65.00	0.10		13.00			
	4th Cross rd	2	65.00	0.10		13.00			
	5th Cross rd	2	65.00	0.10		13.00			
	6th Cross rd	2	65.00	0.10		13.00			
	7th Cross rd	2	65.00	0.10		13.00			
	3rd Cross Rd	2	323.00	0.10		64.60			
	Attur Village								
	Attur Villagae Rd	2	118.00	0.10		23.60			
	Tirumalnagara								
	3rd Cross Rd	2	314.00	0.10		62.80			
	1st Cross Rd	2	37.00	0.10		7.40			
	Santhosh nagara								
	Connecting RD-1	2	26.00	0.10		5.20			
	Connecting RD-2	2	44.00	0.10		8.80			
	Tharman Sharma Rd	2	33.00	0.10		6.60			
	9th B Cross Rd	2	36.00	0.10		7.20			
	7th Cross rd	2	174.00	0.10		34.80			
	1st Cross Rd	2	37.00	0.10		7.40			
	6th Cross Rd	2	429.00	0.10		85.80			
	6th Cross Rd Left Side Roads								
	manjunatha Nilaya Rd	2	19.00	0.10		3.80			
	Varaha Entreprises Rd	2	22.00	0.10		4.40			
	Cross Rd-6	2	23.00	0.10		4.60			
	Sri Lasya Rd	2	25.00	0.10		5.00			
	Health Care Home Rd	2	125.00	0.10		25.00			
	6th Cross Rd Right Side Roads								
	Cross Rd-4	2	43.00	0.10		8.60			
	Cross Rd-5	2	24.00	0.10		4.80			
	White Petal School Rd	2	19.00	0.10		3.80			
	Cross Rd-2	2	19.00	0.10		3.80			
	Cross Rd-1	2	65.00	0.10		13.00			
	4th Cross rd	2	149.00	0.10		29.80			
	2nd Cross Rd	2	161.00	0.10		32.20			
	Ramadasappa Garden1st Cross rd	2	166.00	0.10		33.20			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Veerasagara Main Rd								
	3rd Cross Rd	2	148.00	0.10		29.60			
	6th A Cross Rd	2	65.00	0.10		13.00			
	6th Cross Rd	2	57.00	0.10		11.40			
	8th Main Cross Rd-2	2	93.00	0.10		18.60			
	6th B Cross Rd	2	104.00	0.10		20.80			
	4th A Cross Rd	2	22.50	0.10		4.50			
	4th B Cross Rd	2	22.50	0.10		4.50			
	4th C Cross Rd	2	22.50	0.10		4.50			
	5thA Cross Rd	2	130.00	0.10		26.00			
	Chitra Layout [Harshitha Nilaya]	2	94.00	0.10		18.80			
	6th Cross Rd	2	134.00	0.10		26.80			
	9th Main rd	2	99.00	0.10		19.80			
	10th Main rd	2	43.00	0.10		8.60			
	11th Main Rd	2	54.50	0.10		10.90			
	Chitra Layout 3rd Cross Rd	2	64.00	0.10		12.80			
	Muneshwara Layout								
	1st Cross Rd	2	44.00	0.10		8.80			
	2nd Cross Rd	2	170.00	0.10		34.00			
	3rd Cross Rd	2	48.00	0.10		9.60			
	4th Cross Rd	2	102.00	0.10		20.40			
	5th Cross Rd	2	270.00	0.10		54.00			
	7th Cross Rd	2	190.00	0.10		38.00			
	9th Cross Rd Left Side	2	134.00	0.10		26.80			
	9th Cross Rd Right Side	2	99.00	0.10		19.80			
	10th Cross Rd Left Side	2	44.00	0.10		8.80			
	10th Cross Rd Right Side	2	170.00	0.10		34.00			
	11th Cross Rd	2	48.00	0.10		9.60			
	1st Main Rd	2	102.00	0.10		20.40			
	1st Cross Rd	2	270.00	0.10		54.00			
	6th Cross 1st Cross Rd	2	190.00	0.10		38.00			
	6th Cross 2nd Cross Rd	2	65.00	0.10		13.00			
	6th Cross 3rd Cross Rd	2	57.00	0.10		11.40			
	6th Cross 4th Cross Rd	2	93.00	0.10		18.60			
	5th Cross Rd	2	134.00	0.10		26.80			
	4th Cross Rd	2	99.00	0.10		19.80			
		2	43.00	0.10		8.60			
	3rd Cross Rd	2	54.50	0.10		10.90			
	Sri Sai Layout								
	Cross Rd 1-to Cross Rd-2	2	272.50	0.10		54.50			
	Cross Rd-3	2	16.00	0.10		3.20			
						2411.70	**Sqm**	**525.80**	**1268071.86**
19	Dismantling of **cement concrete pavement** by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatel (V-III Page No.10, Item No.2.19 of PWD SR 2021-22)								
	Basic Rate	**422.00**							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Area Weightage 10%	42.20							
	Total Rate	464.20							
	CC Road								
	Muneshwara Layout								
	Connecting Rd	1	96.00	2.90	0.25	69.60			
	Chitra Layout								
	3rd Cross Rd	1	30.00	19.00	0.25	142.50			
	Deduct	1	-1.70	1.80	0.25	-0.77			
		1	-1.50	1.50	0.25	-0.56			
	Beside Apartment	1	24.00	4.10	0.25	24.60			
	3rd Cross[Connecting Rd]	1	43.00	4.80	0.25	51.60			
	Attur Village								
	Aralikatte	1	4.70	5.30	0.25	6.23			
	Aralikatte Left Side	1	5.00	1.10	0.25	1.38			
		1	15.00	8.00	0.25	30.00			
		1	3.40	2.20	0.25	1.87			
		1	8.20	1.60	0.25	3.28			
	Temple Surrounding	1	10.00	3.50	0.25	8.75			
		1	11.00	10.00	0.25	27.50			
		1	25.00	4.00	0.25	25.00			
	Cross Rd-1	1	48.00	5.20	0.25	62.40			
	Cross Rd-2	1	103.00	4.50	0.25	115.88			
						569.25			
	Deduct 30% Voids					170.78			
						398.48	Cum	464.20	184972.10
20	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:5:10 Using 40 mm nominal size graded crushed coarse aggregates(V-I,I No-2.11, P.No-15of KPWD SR 2021-22)								
	Basic Rate	4976.00							
	Area Weightage 10%	497.60							
	Total Rate	5473.60							
	CC Road								
	Attur Layout								
	6th Cross Dead End	1	22.00	3.10	0.15	10.23			
	Muneshwara Layout								
	Connecting Rd	1	96.00	2.90	0.15	41.76			
	Chitra Layout								
	3rd Cross Rd	1	30.00	19.00	0.15	85.50			
	Deduct	1	-1.70	1.80	0.15	-0.46			
		1	-1.50	1.50	0.15	-0.34			
	Beside Apartment	1	24.00	4.10	0.15	14.76			
	3rd Cross[Connecting Rd]	1	43.00	4.80	0.15	30.96			
	Attur Village								
	Aralikatte	1	4.70	5.30	0.15	3.74			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Aralikatte Left Side	1	5.00	1.10	0.15	0.83			
		1	15.00	8.00	0.15	18.00			
		1	3.40	2.20	0.15	1.12			
		1	8.20	1.60	0.15	1.97			
	Temple Surrounding	1	10.00	3.50	0.15	5.25			
		1	11.00	10.00	0.15	16.50			
		1	25.00	4.00	0.15	15.00			
	Cross Rd-1	1	48.00	5.20	0.15	37.44			
	Cross Rd-2	1	103.00	4.50	0.15	69.53			
	Burial Ground Entrance								
		1	210.00	4.00	0.15	126.00			
						477.78	**Cum**	**5473.60**	**2615176.61**
21	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work.(V-III, P.No-138,I No-20.29, KPWD SR 2021-22).								
	Basic Rate	**6837.00**							
	Area Weightage 10%	**683.70**							
	Total Rate	**7520.70**							
	CC Road								
	Attur Layout								
	6th Cross Dead End	1	22.00	3.10	0.15	10.23			
	Muneshwara Layout								
	Connecting Rd	1	96.00	2.90	0.15	41.76			
	Chitra Layout								
	3rd Cross Rd	1	30.00	19.00	0.15	85.50			
	Deduct	1	-1.70	1.80	0.15	-0.46			
		1	-1.50	1.50	0.15	-0.34			
	Beside Apartment	1	24.00	4.10	0.15	14.76			
	3rd Cross[Connecting Rd]	1	43.00	4.80	0.15	30.96			
	Attur Village								
	Aralikatte	1	4.70	5.30	0.15	3.74			
	Aralikatte Left Side	1	5.00	1.10	0.15	0.83			
		1	15.00	8.00	0.15	18.00			
		1	3.40	2.20	0.15	1.12			
		1	8.20	1.60	0.15	1.97			
	Temple Surrounding	1	10.00	3.50	0.15	5.25			
		1	11.00	10.00	0.15	16.50			
		1	25.00	4.00	0.15	15.00			
	Cross Rd-1	1	48.00	5.20	0.15	37.44			
	Cross Rd-2	1	103.00	4.50	0.15	69.53			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Burial Ground Entrance								
		1	210.00	4.00	0.15	126.00			
						477.78	**Cum**	**7520.70**	**3593240.05**
22	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications. (V-I.No 9.31,Page No-64 PWD SR 2021-22)								
	Basic Rate	1087.00							
	Area Weightage 10%	108.70							
	Total Rate	**1195.70**							
	For Cobble Stone								
	Apartment Side								
	S-LIG, 39,40,41,42								
	39 Back Side	1	5.50	3.50		19.25			
	40 Back Side	1	6.00	6.00		36.00			
	41 Behing Neha Prakash Hospital	1	22.00	10.50		231.00			
	42 Front Side	1	33.00	5.80		191.40			
	42 Back Side	1	30.00	15.00		450.00			
	42 Right Side	1	8.00	5.20		41.60			
		1	6.00	1.80		10.80			
	15th Block								
	Part-A	1	31.00	5.00		155.00			
	Part-B	1	9.00	3.50		31.50			
	Part-C	1	31.00	7.50		232.50			
	Part-D	1	9.00	3.50		31.50			
	Part-E	1	6.30	5.30		33.39			
	Part-F	1	9.40	5.30		49.82			
	S-HIG32								
	Part-A	1	9.30	5.00		46.50			
	Part-B	1	6.10	5.40		32.94			
	S-HIG B-09								
		1	29.00	6.00		174.00			
		1	37.40	5.50		205.70			
	Ward No-04								
	For Pathway								
	7thB Cross Rd	1	29.00	6.00		174.00			
	Opp To Annapurnashwerl Catering								
	Part-A	1	33.00	4.60		151.80			
	Part-B	1	10.50	5.30		55.65			
	Part-C	1	22.00	5.00		110.00			
	Part-D	1	10.50	16.20		170.10			
	Part-E	1	60.00	6.50		390.00			
	Part-F	4	8.50	2.50		85.00			
	Part-G	3	8.50	3.00		76.50			
	S-LIG 42								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Beside Neha Prakasha Hospital								
	Part-A	1	27.00	5.00		135.00			
	Part-B	1	30.00	22.00		660.00			
	Part-C	1	27.00	4.50		121.50			
	Part-D	2	8.50	2.50		42.50			
	Part-E	2	8.50	3.00		51.00			
	Part-F	1	20.50	5.80		118.90			
	Part-G	1	15.00	8.00		120.00			
	Part-H	1	5.00	5.00		25.00			
	Part-I	1	8.30	3.00		24.90			
	Part-J	1	37.00	5.00		185.00			
	Part-K	1	20.00	7.60		152.00			
	Part-L	1	37.00	4.80		177.60			
	Part-M	2	8.50	2.50		42.50			
	Part-N	2	8.50	3.00		51.00			
	Deduct Sump	-4	4.00	3.00		-48.00			
						5044.85	Sqm	1195.70	6032127.15
23	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km (V-III Page No.3, Item No.1.4 A of PWD SR 2021-22)								
	Basic Rate	12.00							
	8KM Lead = 12*8	96.00							
	Area Weightage 10%	9.60							
	Total Rate	105.60							
	Qty frm Item No-2		12902.39	1.28		16515.06			
	Qty frm Item No-11		8088.12	1.28		10352.79			
	Qty frm Item No-19		398.48	2.10		836.80			
						27704.65	t.Km	105.60	2925610.60
24	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work Depth exceeding 1.5 m, but not exceeding 3 (V-I Page No.8, Item No.1.15.2 of PWD SR 2021-22)								
	Basic Rate	320.00							
	Area weihgtage 10%	32.00							
	Total	352.00							
	Burial Ground Compound								
	North Side								
	Footing Every 3.50mtr	26	1.50	1.50	1.50	87.75			
	For SSM Foundation	1	53.00	0.90	0.90	42.93			
	For SSM For Gate	1	3.50	0.90	0.80	2.52			
	Valdhika Sabha building								
	Footing	16	2.00	2.00	1.50	96.00			
	SSM Foundation								
		5	19.10	0.75	0.90	64.46			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		4	13.75	0.75	0.90	37.13			
		4	1.55	0.75	0.90	4.19			
	Sump	1	3.20	3.20	1.50	15.36			
						350.33	Cum	352.00	123317.04
25	Providing and laying in position Reinforced cement concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) **M25 Design Mix Using 20 mm nominal size** graded crushed coarse aggregates (V-I Page No.15, Item No.2.2.2.1 of PWD SR 2021-22)								
	Basic Rate	6285.00							
	Shuttering 10%	628.50							
		6913.50							
	Area weihgtage 10%	691.35							
	Total	7604.85							
	Burial Ground Compound								
	North Side								
	Footing Every 3.50mtr	26	1.35	1.35	0.45	21.32			
	Cloumn upto Plinth	26	0.20	0.35	1.50	2.73			
	Plinth beam	1	92.00	0.45	0.20	8.28			
	Vaidhika Sabha building								
	Footing	16	1.85	1.85	0.60	32.86			
	Coloumn Upto Plinth	16	0.20	0.60	1.30	2.50			
	Plinth beam	5	19.10	0.20	0.45	8.60			
		4	15.00	0.20	0.45	5.40			
		4	1.90	0.45	0.15	0.51			
	Sump Bottom Slab	1	2.60	2.60	0.15	1.01			
						83.21	Cum	7604.85	632778.66
26	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately)**M20 Design Mix Using 20 mm nominal size** graded crushed coarse aggregates (V-I Page No.17, Item No.2.5.1 of PWD SR 2021-22)								
	Basic Rate	6471.00							
	Shuttering 10%	647.10							
		7118.10							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Area weihgtage 10%	711.81							
	Total	7829.91							
	Burial Ground Compound								
	North Side								
	Cloumn Above Plinth	26	0.20	0.35	2.40	4.37			
	For SSM For Gate	1	3.50	0.60	0.10	0.21			
	Vaidhika Sabha building								
	Coloumn Above Plinth	16	0.20	0.60	2.45	4.70			
	Coloumn Above Slab	16	0.20	0.60	0.75	1.44			
	Roof Beam	5	19.10	0.20	0.30	5.73			
		4	15.00	0.20	0.30	3.60			
	Slab	1	19.10	16.00	0.15	45.84			
	Sump Top Slab	1	3.00	3.00	0.15	1.35			
	Lintel								
	MD	1	2.10	0.20	0.15	0.06			
	D1	1	3.50	0.20	0.20	0.14			
	D2	6	1.50	0.20	0.15	0.27			
	D3	6	1.05	0.20	0.15	0.19			
	W	10	1.80	0.20	0.15	0.54			
	W2	6	1.05	0.20	0.15	0.19			
	Chajja								
	W	10	1.80	0.75	0.10	1.35			
	W2	6	1.05	0.75	0.10	0.47			
						70.46	Cum	7829.91	551660.22
27	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6(1 cement : 6 coarse sand) (V-II Page No.9, Item No.5.4 of PWD SR 2021-22)								
	Basic Rate	5422.00							
	Area weihgtage 10%	542.20							
	Total	5964.20							
	Burial Ground Compound								
	North Side								
	For SSM Foundation	1	86.80	0.75	0.45	29.30			
		1	86.80	0.45	0.45	17.58			
	For SSM For Gate	1	3.50	0.60	0.60	1.26			
	Vaidhika Sabha building								
	SSM Foundation	5	19.10	0.60	0.45	25.79			
		4	14.20	0.60	0.45	15.34			
		4	1.70	0.60	0.45	1.84			
		5	19.10	0.45	0.45	19.34			
		4	14.20	0.45	0.45	11.50			
		4	1.70	0.45	0.45	1.38			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
						123.31	Cum	5964.20	735426.12
28	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.(V-I Page No.7, Item No.1.9 of PWD SR 2021-22)								
	Basic Rate	204.00							
	Area weihgtage 10%	20.40							
	Total	224.40							
	Qty from Item No-1					350.33			
	Building Inside Area	1	18.60	15.60	0.45	130.57			
						480.90	Cum	224.40	107914.97
29	Providing Thermo-Mechanically Treated bars of grade Fe-500D or more Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, binding and anchoring to adjacent members whereever necessary complete as per Design including cost of material, labour, usage charges complete as per specifications. (The laps and wastages shall not be measured separately) (V-II Page No.11.32, Item No.84 of PWD SR 2021-22) Issue Rate								
	Basic Rate	106.00							
	Area weihgtage 10%	10.60							
	Total	116.60							
	Burial Ground Compound	Kgs							
	North Side								
	For Footing	1	21.32		100.00	2132.33			
	For Coloumn	1	7.10		100.00	709.80			
	Plinth	1	8.28		80.00	662.40			
	Vaidhika Sabha building								
	Footing	1	32.86		120.00	3942.72			
	Column	1	8.64		120.00	1036.80			
	Plinth Beam	1	14.51		100.00	1450.80			
	Roof Beams and Slab	1	56.52		120.00	6782.40			
	Chajja and Lintel	1	3.21		80.00	257.08			
						16974.33	Kgs	116.60	1979206.30
30	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. (V-II Page No.17, Item No.6.32 of PWD SR 2021-22)								
	Basic Rate	1202.00							
	Area weihgtage 10%	120.20							
	Total	1322.20							
	Burial Ground Compound								
	North Side								
	For Wall	1	86.80		2.40	208.32			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Vaidhika Sabha building								
		1	15.40		2.60	40.04			
		4	19.10		2.60	198.64			
		3	15.00		2.60	117.00			
		1	13.50		2.60	35.10			
	Sump	2	3.00		1.60	9.60			
		2	2.60		1.60	8.32			
	Lintel								
	MD	-1	1.80		2.10	-3.78			
	D1	-1	3.05		2.10	-6.41			
	D2	-6	1.20		2.10	-15.12			
	D3	-6	0.75		2.10	-9.45			
	W	-10	1.50		1.50	-22.50			
	W2	-6	0.75		0.60	-2.70			
						557.07	Sqm	1322.20	736551.34
31	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x100x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.(V-II Page No.17, Item No 6.34 of PWD SR 2021-22)								
	Basic Rate	946.00							
	Area weihgtage 10%	94.60							
	Total	1040.60							
	Vaidhika Sabha building	Sqm							
	For Partition wall	4	2.30		3.00	27.60			
	D3	-2	0.75		2.10	-3.15			
						24.45	Sqm	1040.60	25442.67
32	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m2 to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.(V-II Page No.133, Item No.15.1 of PWD SR 2021-22)								
	Basic Rate	745.00							
	Area weihgtage 10%	74.50							
	Total	819.50							
	Vaidhika Sabha building								
	Terrace	1	18.70	15.60		291.72			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		-1	3.42	2.30		-7.87			
						283.85	Sqm	819.50	232618.35
33	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications.(V-II Page No.99, Item No.12.11 of PWD SR 2021-22)								
	Basic Rate	90393.00							
	Area weihgtage 10%	9039.30							
	Total	99432.30							
	Vaidhika Sabha building	Sqm							
	MD	1	7.20	0.15	0.13	0.90			
	D2	6	6.60	0.13	0.10	3.96			
						4.86	Sqm	99432.30	483240.98
34	Fixing of door frame in an existing opening including embedding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debris with lead upto 50 m. including cost of materials, labour charges, complete as per specifications.(V-II Page No.105, Item No.12.51 of PWD SR 2021-22).								
	Basic Rate	1485.00							
	Area weihgtage 10%	148.50							
	Total	1633.50							
	Vaidhika Sabha building								
	MD	1				1.00			
	D2	6				6.00			
						7.00	Nos	1633.50	11434.50
35	Providing and fixing flush door shutter made out of solid core block board type, well seasoned , chemicaly treated hard wood battens and internal frame with minimum 45 mm wide wooden frame alround door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door useing liquid phenol formaldehyde resin as per IS specifications 2202 (part-I) 1991. from manufacturer complete as per spcification. 30 mm thick both side commercial (V-II Page No.105, Item No.12.51 of PWD SR 2021-22). Clm 12.57.3 P-106								
	Basic Rate	2638.00							
	Area weihgtage 10%	263.80							
	Total	2901.80							
	Vaidhika Sabha building	Sqm							
	MD	1	7.20		2.10	15.12			
	D2	6	6.60		2.10	83.16			
						98.28	Sqm	2901.80	285188.90

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
36	Providing & fixing of 2-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6 PHR with TPE (Thermo Plastic Elastomer) and lead free, gaskets -grey color having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 44mm width x 40mmheight with reinforcement of 1mm thickness and Sash with overall size of 27mm X 53mm with UPVC honeycomb structure inside in lieu of GI reinforcement. Coextruded Glazing bead for fixing of glass shall be of size 9.5mm x 21.5mm. Windows shall be provided with 5mm plain float glass, standard hardware& single point locking system with Crescent Locks. Wall thickness of frame & sash shall be of 2 mm.Maximum possible size – 1219mm x 1219mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made) (V-II, Page No.110, Item No.12.84 of PWD SR 2021-22)								
	Basic Rate	4114.00							
	Area weihgtage 10%	411.40							
	Total	4525.40							
	Vaidhika Sabha building								
	W	10	1.50		1.50	22.50			
	W2	6	0.75		0.60	2.70			
						25.20	Sqm	4525.40	114040.08
37	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding (V-II, Page No.85, Item No.11.34A of PWD SR 2021-22)								
	Basic Rate	131.00							
	Area weihgtage 10%	13.10							
	Total	144.10							
	Vaidhika Sabha building								
	W	10	1.50		1.50	22.50			
	W2	6	0.75		0.60	2.70			
						25.20			
	Total Qty in kgs (qty in Sqm					529.20			
						529.20	Sqm	144.10	76257.72
38	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x6 mm for diagonal braces including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.(V-II, Page No.75, Item No.11.5.1 of PWD SR 2021-22)								
	Basic Rate	3660.00							
	Area weihgtage 10%	366.00							
	Total	4026.00							
	Vaidhika Sabha building	Sqm							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	D3	6	0.75		2.10	9.45			
						9.45	Sqm	4026.00	38045.70
39	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement: 4 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.41, Item No.8.2.1 of PWD SR 2021-22)								
	Basic Rate	253.00							
	Area weihgtage 10%	25.30							
	Total	278.30							
	Vaidhika Sabha building								
	Ceiling Plastering	1	18.70	15.60		291.72			
		-1	3.42	2.30		-7.87			
	Inside Plastering	1	15.00		2.60	39.00			
		6	18.70		2.60	291.72			
		1	15.60		2.60	40.56			
		1	13.10		2.60	34.06			
		4	5.90		2.60	61.36			
		2	4.30		2.60	22.36			
	Toilets	6	7.6		1.40	63.84			
	Sump	2	2.60		1.60	8.32			
		2	2.60		1.60	8.32			
	Deductions								
	MD	-1	1.80		2.10	-3.78			
	D1	-1	3.50		2.10	-7.35			
	D2	-12	1.50		2.10	-37.8			
	D3	-12	1.05		0.60	-7.56			
	W	-10	1.50		1.50	-22.5			
	W2	-6	0.75		0.60	-2.7			
						771.70	Sqm	278.30	214764.11
40	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonary including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.41, Item No.~~8.3.1~~ 8.2.1 of PWD SR 2021-22)								
	Basic Rate	253.00							
	Area weihgtage 10%	25.30							
	Total	278.30							
	Burial Ground Compound	Sqm							
	North Side								

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Compound Wall	2	92.00		2.50	460.00			
		2	0.15		2.50	0.75			
	Vaidhika Sabha building								
	External Plastering	2	19.10		4.75	181.45			
		2	16.00		4.75	152.00			
	Deductions								
	MD	-1	1.80		2.10	-3.78			
	W	-10	1.50		1.50	-22.50			
	W2	-6	0.75		0.60	-2.70			
						765.22	Sqm	337.70	258414.79
41	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed including cost of materials, mortar, labour, curing complete as per specifications.(V-II, Page No.64, Item No.9.30 of PWD SR 2021-22)								
	Basic Rate	2401.00							
	Area weihgtage 10%	240.10							
	Total	2641.10							
	Vaidhika Sabha building								
		3	6.10	5.90		107.97			
		2	2.30	2.44		11.22			
		2	1.80	4.00		14.40			
	Passage	1	18.90	5.00		94.50			
						228.09	Sqm	2641.10	602419.06
42	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including pointing the joints with white cement and matching pigments etc., complete (V-II, Page No.60, Item No.9.11 of PWD SR 2021-22)								
	Basic Rate	773.00							
	Area weihgtage 10%	77.30							
	Total	850.30							
		Sqm							
	Vaidhika Sabha building	1	6.90	1.74		12.01			
		1	3.2	1.74		5.57			
		6	1.5	2.30		20.70			
						38.27	Sqm	850.30	32544.38

CORRECTED

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
43	Providing skirting, dadooing, rises of steps with white glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.(V-II, Page No.65, Item No.9.38 of PWD SR 2021-22)								
	Basic Rate	1963.00							
	Area weihgtage 10%	196.30							
	Total	2159.30							
	Vaidhika Sabha building								
	Toilets	6	7.60		1.50	68.4			
	Deductions								
	D3	-6	0.75		1.50	-6.75			
						61.65	Sqm	2159.30	133120.85
44	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two coats on new work after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (V-II, P-48, Item-8.39								
	Basic Rate	95.00							
	Area weihgtage 10%	9.50							
	Total	104.50							
	Qty Same as Inside Plaster					771.70			
	Deduct Sump Plastering					16.64			
						755.06	Sqm	104.50	78903.77
45	Providing White washing with lime to give an even shade :New work (three coats) with lime of approved quality, including cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (V-II, Page No.44, Item No.8.21 of PWD SR 2021-22)								
	Basic Rate	19.00							
	Area weihgtage 10%	1.90							
	Total	20.90							
	Qty Same as External Plaster					765.22			
						765.22	Sqm	20.90	15993.10
46	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67 ltr/10 m² over and including priming coat of exterior primer applied @ 2.20 kg/10 m²) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.46, Item No.8.30 of PWD SR 2021-22)								
	Basic Rate	136.00							
	Area weihgtage 10%	13.60							
	Total	149.60							
	Qty Same as External Plaster					765.22			
						765.22	Sqm	149.60	114476.91

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
47	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.(V-II, Page No.48, Item No.8.41 of PWD SR 2021-22)								
	Basic Rate	130.00							
	Area weihgtage 10%	13.00							
	Total	143.00							
	W	10	1.50		1.50	22.50			
	W2	6	0.75		0.60	2.70			
						25.20	Sqm	143.00	3603.60
48	Providing and fixing chromium plated brass handles of 100/125 mm with necessary screws etc. Complete(V-II Page No.107, Item No.12.62 of PWD SR 2021								
	Basic Rate	175.00							
	Area weihgtage 10%	17.50							
	Total	192.50							
	Vaidhika Sabha building	14				14.00			
						0.00			
						14.00	Nos	192.50	2695.00
49	Providing and fixing ISI marked M.S. pressed butt hinges bright finished with necessary screws etc.125x65x2.12mm(V-II Page No.107, Item No.12.68.1 of PWD								
	Basic Rate	38.00							
	Area weihgtage 10%	3.80							
	Total	41.80							
	Vaidhika Sabha building	24				24.00			
						24.00	Nos	41.80	1003.20
50	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. Complete 250x10mm (V-II Page No.109, Item No.12.76 of								
	Basic Rate	337.00							
	Area weihgtage 10%	33.70							
	Total	370.70							
	Vaidhika Sabha building	8				8.00			
						8.00	Nos	370.70	2965.60
51	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid (V-II Page							14.3.1 P- 123	
	Basic Rate	5005.00							
	Area weihgtage 10%	500.50							
	Total	5505.50							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Vaidhika Sabha building	6				6.00			
						6.00	Nos	5505.50	33033.00
52	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required : Size 600x450x200 mm (V-II Page No 126, Item No 14.11.2 of PWD SR 2021-22) 14.11.2								
	Basic Rate	4644.00							
	Area weihgtage 10%	464.40							
	Total	5108.40							
	Vaidhika Sabha building	4				4.00			
						4.00	Nos	5108.40	20433.60
53	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required : Single half stall urinal with 5 litre P.V.C. automatic flushing cistern (V-II Page No.124, Item No 14.5.1 of PWD SR 2021-22)								
	Basic Rate	6628.00							
	Area weihgtage 10%	662.80							
	Total	7290.80							
	Vaidhika Sabha building	2				2.00			
						2.00	Nos	7290.80	14581.60
54	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 20mm nominal dia pipes (V-II Page No 124, Item No 13.22.2 of PWD SR 2021-22)								
	Basic Rate	373.00							
	Area weihgtage 10%	37.30							
	Total	410.30							
	Vaidhika Sabha building	m	45.00			45.00			
						45.00	m	410.30	18463.50
55	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 25mm nominal dia pipes (V-II Page No 124, Item No 13.22.3 of PWD SR 2021-22)								
	Basic Rate	476.00							
	Area weihgtage 10%	47.60							
	Total	523.60							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Vaidhika Sabha building		60.00			60.00			
						60.00	m	523.60	31416.00
56	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge. Concealed work, including cutting chases and making good the walls etc. 32mm nominal dia pipes (V-II Page No.124, Item No.13.22.4 of PWD SR 2021-22)								
	Basic Rate	556.00	Addendum - 1, I - 13.30 %						
	Area weihgtage 10%	55.60							
	Total	611.60							
	Vaidhika Sabha building		30.00			30.00			
						30.00	m	611.60	18348.00
57	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. for PVC pipes 110mm dia , 6 kg/sqcm & class 3(Page No.134, Item No.1.7 of BWSSB SR 2021-22) Item 1.7								
	Vaidhika Sabha building Toilet Area	1	45.00			45.00			
						45.00	M	394.00	17730.00
58	Providing and fixing gun metal non- return valve of approved quality (screwed end)(V-II Page No.115, Item No.13.6.1.2 of PWD SR 2021-22) Basic Rate - 553								
	Vaidhika Sabha building	6				6.00			
			Add on Weightage 10%			6.00	Nos	608.30	3649.80
59	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete(V-II Page No.115, Item No.13.5.2 of PWD SR 2021-22)								
	Vaidhika Sabha building	4				4.00			
			Basic Rate 360.00			4.00	Each	396.00	1584.00
60	Providing and fixing PTMT pillar cock of approved quality and colour15 mm nominal bore, 125 mm long foam flow, weighing not less than 120 gms(V-II Page No.118, Item No.13.20.2 of PWD SR 2021-22)								
	Vaidhika Sabha building	6				6.00			
			Basic Rate 220.00			6.00	Each	242.00	1452.00
61	Bottle trap 38 mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 263 gms (V-II Page No.129, Item No.14.37.2 of PWD SR 2021-22)								
	Vaidhika Sabha building	6				6.00			
			Basic Rate 244.00			6.00	Each	268.40	1610.40

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
62	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 19/20mm dia 2mm thick conforming to IS 2509 with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipes ends should be covred using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.19/20mm dia 2mm thick (Page No.1, Item No.1.2.1 of PWD Electrical SR2022-23)								
	Vaidhika Sabha building	1	100.00			100.00			
						100.00	m	61.00	6100.00
63	Providing and fixing Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including cost of materials, labour, usage charges ofmachinery complete as per specifications and as per directions of the Engineer-in-Charge. (V-2 Page No.82, Item No.11.25.2 of PWD SR 2021-22) Issue Rate On 07-04-22								
	Basic Rate	133.00							
	Area weihgtage 10%	13.30							
	Total	146.30							
	For Gate	1	3.50		2.40	8.40			
	Consider 55kg/Sqm					462.00			
						462.00	Kg	146.30	67590.60
64	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 25mm dia 2mm thick conforming to IS 2509 with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipes ends should be covred using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.a)25mm dia 2 mm thick (Page No.1, Item No.1.2.2 of PWD Electrical SR 2021-22								
	Hall	1	100.00			100.00			
						100.00	m	70.00	7000.00
65	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 19/20mm dia 2mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.19/20mm dia 2mm thick(Page No.1, Item No.1.3.1 of PWD Electrical SR 2021-22)								
	Hall	1	100.00			100.00			
						100.00	m	75.00	7500.00
66	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 25mm dia 2.mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.a)25mm dia 2 mm thick (Page No.1, Item No.1.3.2 of PWD Electrical SR 2021-22)								
	Hall	1	100.00			100.00			
						100.00	m	80.00	8000.00

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
67	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 32mm dia 2.5mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.32mm dia 2.5 mm thick (Page No.1, Item No.1.3.3 of PWD Electrical SR 2021-22)								
	Hall	2	5.00			10.00			
						10.00	m	105.00	1050.00
68	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper conductor single core cable in open or concealed system of wiring with specified IS-694:1990 & conforming to GTP of Group-A (Page No.3, Item No.2.3 of [illegible])								
	1.0 Sqm	2	100.00			200.00	m	18.00	3600.00
69	1.5 Sqm	2	45.00			90.00	m	26.00	2340.00
70	2.5 Sqm	2	85.00			170.00	m	40.00	6800.00
71	4.0 Sqm	2	45.00			90.00	m	59.00	5310.00
72	10.0 Sqm	2	20.00			40.00	m	157.00	6280.00
73	Point wiring using Copper wire without switch.Supplying and wiring adopting loop system in existing PVC Conduit/casing capping using 1100V Grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2x1.5 Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose lenght in a wood/PVC round block. complete for each outlet.(5/2.3) Using class A materials (Page No.3, Item No.2.2 of PWD Electrical SR 2021-22)								
	Short point up to 3mtrs from tapping point to out let via switch (Page No.3, Item No.2.2.1 of PWD Electrical	2	18.00			36.00	Point	251.00	9036.00
74	Medium point a above 3mtr up to 6mtr from tapping point to out let via switch (Page No.3, Item No.2.2.2 of PWD Electrical SR 2021-22)	2	18.00			36.00	Point	361.00	12996.00
75	Long point a above 6mtr up to 10mtr from tapping point to out let via switch (Page No.3, Item No.2.2.3 of PWD Electrical SR 2021-22)	2	12.00			24.00	Point	542.00	13008.00
76	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve , indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required conforming to IEC60898.5-32Amps DP (Page No.13, Item No.5.17 of PWD Electrical SR 2021-22)								
	6-32Amps SP	15				15.00	Each	523.00	7845.00
77	6-32 Amps DP	15				15.00	Each	1103.00	16545.00
78	40 Amps TPN	8				8.00	Each	2393.00	19144.00
79	50-63 Amps SP	8				8.00	Each	734.00	5872.00

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
80	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure,III-Single Door.Group A12Way SP &N (Page No 13, Item No.5.18.4 of PWD Electrical SR 2021-22)								
	Hall	10				10.00			
						10.00	Each	1591.00	15910.00
81	Supplying and fixing regular MCB distribution boards on wall/wood board/flush mounting using required clamps, bolts, nuts etc. with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with power coated painting etc., complete: Double door: 6 way TP &N , Group (A) (Page No.13, Item No.5.18.12 of PWD Electrical SR 2021-22)								
	Hall	5				5.00			
						5.00	Each	3735.00	18675.00
82	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply & completely wired on existing box. (Page No.6, Item No.3.7 of PWD Electrical SR 2021-22)								
	Hall	5				5.00			
						5.00	Each	747.00	3735.00
83	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall 1-3 Way (Page No.5, Item No.3.4.1 of PWD Electrical SR 2021-22)								
	Hall	25				25.00			
						25.00	Each	123.00	3075.00
84	Supplying and fixing of 20/40 Watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes : Supplying and fixing of 20/40 Watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes, Class H Insulated copper wire, Vacuum impregnated high quality with Low loss silicon steel lamination operated on 240V,50Hz supply with IEC 60920 (Safety) & IEC 60921(Performance). Operating voltage range from 180V to 265V, 50Hz AC power Supply. (Page No.41, Item No.12.23 of PWD Electrical SR 2021-22)								
	Hall	20				20.00			
						20.00	Each	300.00	6000.00
85	Supply and fixing metal fan box with round hook (Page No.2, Item No.1.12 of PWD Electrical SR 2021-22)								
	Hall	12				12.00			
						12.00	Nos	163.00	1956.00
86	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293.(Page No.5, Item No.3.6 of PWD Electrical SR 2021-22)								
	6Amps SP Switch	50				50.00	Each	88.00	4400.00
87	6Amps 3way 5 pin socket	20				20.00	Each	162.00	3240.00
88	16Amps SP Switch	10				10.00	Each	249.00	2490.00
89	32Amps Flush/projected	10				10.00	Each	375.00	3750.00

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
90	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall (Page No.5, Item No.3.4 of PWD Electrical SR 2021-22)								
	1-3Way	20				20.00	Each	123.00	2460.00
91	4-5Way	20				20.00	Each	138.00	2760.00
92	6Way	20				20.00	Each	212.00	4240.00
93	8Way	24				24.00	Each	250.00	6000.00
94	10-12Way	16				16.00	Each	325.00	5200.00
95	16Way	4				4.00	Each	354.00	1416.00
96	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. (Page No.5, Item No.3.5 of PWD Electrical SR 2021-22)								
	1 to 3 Module	20				20.00	Each	152.00	3040.00
97	4Moudule	20				20.00	Each	175.00	3500.00
98	6Moudule	20				20.00	Each	244.00	4880.00
99	8Moudule	24				24.00	Each	302.00	7248.00
100	10Moudule	16				16.00	Each	363.00	5808.00
101	12Moudule	4				4.00	Each	403.00	1612.00
102	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies for operation on 230 Volts, 50 Cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system.(84/9.3)56" Sweep (1400mm) Regular model (Page No.22, Item No.6.3.2 of PWD Electrical SR 2021-22)								
	Hall	10				10.00			
						10.00	Each	2170.00	21700.00
103	Supplying and fixing of Electronic Ballast suitable for T8 Lamp with housing made of Pre-coated steel/PC, Operating voltage range from 180V to 265V, 50Hz AC power Supply flicker free warm start with over voltage protection, Inrush current protection, De-activated lamp protection & End of Lamp life protection with PF> 0.95 & TC(deg C) > 65 degC. Operating voltage range from 180V to 265V, 50Hz AC power Supply (Page No.40, Item No.12.22.3 of PWD Electrical SR 2021-22)								
	Hall	10				10.00			
						10.00	Each	725.00	7250.00
104	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps. 14.7.1 On wall / ceiling / Rafter / Girders (Page No.45, Item No.13.7.1 of PWD Electrical SR 2021-22)								
	Hall	30				30.00			
						30.00	Each	119.00	3570.00

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
105	**Geophysical investigation** at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner orSchlumbergers's method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1) Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2) A sum of Rs. 100/- is to be deducted for Dry Borewell towards yield test. (P.151, I.No-4 Code No-O040A) BWSSB.SR 2021-22								
	Basic Rate	5141.00							
	Area Weightage 10%	514.10							
	Total	5655.10							
		1				1.00	Nos	5655.10	5655.10
106	**Sinking of Borewell of 165mm dia** clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete)(P.151, I.No-1) BWSSB.SR 2021-22								
	Basic Rate	290.00							
	Area Weightage 10%	29.00							
	Total	319.00							
	0 to 50 m (Code No-O010A)	1	50.00			50.00	m	319.00	15950.00
107	Basic Rate	364.00							
	Area Weightage 10%	36.40							
	Total	400.40							
	50 to 100 m (Code No-	1	50.00			50.00	m	400.40	20020.00
108	Basic Rate	387.00							
	Area Weightage 10%	38.70							
	Total	425.70							
	100 to 150 m (Code No-	1	50.00			50.00	m	425.70	21285.00
109	Basic Rate	449.00							
	Area Weightage 10%	44.90							
	Total	493.90							
	150 to 200 m (Code No-	1	50.00			50.00	m	493.90	24695.00
110	Basic Rate	527.00							
	Area Weightage 10%	52.70							
	Total	579.70							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	200 to 250 m (Code No-	1	50.00			50.00	m	579.70	28985.00
111	Basic Rate	558.00							
	Area Weightage 10%	55.80							
	Total	613.80							
	250 to 300 m (Code No-	1	50.00			50.00	m	613.80	30690.00
112	Basic Rate	620.00							
	Area Weightage 10%	62.00							
	Total	682.00							
	300 to 350 m (Code No-	1	50.00			50.00	m	682.00	34100.00
113	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m.prices include Collar-Medium duty (P.154, I.No 32, O160A) BWSSB.SR 2021-22								
	Basic Rate	1933.00							
	Area Weightage 10%	193.30							
	Total	2126.30							
		1	60.00			60.00			
						60.00	Rmtr	2126.30	127578.00
114	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark (one end fitted with Heavy Duty collar and other end fitted with protective cover) 50 mm (P. No 162, I. No. 33.1 BWSSB SR 2021-22) P 710 A								
	Basic rate	3050.00							
	Area Weightage 10%	305.00							
	Total	3355.00							
		24				24.00			
						24.00	Each	3355.00	80520.00
115	PVC pipe - OD 250mm and 6 Kg/sqcm P.No-34, Sl.No.1175,BWSSB.SR 2021-22								
	Basic rate	1100.00							
	Area Weightage 10%	110.00							
	Total	1210.00							
		1	6.00			6.00			
						6.00	Rmtr	1210.00	7260.00
116	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper withflexible copper with low resistance conductor confirming to13:8130-1984 and virgin grade PVC insulation and powdercoating extruded PVC sheathed suitable for working voltageupto 1100 V as per IS-694:2010. 3C x 6 mm2 P. No. 4/ I No. 2.6.4 KPWD Electrical SR 2021-22								
		242.00							
		1	620.00			620.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
						620.00	Mtr	242.00	150040.00
117	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000;3Phase, SS Bowl & Impeller with Low volt Motor as per specifications,as per necessary ammendments and instructions of engineer incharge of work. 15.00 HP - 120 LPM @ 266 m = 23 STG Outlet Dia - 2.00"(P. No.161, I. No. 18.6, BWSSB SR 2021-22)								
	Basic rate	69258.00							
	Area Weightage 10%	6925.80							
	Total	76183.80							
		1				1.00			
						1.00	Nos	76183.80	76183.80
118	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia. (P. No.164, I. No. 45, BWSSB SR 2021-22)								
	Basic rate	3750.00							
	Area Weightage 10%	375.00							
	Total	4125.00							
		1				1.00			
						1.00	job	4125.00	4125.00
119	Supply and fixing polished wood board made of not lessthan 15mm thick plank on both sides of not more than 2pieces and fixing the same to the wall using tapered invertedwooden plugs screws. 20" x 20" x 2.5" (P No. 10 No.5.6.6,Part-I Electrical SR 2021-22)								
		315.00							
		1				1.00			
						1.00	Each	315.00	315.00
120	Supplying & fixing of Porcelain fuse channel with cut out onexisting wooden/panel using necessary nuts, bolts andwashers. 63 A (P No. 10 No.5.6.6,Part-I Electrical SR 2021-22) 5.7.3								
		372.00							
		1				1.00			
						1.00	Each	372.00	372.00
121	Supplying & fixing miniature circuit breakers on existingMCB distribution boards using necessary fixing materialsand 'C' Type curve, indicator ON/OFF, energy cross-3 withShort circuit breaking capacity of 10K and complete wiring asrequired confirming to IEC 60898. 50-63 A TPN (P No. 13 I.No.5.17.9,Part-I Electrical SR 2021-22)								
		2399.00							
		1				1.00			
						1.00	Each	2399.00	2399.00

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
122	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum.(V-I.No 1.4,Page No-5 PWD SR 2021-22)								
	Basic Rate	186.00							
	Area Weightage 10%	18.60							
	Total Rate	204.60							
	Pipeline	1	400.00	0.75	0.60	180.00			
						180.00	Cum	204.60	36828.00
123	Supplying and filling in plinth with sand under floors, foundation of Bridges including watering, ramming, consolidating and dressing complete. (P.No-7,I No-1.11,V-I of PWD SR 2021-22)								
	Basic rate	2177.00							
	Area Weightage 10%	217.7							
	Total	2394.70							
		1	400.00	0.30	0.30	36.00			
						36.00	Cum	2394.70	86209.20
124	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc.63mm outer dia, 6kg/sqcm & class 3 for.(P. No.134 I No 1.4 BWSSB SR 2021-22)								
	Basic rate	153.00							
	Area Weightage 10%	15.3							
	Total	168.30							
		1	400.00			400.00			
						400.00	Mtr	168.30	67320.00
125	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications P. No. 7, I No. 1.10,V-I PWD SR 2021-22								
	Basic rate	122.00							
	Area Weightage 10%	12.2							
	Total	134.20							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
		1	400.00	0.75	0.40	120.00			
						120.00	Cum	134.20	16104.00
126	Supplying fully automatic star-delta starter unit push buttontype with suitable wires, 3 contactors, one adjustablethermal timer mounted on a common base plate held in steel enclosure for use on 400/440 V 3 phase and wired after fixingto the existing wooden board for motor. Above 12.5 HP upto 25 HP (P No. 10 I.No.5.2.2,Part-I Electrical SR 2021-22)								
		8640.00							
		1				1.00			
						1.00	Nos	8640.00	8640.00
								Total Construction Cost	186498920.44
								Sub Total-1	186498920.44
								12% GST for Construction Cost	22379870.45
								BESCOM Deposite Charges	14,000.00
								Towards DPR & PMC Cost including GST	4600000.00
								Sub Total -2	213492790.89
								Utility Shifting,Miscellaneous and Rounding off	7,209.11
								GRAND TOTAL	213500000.00

Certificate

1. The workspot was inspected and works is found to be necessary
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle for year 2021-2022, Data rates and issue rates dated 07-04-2022

Assistant Engineer
Ward No-3 & 4
BBMP Bangalore

Asst. Executive Engineer,
Yelahanka Satellite Town Sub Division
BBMP Bangalore

Executive Engineer,
Yelahanka Division
BBMP Bangalore

APPROVED RATA COPY TO BE ENCLOSED

Administrative Sanction for Rs. 2135.00 Lakhs
Rupees Twenty One Crores
Thirty five lakhs Only
is accorded under head P-3877
Amruth Nagarothana Grants
Registered as CE No. 25 Subject
to conditions contained in enclosed memo
No. BBMP/EE(YNK-D)AS/25/22-23 Dt. 12/8/22

Executive Engineer

Technical Sanction
Accorded For 2135.00 Lakhs
Head of A/C P-3877
CER NO : 23 Dt: 21/6/22

TA

CE